

PRICE LIST 2024



EFFECTIVE MARCH 1<sup>ST</sup>, 2024

#### **OPUS 6434 TMU**

NEW FINESTONE SOLID SURFACE BATH WITH AIR JET SYSTEM 64" x 34" x 25" (freestanding)

BainUltra Opus reaches new heights by offering all the therapeutic benefits of Hydro-thermo massage® with the innovation of air jets in our FineStone solid surface bathtub.

Opus FineStone® Solid Surface comes in 2 categories:

- TMU: Thermomasseur® air jet system and heated backrest
- TUB (Soaker)

#### A symphony of lines and curves

All details, lines, and curves drawn by our designers and craftspeople are like strokes of a pen, or notes in a symphony blending harmoniously together in the final masterpiece.

See page 46.





#### **LAUNCH MARCH 1<sup>ST</sup>, 2024**

#### **LIBRA STELLA 7038**

70" x 38" x 25" (freestanding)

Stella, a name with Latin roots, gracefully translates to "star", one that shines brightly and beautifully - adding a celestial touch to its timeless charm.

While the Libra constellation reminds us of universal balance, the Stella bath integrates gently into this collection, with its curved lines, identical sides and unique character which stands out like a shining star. Magnificent and imposing with its dimensions of 70" x 38" x 25", and with perfectly symmetrical backrests, Stella will bring relaxation and comfort for 2 bathers while enjoying their thermomasseur bath.

This rising star also offers as options, Illuzio chromatherapy as well as the brand new Aromaflow essential oil diffuser that is perfectly integrated into the bath's overflow. Indulge in the divine allure of Libra Stella, turning your bath into a sanctuary of earthly bliss.

See page 98.

# WHAT'S NEW FOR 2024


#### **AROMAFLOW**

DISCOVER THE NEXT EVOLUTION OF AROMATHERAPY IN THE BATH WITH AROMAFLOW.

The AromaFlow is an essential oil diffuser that combines the benefits of aromatherapy while being elegantly included into the bathtub's integrated overflow.

Easy-to-use seamless design, the AromaFlow offers a beautiful and therapeutic way to enjoy essential oils with your BainUltra bathtub\*. One to two drops of essential oil are enough for a 30-45 minutes session.

\*Offered as an option in all collections except BeOne, Balneo, Celestia, and Opus.



#### **SIGNATURE PRODUCT**

A BAINULTRA SIGNATURE BATH IS A PRODUCT DESERVING SPECIAL PROMOTION AND CONSIDERATION FOR SALES.

Here's why: Signature baths are a special class of products offering that bring forward elements that are exclusive to BainUltra's brand. They include designs not seen anywhere else.

These baths set themselves apart, not only in our product offering but also in the market place in general.

This is advantageous to everyone that sells BainUltra because it gives an opportunity to give your customer a product they cannot find elsewhere and allows you to upsell within the BainUltra product offering.

- · Distinctive product design
- Distinctive product offering
- Premium marketing positioning
- Best-selling products
- · Higher profit margin

To learn more on BainUltra Signature products, contact your local sales agent or BainUltra.

To quickly recognize a Signature bath, each product page will have this logo:



#### SIGNATURE BATHS COLLECTIONS ARE:

• BeOne

- Esthesia

Celestia

- Evanescence
- OpaliaOpus

CharismEssencia

- LibraMonarch
- Scala

#### **REMINDER**

#### NEW AND DISCONTINUED PRODUCTS IN 2024

#### **NEW PRODUCTS**

- OPUS TMU, New FineStone bathtub with air jets
- Libra Stella 7038 freestanding (TMU & TUB)

#### DISCONTINUED PRODUCTS

- Ellipse 6036
- Essencia Design 7438 (Drop-in)
- Nokori 5827
- Vibe Tulipa







	INDEX
OVERVIEW	2 - 3
COMMERCIAL TERMS & CONDITIONS	4
THE BAINULTRA® LIMITED WARRANTY	4 - 5
GENERAL INFORMATION	6-8
ACCESSORIES	9-13
PRICE LIST SUMMARY	14 - 40
Baths by collection	14 - 40 14 - 24
Baths by size	25 - 36
Accessories	23 - 30 37 - 40
FINESTONE® BATHS – SOLID SURFACE	41
CELESTIA™	42 - 45
OPUS NEW THERMOMASSEUR BATH	46 - 47
FREESTANDING THERAPEUTIC BATHS	49 - 51
AMMA®	52 - 55
BALNEO®	56 - 67
BEONE™	68 - 69
CHARISM®	70 - 75
ESSENCIA®	76 - 81
ESTHESIA®	82 - 83
EVANESCENCE®	84 - 91
LIBRA NEW BATH	92 - 97
NOKORI® OPALIA®	100 - 109 110 - 119
SCALA™	120 - 123
VIBE®	124 - 131
DROP-IN AND ALCOVE THERAPEUTIC BATHS	133 - 135
AMMA®	136 - 151
BAIN DE VILLE™	152 - 155
CITTI®	156 - 165
ELEGANCIA®	166 - 173
ESSENCIA®	174 - 175
ESTHESIA®	176 - 177
INUA®	178 - 183
MERIDIAN®	184 - 207
MONARCH	208 - 221
ORIGAMI®	222 - 233
THALASSA	234 - 235
VIBE®	236 - 237
THERAPEUTIC CARE UNIT	
VEDANA®	238 - 240
COMPLEMENTARY PRODUCTS	
AKAŠA®	241
SKIRTS	243 - 244

#### **OVERVIEW**

Our **product pages** present all the information you need **TO ORDER** your bath and Complementary Products.

#### PRODUCT NO.

The product number is the **SKU required when you place** an order.

SKU numbers are made from letters and numbers: **BBSUOFN0T-XX**.

- The 0 in the last 3 digits is a zero
- The last two XX should be replaced with the number of the applicable color

Pictures show features and alternative views of the bath.

#### **FEATURES**

The left column indicates the retail price of the product, the features and the options available.

#### **OPTIONS (UPCHARGE APPLICABLE)**

On the right column, are the additional options available with an upcharge. Please add any additional **SKU** required to your order.



#### **INSTALLATION**

The Installation section highlights the dimensions of the bath.

#### **TECHNICAL SPECIFICATIONS**

The Technical Specifications section highlights the technical details for installation of the bath.

Please refer to the Owner's manual for detailed information regarding installation.



## HOW TO COMPLETE YOUR ORDER FORM

All order forms are available in an interactive PDF.

You can find the order forms

- at the last section of this Interactive Price List: bainultra.com/interactive-price-list
   OR
- on our Extranet: bainultra.com/extranet

OR

 request them to our Order Desk orderdesk@bainultra.com

Then, please send by email to **orderdesk@bainultra.com** or by fax at **1-800-382-8587** 



### **COMMERCIAL TERMS &** CONDITIONS

#### 1. MODIFICATIONS

BainUltra® reserves the right to change, without notice, the models, the colors, the specifications and the prices of its products.

#### 2. PAYMENT TERMS

A quick payment discount of 2% can be applied if all sums due are paid by the 10th of the month following the invoice date. Interest charges of one point five percent (1.5%) per month, eighteen percent (18%) per year, will be charged on all past due accounts. Administrative fees of fifteen percent (15%) will be added to the interest charges on all overdue accounts when payment is obtained through a collection agency.

#### 3. MERCHANDISE OWNERSHIP

BainUltra® will remain the owner of all the products sold to Dealer until full and final payment of the invoice is received by BainUltra®. Until such time that an invoice is paid in full, the Dealer must take reasonable care of the BainUltra® merchandise and will be held responsible for all losses and damages when in possession of the merchandise so long as Dealer is solvent. Upon request of BainUltra®, the Dealer must provide proof of insurance to BainUltra®. In the event that one of the parties files for bankruptcy, standard security interest priorities will apply.

#### 4. ADVISING OBLIGATIONS

Dealer agrees to advise BainUltra®, without delay, of all seizures, losses or damages that involve any BainUltra® products in Dealer's inventory for which BainUltra® has not been paid in full.

#### 5. INTELLECTUAL PROPERTY RIGHTS

Dealer acknowledges that all intellectual property rights regarding BainUltra®'s business, activities, products, promotional materials, and any technology pertaining thereto, are the sole property of BainUltra®. Dealer agrees to limit its use of BainUltra®'s intellectual property rights to only those uses expressly authorized by BainUltra®. Dealer agrees to promptly and fully inform BainUltra® of any infringement or alleged infringement of any BainUltra® intellectual property right by any person, including any competitor of BainUltra®, of which Dealer may become

#### 6. NON-STANDARD PRODUCT

- 1. All modifications brought to a standard product will be considered as a non-standard product (ex: removing grab bars). Therefore no deduction of price will be applied to any option removed from a standard product. As for added features (listed as options & upgrades), the price applied will be as listed in the price list.
- 2. Once in production, a non-standard product cannot be cancelled by Dealer and will be invoiced and shipped as ordered, no return possible (see restocking charges).

#### 7. RESTOCKING CHARGES

Merchandise may not be returned for any reason without prior written consent from BainUltra. With the exception of TMU baths with Chromatherapy and factory installed tile flange, no return will be accepted on a non-standard bath and baths without system. Products returned for any reason other than BainUltra's error will be subject to a 25% restocking and handling charge on the Dealer's base net price, in addition to all applicable charges for labor, material and/or freight. BainUltra Inc. reserves the right to refuse a return on a non-standard bath.

#### 8. COLLECTION CHARGES

In the event that any payment due to BainUltra® hereunder is collected at law or through an attorney-at-law, or under advice therefrom, or through a collection agency, Dealer agrees to pay all costs of collection, including, without limitation, all court costs, reasonable attorneys' fees and/or collection agency fees.

#### 9. FREIGHT CHARGES

Freight charges apply to soakers as well as residential, commercial and construction site drop shipments. Add a \$50 fee for a TUB only with at least one therapy. Other shipping charges such as reconsignment, redelivery and storage charges may apply when requested by a dealer or customer. Please contact the BainUltra® order desk for applicable fees.

#### 10. CURRENCY

Unless otherwise indicated, all dollar amounts referred to in these terms and conditions are in United States funds for sales in the U.S.A. and in Canadian funds for sales in Canada.

### THE BAINULTRA® TRANSFERABLE LIMITED WARRANTY

This transferable limited warranty is extended to the original purchaser of the unit who possesses the receipt of purchase. It is valid when the unit is purchased through an authorized Bains Ultra Inc. ("BainUltra®") retailer and registered with BainUltra® (registration is not required for consumer purchasers domiciled in the Province of Québec).

This warranty is also transferable to subsequent home/property owners within the original warranty window, calculated from the date of purchase. As long as the unit is within the warranty period, any eligible warranty claims will be honoured, irrespective of changes in ownership. Please note that this transferability applies only to the original warranty window and does not extend the duration of the original warranty. It is advisable to contact BainUltra® directly when transferring ownership in order to update registration records and ensure a more seamless customer support experience.

When taking delivery of a new bathtub (i.e. original purchase and not transfer of ownership), please note that you are responsible for inspecting the product and all parts prior to installation. This warranty will not apply if a product with visible defects has been installed without providing notice to BainUltra® of the defect.

This revised warranty policy is effective March 1st, 2024

Your BainUltra® ThermoMasseur® or soaking bath is covered by the best warranty in the industry. BainUltra® guarantees the shell material (made with pure acrylic or FineStone®) and motor turbine of your bath for a twenty-(20) year period from the original purchase date against defects in materials and workmanship.

In the case of the electronic components of the therapeutic baths parts of the Vedana® and the technologies Geysair®, the **NEW** AromaFlow, AromaCloud®, WarmTouchShell® and Chromatherapy. BainUltra® guarantees against defects in materials and workmanship for a five-(5) year period from the original purchase date.

Armrests, grab bars and metallic feet are guaranteed for a two-(2) year period.



The wastes and overflows are guaranteed for a one-(1) year period from the original purchase date.

The Akaša® Bath Pillow and Comfort Cushion are guaranteed for a two-(2) year period.

Tile flanges are guaranteed prior to installation only.

BainUltra® products are designed for residential use only. BainUltra® products used for commercial or display applications will be limited to a two-(2) year warranty against defects in materials and workmanship regardless of the specific nature of any potential defects.

BainUltra® products sold outside of North America will be limited to a parts-only warranty through the dealer of the sale. Our service department will help diagnose any problems with your unit and will provide parts only for repairs or replacements covered by the warranty. All parts will be shipped to the dealer in North America. BainUltra® will not be responsible for cost of shipping or servicing outside of North America. Any part that must be changed during the warranty period will be covered by the original warranty or for a two-(2) year period following replacement, according to the first contingency.

#### **EXCLUSIONS**

The above-stated limited warranty applies as long as: i) the damage is not caused by an accident, abuse, misuse, fire, insects, use of abrasive products, force majeure or an act of God. The above-stated limited warranty does not apply to: Transport, handling or installation damages.

Moreover, this warranty is void if: i) your BainUltra® ThermoMasseur® bath, your Vedana®, or any other BainUltra® product is installed by anyone other than a licensed contractor; ii) your BainUltra® bath, your Vedana®, or any other BainUltra® product or part thereof has been modified or if any repairs have been attempted by anyone other than BainUltra®, an authorized BainUltra® dealer, or other representative of BainUltra®; or iii) the unit is installed outdoors, or has not been installed in accordance with BainUltra®'s instructions, or in compliance with local codes and ordinances.

Any and all components that are not provided by BainUltra®, as well as any items attached or installed on your BainUltra® ThermoMasseur®, your Vedana®, or on any other BainUltra® product after the date of manufacture are expressly excluded from this limited warranty.

This limited warranty does not cover any breakage and/or damage resulting from improper (non-factory) installation of AromaCloud® and the **NEW** AromaFlow technologies.

As for the Monarch collection, quartz bathtub deck surface is very strong and resilient; however it can be damaged by impact. The Monarch limited warranty will not cover any damage due to chipping or damage from impact to the surface of the material including scratching.

This would include any failure by the installer who has not followed the necessary installation techniques specified in the installation manual supplied by BainUltra. Any installation that has been found to be the result of improper installation will be the sole responsibility of the installer to repair or replace.

#### **PROCEDURE**

Any defect involving BainUltra®'s potential liability under this limited warranty shall be reported to BainUltra® within ten-(10) days of its occurrence. To assist you with your warranty, please contact BainUltra®'s customer service by email, telephone or fax between 8 a.m. to 6 p.m. Monday to Thursday (EST) or 8 a.m. to 5 p.m. on Friday (EST).

Email: **info@bainultra.com** Tel.: 1 800 463-2187 or 418 831-7701 Fax: 1 800 382-8587 or 418 831-6623

BainUltra 956, chemin Olivier Lévis, Québec Canada G7A 2N1

Proof of purchase and date of purchase will be required. Units claimed to be defective shall be held until inspected by an authorized representative of BainUltra®, and upon their specific instructions, units found to be defective will be repaired or replaced at BainUltra®'s exclusive choice. The liability of BainUltra® with respect to the sale of this unit shall be limited to repair or replacement by a similar product as provided above and does not include any cost of removal, reinstallation, transport and shipping of defective product, loss of time, salary or any other expenses as well as any consequential damages of any kind.

BainUltra® and its representatives shall not be liable for any injury, loss, cost or other damage, whether direct, consequential, incidental, or special, that arise from any defect covered under this limited warranty, even if BainUltra® has been advised of the possibility of such damage. Some states and provinces may not allow the exclusion or limitation of incidental or consequential damages, so the above limitation or exclusion may not apply to you, but these limitations or exclusions will be enforced to the maximum extent of the law.

An adequate access way to mechanical and electrical parts of your BainUltra® ThermoMasseur® bath, your Vedana®, or any other BainUltra® product must be anticipated and prepared before an authorized representative arrives on the premises to carry out a repair. The costs incurred to provide access to the motor turbine, the electronic module or the heating system will not be covered by this warranty.

#### **LIMITATIONS**

Except for consumer purchasers domiciled in the Province of Québec, and except to the extent prohibited by applicable law, this limited warranty replaces all other warranties, expressed or implied, in fact or at law, including implied warranties based on course of dealing, usage of trade, and merchantability and fitness for a particular purpose. (Inapplicable in Québec). The terms of this limited warranty cannot be modified or extended in any way whatsoever by any agent, dealer, distributor, service company or party other than BainUltra®.

BainUltra® excludes any statement in any advertisement or instruction, any picture, or any guideline as an express warranty for our products. We recognize that some states and provinces may not allow limitations on implied warranties, so the above limitations and exclusions may not apply to you, but they will be enforced to the maximum extent of the law.

#### **LEGAL RIGHTS**

This limited warranty gives specific legal rights and is not applicable if it interferes with any law or regulation in any state, province or country.

#### **TURBINE LOCATION**

The turbine must be remotely installed on certain Thermomasseur bath models. Please, follow the specific installation instructions of the Owner's Manual otherwise the warranty will be void.

Failure to follow these instructions may result in serious personal injury or property damage for which BainUltra cannot be held responsible.

### FINESTONE® BATHS





FineStone® is a high quality solid surface material composed of refined minerals and pure liquid acrylic. Baths made with FineStone are now available in two categories: ThermoMasseur® (TMU) (except Celestia collection) and TUB.

#### FineStone TMU bathtubs offer:

- Hydro-thermo Massage® with air jet system
- · Heated backrest

#### Designed with care, FineStone offers a new way to enjoy BainUltra bathing:

- · Thermal insulant; hot temperature resistant
- · Strong, resistant, and durable
- · Light/color resistant. No color bleed or wear
- Non porous, hygienic and easy to clean
- · Can be easily repaired

Bath models made with FineStone are offered in White Satin Finish.



#### THERAPEUTIC BATHS

Our therapeutic baths are made of 100% pure high quality acrylic and come in two categories: ThermoMasseur® and TUB.

#### **THERMOMASSEUR**®

Our air jet baths artfully combine the gentleness of water, the force of air, and the comfort of heat to provide you with the extraordinary benefits of deep massage.

All ThermoMasseur® baths prices are based on standard colors offered.

#### Also included

- · The Geysair® technology
- The standard air-heating system: heated backrest and headrest
- The Mia® or MiaPlus® electronic control and BU-Touch Control Application, depending on the model
- · Grab bars, when applicable

#### Optional therapies offered

- · Illuzio Chromatherapy
- AromaCloud®
- 2<sup>nd</sup> heated backrest (WTS technology - 1 zone)

#### Other options

- · Optional colors
- · UltraVelour matte finish





#### **TURBINE (MOTOR)**

Thermomasseur models must be connected to a dedicated 20 AMP, 120 V, 60 Hz supply circuit protected by a ground-fault circuit interrupter (GFCI). Thermomasseur models



equipped with two heated backrests and/or Illuzio Chromatherapy, and/or AromaCloud® require an additional 15 AMP supply circuit.

#### TUB

All TUBs prices are based on standard colors offered and include grab bars, when applicable.

#### Optional therapies offered (FineStone solid surface baths excluded)

- Illuzio Chromatherapy (with DOT control)
- · WarmTouchShell 3 zones (with DOT control)
- AromaCloud®

#### Other options

- · Optional colors
- · UltraVelour matte finish



#### **ULTRAVELOUR**

UltraVelour is a matte finish, offered in White, and exclusively manufactured by BainUltra. The exceptional quality of UltraVelour finish is a testament to refinement expertise found in this handcrafted bath finish. BainUltra's UltraVelour finish is available across a number of collections\*. See FINISH, p. 13.



**NOKORI** 7131 ULTRAVELOUR

The UltraVelour finish is offered on grab bars. It is not available for Controls, AromaCloud® and Universal Skirts SJ1 & SJ3.

\* Not offered for Essencia Oval 7236 Freestanding model.

#### THERAPEUTIC CARE UNIT

This care unit provides unique therapeutic experiences. It combines multiple therapies, which can be activated independently or simultaneously according to your needs at any given time, to produce a specific emotional state (harmony, balance, sense of fulfillment, etc.) by stimulating your senses.

#### **VEDANA®**

#### Five therapies combined. A unique system.

With Vedana, BainUltra transforms your shower area into a veritable heaven of health and well-being. Intelligently designed, cozy, and welcoming, Vedana offers the well known benefits of five therapies in a single system.

The Vedana system includes:

- One care unit combining five therapies: Aromatherapy, Light Therapy, Thermotherapy, Chromatherapy, and Sound Therapy
- Two integrated 30 minute preprogrammed sessions
- Four 15 minute preprogrammed experiences
- A discovery box (essential oils and nebulizer)
- User guide
- · Available in two colors: White and Biscuit
- · MiaPlus® Control



## AKAŠA®'S COMPLEMENTARY PRODUCTS

Exclusively from BainUltra, Akaša's complementary products are specifically designed and built for you to enhance the therapeutic experience provided by our other products.

#### **BATH PILLOW**

Finesse, smoothness and sturdiness come together to offer the bather more comfort and well-being. Wisely placed by bather to the desired position, the bath pillow supports the neck wonderfully to offer the upmost in comfort and a feeling of complete relaxation and increased benefits.

#### **COMFORT CUSHION**

Made in Italy, this high quality urethane cushion offers the best comfort possible and bonifies the Hydro-thermo Massage® experience benefits. Its isolating properties will keep your body feeling warm all through the bath session. It will adhere naturally to the bath. No magnets are used. The Akaša Comfort Cushion is available for several BainUltra models (see page 241 for the list of Bath Models available for the Akaša Comfort Cushion).

#### NORDIC SPIRIT ESSENTIAL OILS (15 ml bottle)

#### For the Aromacloud®, Aromaflow, and the Vedana®

Optimize the benefits of your therapeutic products with the essential oils synergy Nordic Spirit. This synergy prepared from pure and healthy ingredients and plunges your body and mind into a deep wellness.

Nordic Spirit Synergy can be used with our essential oil diffusers AromaCloud\*, and AromaFlow\*, and Vedana Therapeutic Unit.

\*Do not pour essential oils directly into your bath water.



#### **THERAPIES**

#### SUPPORTED BY TECHNOLOGIES THAT ENSURE YOUR WELL-BEING

#### **GEYSAIR®** (HYDRO-THERMO MASSAGE)

Geysair® is a revolutionary system of warm air jets exclusive to BainUltra®. Like the hot water that spurts out of a geyser, the air jets conserve their heat until they hit your skin, thanks to Geysair technology. This eliminates the cold feeling of dry air bubbles on your body and keeps the temperature uniform. How it works is very simple: Geysair heats and humidifies the air, which is then able to conserve its warmth. Geysair can be turned on using the MiaPlus® Control or the BU-Touch Control Application.



Included on all ThermoMasseurs.

#### AROMACLOUD® (AROMATHERAPY)

AromaCloud®: an essential oil diffuser ingeniously built into the bathtub's deck. Energizing, anti-inflammatory, and regenerating, diffused essential oils are absorbed effectively by your body.

AromaCloud® installation may vary depending on the model. It is usually incorporated into the deck. If there is insufficient space, the deck will be adapted to house the AromaCloud®. The AromaCloud is not offered in UltraVelour finish.

AromaCloud® works independently of the other technologies and is easy to turn on. Includes one 15 ml vial of essential oil.

Available as an option on ThermoMasseurs and TUBs.



#### NEW

#### **AROMAFLOW (AROMATHERAPY)**

Discover the next evolution of aromatherapy in the bath with AromaFlow. The AromaFlow is an essential oil diffuser that combines the benefits of aromatherapy while being elegantly included into the bathtub's integrated overflow.

Easy-to-use seamless design, the AromaFlow offers a beautiful and therapeutic way to enjoy essential oils with your BainUltra bathtub\*. One to two drops of essential oil are enough for a 30-45 minutes session.

\*Offered as an option in all collections except BeOne, Balneo, Celestia, and Opus.




#### WARMTOUCHSHELL® (THERMOTHERAPY)

WarmTouchShell® technology features heating zones built into your bath's inner shell. These heating zones transmit and circulate continuous heat to the headrest, backrests and seat. They touch and warm the body's most sensitive areas, providing a deep feeling of relaxation.

WarmTouchShell system can be turned on independently using a DOT control.

Available as an option on TUBs.

Available as an option on ThermoMasseurs with 2nd heated backrest (backrest zone only).



#### **ILLUZIO (CHROMATHERAPY)**

BainUltra has developed ILLUZIO, a chromatherapy system with hidden LED lights that leaves the bath's inner shell completely intact and smooth when the system is not in operation. Activate Illuzio and see the spectrum of colors come to life. Chromatherapy, an age-old technique recently rediscovered by scientists, can enhance your health and well-being.

ILLUZIO uses various colors (red, orange, yellow, green, blue, and purple) that deliver the most effective chromatherapy with maximum benefits.

ILLUZIO Chromatherapy can be turned on independently using a DOT control, MiaPlus® Control or with the BU-Touch Control Application in a TMU.

Available as an option on ThermoMasseurs and TUBs.



(Prices on page 40)

## THERMOMASSEUR® CONTROLS

#### **BU-TOUCH CONTROL APPLICATION**

With the purchase of a ThermoMasseur® with a Mia® or MiaPlus® Control, you now have the option to add the virtual control to navigate through the therapies and functions of your ThermoMasseur.

The BU-Touch is a new and simple way to control your bath session from your mobile devices. It comes with the same functional and operational features as the Mia & MiaPlus.

Activate Hydro-thermo Massage® and Geysair warm air jets

Set heated backrest & headrest temperature

Select colors for chromatherapy (Bath with Illuzio)

Program drying cycle



You can now start and program your session from a distance or easily change your settings while enjoying your Hydro-thermo Massage.

BU-Touch application is available on Google Play or App Store. BU-Touch works with a Home transmitter (included) that must be connected to your router.





#### MIA® CONTROL

Simple and understated, the Mia® Control lets you adjust the air jet intensity to relax the way you want.

· Increase or decrease air jet intensity

· Activate the drying cycle



#### MIAPLUS® CONTROL

Its clear display is easy to read from all angles, letting you select your own customized relaxation session.

- · Air jet intensity
- Activates the Geysair warm air jets
- Choice of light color (Chromatherapy option)
- · Session duration

- · Backrest temperature
- Personalized session settings for up to 4 different users
- Personalized drying cycle



## **TUB CONTROLS**

#### **DOT CONTROLS**


Our DOT controls blend perfectly with all our acrylic bath models. Simple and user-friendly. It allows you to separately enable/disable the heating zones of WarmTouchShell® and the chromatherapy of your TUB. Available in White & Biscuit.

When the deck of the bath has been modified to integrate the AromaCloud®, the DOT control will not be at its standard location.





#### Position of DOT control on modified deck.



On either side of the AromaCloud® For the following models: Balneo, all the Ellipse with rolled deck, Essencia 6838.



Side by side, beside the AromaCloud® Essencia Oval 7236

## **WASTE & OVERFLOW**

(Prices on page 38)

#### **INTEGRATED WASTE & OVERFLOW**

An Integrated waste & overflow with customize molding. Chic, modern and unobtrusive.



Choice of finish:

















White

Biscuit

Chrome

Nickel

Nickel

Brushed

Matte Black

Satin Brass

Matte White

- · Installed and included on Bain de Ville, BeOne, Celestia, Charism, Citti, Esthesia, Evanescence, Libra, Monarch, Nokori, Opalia, Opus, Scala, Vibe collections and the Essencia Design model.
- Offered as an option on other models (see product pages for information).
- For UltraVelour matte finish or FineStone satin finish, the white integrated waste & overflow will be Matte White.
- · Integrated waste & overflow is mandatory when buying an AromaFlow essential oil diffuser (upcharge may apply depending on the bath model).

#### WASTE & OVERFLOW D14 (ELEGANCIA® COLLECTION)

Fit perfectly with Elegancia baths. Pop-up system.















Polished Nickel

Brushed Nickel

#### **WASTE & OVERFLOW 16" X 35"**

The finishing touch for your bath. Cable driven.













Nickel





Nickel



Oil-rubbed Bronze

#### WASTE & OVERFLOW D13\* (EXPOSED)

Exposed\* waste & overflow complete the luxurious look of Balneo baths.

\* Please note that the D13 piping is visible from the outside of the bath.















Unplated

Note: Printed colors shown here may vary slightly from actual colors. Please use this chart as a reference only.

## ISLAND TUB DRAIN™ & TILE FLANGE

(Prices on pages 39 and 40)

#### ISLAND TUB DRAIN™

The Island Tub Drain™ makes it easy to install a freestanding bathtub.

Here are the key benefits:

- Easy to connect plumbing
- Installation from above the floor; no need to have access under the bath
- · Ideal for installation on a concrete slab
- Allows for the bath to be installed after tiles or other floor finish



#### **CAST IRON ISLAND TUB DRAIN™**

#### Features:

- Asymmetric design 18 Gauge Epoxy coated Metal Deck Plate with holes to lock to Thinset
- Snap off Test Cap (Rated to 30psi)
- · Mortar/Tile Guard
- ID357 features a Cast Iron Body
- Low profile design allows for installation in 8" joist spaces or greater



#### **TILE FLANGE**

When ordering a bath with a factory-installed or molded tile flange, it is essential to specify the position of the waste. If waste is central, specify front or back. If waste is at the end, specify right or left. For a special installation, a sketch must be provided.









#### AromaCloud® position

When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.

#### WARNING

The AromaCloud® may interfere with shower doors.

## **GRAB BARS, ARMRESTS & FEET**

(Prices on page 39)

#### **GRAB BARS**

#### 1- Acrylic







White

**Biscuit** 

Note: White grab bars are also available in the UltraVelour Matte finish.

#### 2- Clear Acrylic



Transparent with Chrome or Brushed Nickel inserts

### **ARMRESTS & FEET**



Scala exclusive armrests



Scala feet

Chrome

Scala armrests & feet are available in the following finishes:





Polished

Nickel



Nickel





Satin Brass

Note: Acrylic grab bars are available for most of our models. For more information, please contact BainUltra customer service.

#### **UNIVERSAL ARMRESTS**



Universal Armrests are available in White, Glossy Finish only, for the collections: Bain de Ville, Balneo, Charism, Citti, Esthesia, Evanescence, Libra\*, Nokori, Opalia, Origami\*, and Vibe.

\* Except the Libra Oval 6635, & Origami 6030 models.



#### **CLAW FEET FOR CELLA MODELS** (EXCLUSIVE TO BALNEO® COLLECTION)

Cella comes with claw feet to add a personalized and unique touch of class to this freestanding bath.









Nickel

Polished Nickel

Unplated



Oil-rubbed Bronze

Please use this chart as a reference only.

Note: Printed colors shown here may vary slightly from actual colors.

## **COLOR & FINISH**

#### COLOR

BainUltra®'s acrylic baths are offered in a vast range of standard as well as optional colors to match perfectly to the colors widely offered by most manufacturers of bathroom fixtures today.

#### **BATHS | STANDARD COLORS**





White

Biscuit

#### **BATHS | OPTIONAL COLOR**



Black / White

#### MIA® AND DOT CONTROLS | COLORS





White

**CHARISM BATHS | STANDARD DECK COLORS** 



White

#### CHARISM BATHS | OPTIONAL DECK COLORS







Crystal Rock

Copper

#### **BATHS MADE WITH FINESTONE®** STANDARD COLOR



White

#### MONARCH BATHS | DECK COLORS

Monarch baths deck surfaces are made of **high quality quartz** offered in various natural and vibrant colors.



(Silestone)







Lagos Blue (Caesarstone)

#### MONARCH BATHS | OPTIONAL DECK COLORS







Piatra Grey (Caesarstone)



Bianco Drift (Caesarstone)







Statuario Maximus (Caesarstone)

#### **FINISH**

#### **ACRYLIC**





**FINESTONE** 

Satin

#### FINESTONE® - SOLID SURFACE - SUMMARY PRICE LIST

#### **BY COLLECTION**



 $Models\ presented\ in\ this\ section\ are\ made\ with\ Fine Stone @,\ an\ exclusive\ high\ quality\ solid\ surface\ material\ developped\ by\ Bain Ultra.$ They are available as soaking TUBs and ThermoMasseurs (TMU) (OPUS) in White, Satin Finish only. For further information on FineStone, please refer to page 6.

							THERAPIES (+)		CONTROL (+)			
Page			TUB	Thermo- Masseur TMU	Aroma- Cloud®	Illuzio Chroma- therapy	Warm TouchShell WTS	Heated Backrest	2 <sup>nd</sup> WTS	MiaPlus® Control	DOT control	BU-Touch
	CELESTIA™ 🥨											
42	CELESTIA 6233 (FS) 62" x 33" x 24"	•	\$8,000	_	_	_	_	_	_	_	_	_
44	CELESTIA 6635 (FS) 66" x 35" x 25"	**	\$8,600	_	_	_	_	_	_	_	_	_
	OPUS											
46	OPUS 6434 (FS) 64" x 34" x 25" NEW TMU	**	\$8,900	\$11,750	_	_	_	Incl.	_	Incl.	_	Incl.

### THERMOMASSEUR® (TMU) – SUMMARY PRICE LIST

	_			THERAPIES (+)					CONTROLS (+)			OPTIONS (+)		
Page			Thermo- Masseur TMU	Aroma- Cloud®	Aroma- Flow	Illuzio Chroma- therapy	Heated Backrest	2 <sup>nd</sup> Heated Backrest	Heated Headrest	Mia®	MiaPlus®	BU- Touch App <sup>‡‡</sup>	Colors	Ultra- Velour matte finish
	AMMA®													
136	AMMA 6030 60" x 30" x 21"	•	\$6,545	\$490†	\$9500	\$925	Incl.	_	Incl.	_	Incl.	\$430	_	_
138	AMMA 6032 60" x 32" x 21"	•	\$6,545	\$490†	\$950	\$925	Incl.	_	Incl.	_	Incl.	\$430	_	_
140	AMMA 6036 60" x 36" x 21"	•	\$7,455	\$490†	\$950	\$925	Incl.	_	Incl.	_	Incl.	\$430	_	_
142	AMMA 6636 66" x 36" x 21"	•	\$7,680	\$490†	\$950	\$925	Incl.	_	Incl.	_	Incl.	\$430	_	_
144	AMMA OVAL 6638 66" x 38" x 21"	•	\$7,680	\$490	\$950	\$925	Incl.	_	Incl.	_	Incl.	\$430	_	_
146	AMMA 7236 72" × 36" × 21"	**	\$7,965	\$490†	\$950	\$925	Incl.	Incl.	Incl.	_	Incl.	\$430	_	_
148	AMMA 7242 72" × 42" × 22"	**	\$8,105	\$490†	\$950°	\$925	Incl.	Incl.	Incl.	_	Incl.	\$430	_	_
150	AMMA OVAL 7242 Raised or flat deck 72" x 42" x 22"	**	\$7,965	\$490	\$950°	\$925	Incl.	Incl.	Incl.	_	Incl.	\$430	_	_
52	AMMA OVAL 7242 (FS) Narrow base, raised or flat deck 72" x 42" x 24"	**	\$11,255	\$490	\$950°	\$925	Incl.	Incl.	Incl.	_	Incl.	\$430	_	_
54	AMMA OVAL 7242 (FS) Raised or flat deck 72" x 42" x 28"	**	\$12,645	\$490	\$950°	\$925	Incl.	Incl.	Incl.	_	Incl.	\$430	_	_
	BAIN DE VILLE													
152	BAIN DE VILLE 6030** 60" x 30" x 17"	•	\$3,595	\$490 <sup>†</sup>	\$950	\$925 <sup>‡</sup>	Incl.	_	_	Incl.	\$285	\$430	_	\$650
154	BAIN DE VILLE 6632** 66" x 32" x 20"	•	\$5,085	\$490†	\$950	\$925‡	Incl.	_	_	Incl.	\$285	\$430	_	\$650
	<b>BALNEO</b> ® (Flat or rolled deck)													
56	CELLA 6636 (FS) 66" x 36" x 27"	**	\$10,145	\$490	_	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	_	_
58	CELLA 7240 (FS) 72" × 40" × 27"	**	\$11,100	\$490	_	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	_	_
60	NAOS 6636 (FS) 66" x 36" x 25"	**	\$11,240	\$490	_	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	_	_
62	NAOS 7240 (FS) 72" × 40" × 25"	**	\$12,055	\$490	_	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	_	_
64	SANOS 6636 (FS) 66" × 36" × 24"	**	\$9,880	\$490	_	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	_	_
66	SANOS 7240 (FS) 72" x 40" x 24"	**	\$10,560	\$490	_	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	_	_
	<b>BEONE</b> <sup>TM</sup>													
68	BEONE 4639 (FS) 46" x 39" x 30"	•	\$9,360	_	_	\$925	Incl.	_	_	-	Incl.	Incl.	\$490	\$850

- $\dagger\dagger$  All contours are available at the same price. \* Available with or without integrated tile flange.

Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

† When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.

†† All contours

†† Optional deck color Black, Crystal Rock, and Copper.

# Slim deck available at same price.

\* Available wi

\*\* Integrated tile flange & skirt.

† The MiaPlus® Control is included when purchasing this option.

‡† The BU-Touch Application is available with the purchase of a ThermoMasseur bath with Mia® or MiaPlus® Control.

† When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.

### THERMOMASSEUR® (TMU) - SUMMARY PRICE LIST

				THERAPIES (+)				CONTROLS (+)			OPTIONS (+)			
Page			Thermo- Masseur TMU	Aroma- Cloud®	Aroma- Flow	Illuzio Chroma- therapy	Heated Backrest	2 <sup>nd</sup> Heated Backrest	Heated Headrest	Mia®	MiaPlus®	BU- Touch App <sup>‡‡</sup>	Colors	Ultra- Velour matte finish
	CHARISM®													
70	CHARISM 5736 (FS) 57" x 36" x 23"	•	\$9,655	_	\$950	\$925	Incl.	_	_	_	Incl.	Incl.	\$250†††	\$850
72	CHARISM 6434 (FS) 64" x 34" x 24"	**	\$11,000	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	\$250†††	\$850
74	CHARISM OVAL 6436 (FS) 64" × 36" × 24"	**	\$11,000	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	\$250†††	\$850
	CITTI®													
156	CITTI 17** 60" x 32" x 17"	•	\$3,700	\$490 <sup>†</sup>	\$950	\$925‡	Incl.	_	_	Incl.	\$285	\$430	_	\$650
158	CITTI 6032 WITH INSERT** 60" × 32" × 20"	•	\$4,935	\$490	\$950	\$925 <sup>‡</sup>	Incl.	_	_	Incl.	\$285	\$430	_	\$650
160	CITTI 6032 WITHOUT INSERT** $60" \times 32" \times 20"$	•	\$4,670	\$490	\$950	\$925‡	Incl.	_	_	Incl.	\$285	\$430	_	\$650
162	CITTI 6032 TRIO WITH INSERT (Integrated tile flange) 60" × 32" × 20"	•	\$4,920	\$490	\$950	\$925‡	Incl.	_	_	Incl.	\$285	\$430	_	\$650
164	CITTI 6032 TRIO WITHOUT INSERT (Integrated tile flange) 60" x 32" x 20"	•	\$4,665	\$490	\$950	\$925 <sup>‡</sup>	Incl.	_	_	Incl.	\$285	\$430	_	\$650
	ELEGANCIA®													
166	ELEGANCIA 6636 <sup>††</sup> 66" x 36" x 21"	**	\$6,330	\$490†	\$9500	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	_
168	ELEGANCIA 6642 <sup>††</sup> 66" x 42" x 21"	**	\$6,455	\$490†	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	_
170	ELEGANCIA 7236 <sup>††</sup> 72" x 36" x 21"	**	\$6,500	\$490 <sup>†</sup>	\$9500	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	_
172	ELEGANCIA 7242 <sup>††</sup> 72" x 42" x 21"	**	\$6,585	\$490 <sup>†</sup>	\$950°	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	_
	<b>ESSENCIA</b> ®													
76	ESSENCIA 6838 (FS) 68" x 38" x 26"	•	\$11,035	\$490	\$950	\$925	Incl.	_	Incl.	_	Incl.	Incl.	\$475	\$850
78	ESSENCIA DESIGN (FS) 72" x 36" x 24"	•	\$10,535	_	\$950	\$925	Incl.	_	_	_	Incl.	Incl.	\$475	\$850
80	ESSENCIA OVAL 7236 (FS) 72" x 36" x 27"	•	\$10,995	\$490	\$950	\$925	Incl.	_	Incl.	_	Incl.	Incl.	_	_
174	ESSENCIA OVAL 7236 72" × 36" × 25"	•	\$6,425	\$490	\$950	\$925	Incl.	_	Incl.	_	Incl.	\$430	_	\$850
	ESTHESIA®													
82	ESTHESIA 6436 (FS) 64" x 36" x 25"	**	\$9,510	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	\$835	\$1,025
176	ESTHESIA 6638 66" x 38" x 21"	**	\$5,875	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650

- Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

  † When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.

  ††† Optional deck color Black, Crystal Rock, and Copper. # Slim deck available at same price.

  \*\* Integrated tile flange & skirt. ‡ The MiaPlus® Control is included when p
- †† All contours are available at the same price.

  \* Available with or without integrated tile flange.

- ‡ The MiaPlus® Control is included when purchasing this option.
- ‡‡ The BU-Touch Application is available with the purchase of a ThermoMasseur bath with Mia® or MiaPlus® Control.
- When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.

### THERMOMASSEUR® (TMU) – SUMMARY PRICE LIST

#### BY COLLECTION

						THERA	PIES (+)				CONTROLS (+	)	OPTIC	ONS (+)
Page			Thermo- Masseur TMU	Aroma- Cloud®	Aroma- Flow	Illuzio Chroma- therapy	Heated Backrest	2 <sup>nd</sup> Heated Backrest	Heated Headrest	Mia®	MiaPlus®	BU- Touch App <sup>‡‡</sup>	Colors	Ultra- Velour matte finish
	<b>EVANESCENCE®</b>													
84	EVANESCENCE 5936 (FS) 59" x 36" x 28"	•	\$9,325	_	\$950	\$925	Incl.	_	Incl.	_	Incl.	Incl.	\$475	\$850
86	EVANESCENCE 6634 (FS) 66" x 34" x 28"	**	\$10,420	_	\$950	\$925	Incl.	\$1,125	Incl.	_	Incl.	Incl.	\$475	\$850
88	EVANESCENCE OVAL 6636 (FS) 66" x 36" x 28"	**	\$10,420	_	\$950	\$925	Incl.	\$1,125	Incl.	_	Incl.	Incl.	\$475	\$850
90	EVANESCENCE OVAL 7440 (FS) 74" × 40" × 28"	**	\$10,685	_	\$950	\$925	Incl.	\$1,125	Incl.	_	Incl.	Incl.	\$475	\$850
	INUA® (Slim or standard deck)													
178	INUA 6036# 60" x 36" x 23"	•	\$7,930	\$490	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650
180	INUA 6636# 66" x 36" x 23"	•	\$7,975	\$490	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650
182	INUA 7240# 72" × 40" × 23"	**	\$8,500	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650
	LIBRA													
92	LIBRA 6632 (FS) 66" × 32" × 23"	**	\$8,850	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	\$475	\$850
94	LIBRA AURORA 6634 (FS) 66" x 34" x 24"	**	\$9,330	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	\$475	\$850
96	LIBRA OVAL 6635 (FS) 66" × 35" × 27"	**	\$9,750	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	\$475	\$1,025
98	LIBRA STELLA 7038 (FS) 70" x 38" x 25" NEW	**	\$9,910	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	\$475	\$1,025
	MERIDIAN®													
184	ELLIPSE 6636 Flat or rolled deck 66" x 36" x 21"	**	\$6,080	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	_
186	ELLIPSE 7240 Flat or rolled deck 72" x 40" x 21"	**	\$6,420	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	_
188	MERIDIAN UNO** 60" x 31" x 21"	•	\$4,265	\$490 <sup>†</sup>	\$950	\$925‡	Incl.	_	_	Incl.	\$285	\$430	_	_
190	MERIDIAN DUO** 60" x 31" x 21"	•	\$4,265	\$490 <sup>†</sup>	\$950	\$925‡	Incl.	_	_	Incl.	\$285	\$430	_	_
192	MERIDIAN 6030* 60" x 30" x 21"	•	\$4,265	\$490 <sup>†</sup>	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	_
194	MERIDIAN 6032* 60" x 32" x 21"	•	\$4,885	\$490 <sup>†</sup>	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	_
196	MERIDIAN 50 60" x 36" x 20"	•	\$5,045	\$490 <sup>†</sup>	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	_
198	MERIDIAN 6042 60" x 42" x 21"	•	\$5,440	\$490 <sup>†</sup>	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	_
200	MERIDIAN 55 66" x 36" x 20"	**	\$5,490	\$490 <sup>†</sup>	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	_
202	MERIDIAN 60 72" × 36" × 21"	**	\$5,600	\$490 <sup>†</sup>	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	_
204	PRO-MERIDIAN 55 66" x 34" x 20"	•	\$5,405	\$490 <sup>†</sup>	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	_
206	PRO-MERIDIAN 60 72" × 36" × 20"	•	\$5,770	\$490 <sup>†</sup>	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	_

#### Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

- † When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.
  †† All contours
  †† Optional deck color Black, Crystal Rock, and Copper.

  # Slim deck available at same price.

  \* Available will
  the grated tile flange & skirt.

  † The MiaPlus® Control is included when purchasing this option.
  †† Bu-Touch Application is available with the purchase of a ThermoMasseur bath with Mia® or MiaPlus® Control.

  When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed. †† All contours are available at the same price.

  \* Available with or without integrated tile flange.

### THERMOMASSEUR® (TMU) - SUMMARY PRICE LIST

#### BY COLLECTION

						THERA	PIES (+)				CONTROLS (+	-)	OPTIC	)NS (+)
Page			Thermo- Masseur TMU	Aroma- Cloud®	Aroma- Flow	Illuzio Chroma- therapy	Heated Backrest	2 <sup>nd</sup> Heated Backrest	Heated Headrest	Mia®	MiaPlus®	BU- Touch App‡‡	Colors	Ultra- Velour matte finish
	MONARCH													
208	MONARCH 6032 Standard or Grand Luxury 60" x 32" x 20"	•	S \$5,805 GL \$9,440	_	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650
210	MONARCH 6036 Standard or Grand Luxury 60" x 36" x 20"	•	S <b>\$5,990</b> GL <b>\$9,715</b>	_	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650
212	MONARCH 6636 Standard or Grand Luxury 66" x 36" x 20"	**	S <b>\$6,050</b> GL <b>\$10,140</b>	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650
214	MONARCH 6638F Standard or Grand Luxury 66" x 38" x 20"	**	S <b>\$6,100</b> GL <b>\$10,255</b>	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650
216	MONARCH 7236 Standard or Grand Luxury 72" x 36" x 21"	**	s <b>\$6,285</b> GL <b>\$10,600</b>	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650
218	MONARCH 7238F Standard or Grand Luxury 72" x 38" x 21"	**	s <b>\$6,340</b> GL <b>\$10,705</b>	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650
220	MONARCH 7240 Standard or Grand Luxury 72" x 40" x 21"	**	S <b>\$6,470</b> GL <b>\$10,955</b>	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650
	NOKORI®													
100	NOKORI 6331 (FS) 63" x 31" x 24"	•	\$10,160	_	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$850
102	NOKORI 6429 (FS) 64" x 29" x 23"	•	\$9,790	_	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$850
104	NOKORI OVAL 6737 (FS) 67" x 37" x 24"	**	\$10,380	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	\$475	\$850
106	NOKORI 6935 (FS) 69" x 35" x 24"	**	\$10,620	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$850
108	NOKORI 7131 (FS) 71" x 31" x 24"	**	\$10,485	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$850
	OPALIA®													
110	OPALIA 6839 CENTERED ELLIPSE (FS) 68" x 39" x 25"	**	\$8,815	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	\$475	\$850
112	OPALIA 6839 OFF-CENTERED ELLIPSE - LEFT (FS) 68" x 39" x 25"	**	\$8,815	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	\$475	\$850
114	OPALIA 6839 OFF-CENTERED ELLIPSE - RIGHT (FS) 68" x 39" x 25"	**	\$8,815	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	\$475	\$850
116	OPALIA 6839 OBLIQUE ELLIPSE - LEFT (FS) 68" x 39" x 25"	**	\$8,815	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	\$475	\$850
118	OPALIA 6839 OBLIQUE ELLIPSE - RIGHT (FS) 68" x 39" x 25"	**	\$8,815	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	\$475	\$850

Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

† When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.

†† All contours

†† All contours

†† Optional deck color Black, Crystal Rock, and Copper.

# Slim deck available at same price.

\* Available wi

\* The MiaPlus® Control is included when purchasing this option. †† All contours are available at the same price. \* Available with or without integrated tile flange.



18

<sup>‡‡</sup> The BU-Touch Application is available with the purchase of a ThermoMasseur bath with Mia® or MiaPlus® Control.

When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.

### THERMOMASSEUR® (TMU) – SUMMARY PRICE LIST

				THERAPIES (+)					CONTROLS (+	-)	OPTIONS (+)			
Page			Thermo- Masseur TMU	Aroma- Cloud®	Aroma- Flow	Illuzio Chroma- therapy	Heated Backrest	2 <sup>nd</sup> Heated Backrest	Heated Headrest	Mia®	MiaPlus®	BU- Touch App <sup>‡‡</sup>	Colors	Ultra- Velour matte finish
	ORIGAMI®													
222	ORIGAMI 6030 (2" deck height only) Original Series 60" x 30" x 21"	•	\$5,725	\$490 <sup>†</sup>	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650
224	ORIGAMI 6032# Original Series 60" x 32" x 21"	•	\$5,820	\$490†	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650
226	ORIGAMI 6632# Original Series 66" x 32" x 21"	•	\$6,180	\$490†	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650
228	ORIGAMI 6636# Original Series 66" x 36" x 22"	•	\$6,425	\$490†	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650
230	ORIGAMI 7236# Original Series 72" x 36" x 22"	**	\$6,700	\$490†	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650
232	ORIGAMI 7242# Original Series 72" x 42" x 22"	**	\$7,105	\$490†	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650
	SCALA													
120	SCALA 6638 (FS) 66" × 38" × 25"	**	\$10,875	_	\$950	\$925	Incl.	\$1,125	Incl.	_	Incl.	Incl.	_	\$850
122	SCALA 7242 (FS) 72" × 42" × 25"	**	\$11,750	_	\$950	\$925	Incl.	\$1,125	Incl.	_	Incl.	Incl.	_	\$850
	THALASSA													
234	<b>SENSATION</b> 54" × 54" × 20"	**	\$5,100	\$490	\$950	\$925‡	Incl.	\$1,125	Incl.	Incl.	\$285	\$430	_	_
	VIBE®													
124	VIBE 5828 (FS) 58" x 28" x 21"	•	\$8,655	_	\$950	\$925	Incl.	_	_	_	Incl.	\$430	\$475	\$850
126	VIBE BACK TO WALL 5828 (FS) 58" x 28" x 21"	•	\$9,155	_	\$950	\$925	Incl.	_	_	_	Incl.	\$430	\$475	\$850
128	VIBE OVAL 5830 (FS) 58" × 30" × 21"	•	\$8,655	_	\$950	\$925	Incl.	_	_	_	Incl.	\$430	\$475	\$850
236	VIBE 6030 (Integrated tile flange) 60" x 30" x 19"	•	\$4,895	_	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650
130	VIBE DESIGN 6033 (FS) 60" x 33" x 21"	•	\$8,655	_	\$950	\$925	Incl.	-	_	_	Incl.	\$430	\$475	\$850

- Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

  † When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.
- ††† Optional deck color Black, Crystal Rock, and Copper. # Slim deck available at same price. Integrated tile flange & skirt.
- †† All contours are available at the same price. \* Available with or without integrated tile flange.
- ‡ The MiaPlus® Control is included when purchasing this option.
- The BU-Touch Application is available with the purchase of a ThermoMasseur bath with Mia® or MiaPlus® Control. ♦ When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.

						THERAPIES (+)			CONTROL (+)	OPTIO	ONS (+)
Page			TUB	Aroma- Cloud®	AromaFlow	Illuzio Chroma- therapy	Warm TouchShell WTS	2 <sup>nd</sup> WTS	DOT control	Colors	UltraVelour matte finish
	AMMA®										
136	AMMA 6030 60" x 30" x 21"	•	\$4,055	\$490 <sup>†</sup>	\$950°	\$925	\$1,125	_	Incl.	_	_
138	AMMA 6032 60" x 32" x 21"	•	\$4,055	\$490 <sup>†</sup>	\$950°	\$925	\$1,125	_	Incl.	_	_
140	<b>AMMA 6036</b> 60" x 36" x 21"	•	\$4,685	\$490 <sup>†</sup>	\$950°	\$925	\$1,125	_	Incl.	_	_
142	AMMA 6636 66" x 36" x 21"	•	\$4,790	\$490 <sup>†</sup>	\$950°	\$925	\$1,125	_	Incl.	_	_
144	AMMA OVAL 6638 66" x 38" x 21"	•	\$4,930	\$490	\$950°	\$925	\$1,125	_	Incl.	_	_
146	AMMA 7236 72" × 36" × 21"	**	\$4,930	\$490 <sup>†</sup>	\$950°	\$925	\$1,125	\$370	Incl.	_	_
148	AMMA 7242 72" × 42" × 22"	**	\$5,060	\$490 <sup>†</sup>	\$950°	\$925	\$1,125	\$370	Incl.	_	_
150	AMMA OVAL 7242 Raised or flat deck 72" x 42" x 22"	**	\$5,060	\$490	\$950°	\$925	\$1,125	\$370	Incl.	_	_
52	AMMA OVAL 7242 (FS) Narrow base, raised or flat deck 72" x 42" x 24"	**	\$8,780	\$490	\$950°	\$925	\$1,125	\$370	Incl.	_	_
54	AMMA OVAL 7242 (FS) Raised or flat deck 72" x 42" x 28"	**	\$9,725	\$490	\$950°	\$925	\$1,125	\$370	Incl.	_	_
	BAIN DE VILLE										
152	BAIN DE VILLE 6030** 60" x 30" x 17"	•	\$1,930	\$490 <sup>†</sup>	\$950	\$925	\$1,125	_	Incl.	_	\$650
154	BAIN DE VILLE 6632** 66" × 32" × 20"	•	\$2,760	\$490 <sup>†</sup>	\$950	\$925	\$1,125	_	Incl.	_	\$650
	<b>BALNEO</b> <sup>®</sup> (Flat or rolled deck)										
56	CELLA 6636 (FS) 66" × 36" × 27"	**	\$7,260	\$490	_	\$925	\$1,125	\$370	Incl.	_	_
58	CELLA 7240 (FS) 72" × 40" × 27"	**	\$8,485	\$490	_	\$925	\$1,125	\$370	Incl.	_	_
60	NAOS 6636 (FS) 66" x 36" x 25"	**	\$8,195	\$490	_	\$925	\$1,125	\$370	Incl.	_	_
62	72" x 40" x 25"	**	\$9,040	\$490	_	\$925	\$1,125	\$370	Incl.	_	_
64	SANOS 6636 (FS) 66" x 36" x 24"	**	\$7,230	\$490	_	\$925	\$1,125	\$370	Incl.	_	_
66	SANOS 7240 (FS) 72" x 40" x 24"	**	\$7,925	\$490	_	\$925	\$1,125	\$370	Incl.	_	_
	BEONE™										
68	BEONE 4639 (FS) 46" x 39" x 30"	•	\$7,280	_	_	\$925	\$1,125	_	Incl.	\$475	\$850
	CHARISM®										
70	CHARISM 5736 (FS) 57" x 36" x 23"	•	\$7,050	_	\$950	\$925	\$1,125	_	Incl.	\$250†††	\$850
72	CHARISM 6434 (FS) 64" x 34" x 24"	**	\$8,525	_	\$950	\$925	\$1,125	\$370	Incl.	\$250†††	\$850
74	CHARISM OVAL 6436 (FS) 64" x 36" x 24"	**	\$8,525	_	\$950	\$925	\$1,125	\$370	Incl.	\$250†††	\$850

- Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

  † When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.

  ††† Optional deck color Black, Crystal Rock, and Copper. # Slim deck available at same price.
  - †† All contours are available at the same price.

    \* Available with or without integrated tile flange.

- \*\* Integrated tile flange & skirt. ‡ The MiaPlus® Control is included when purchasing this option.

When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.



						THERAPIES (+)			CONTROL (+)	OPTI	ONS (+)
Page			TUB	Aroma- Cloud®	AromaFlow	Illuzio Chroma- therapy	Warm TouchShell WTS	2 <sup>nd</sup> WTS	DOT control	Colors	UltraVelour matte finish
	CITTI®										
156	CITTI 17** 60" x 32" x 17"	•	\$2,015	\$490†	\$950	\$925	\$1,125	_	Incl.	_	\$650
158	CITTI 6032 WITH INSERT** 60" x 32" x 20"	•	\$2,590	\$490	\$950	\$925	\$1,125	_	Incl.	_	\$650
160	CITTI 6032 WITHOUT INSERT** 60" x 32" x 20"	•	\$2,315	\$490	\$950	\$925	\$1,125	_	Incl.	_	\$650
162	CITTI 6032 TRIO WITH INSERT (Integrated tile flange) $60^{\circ} \times 32^{\circ} \times 20^{\circ}$	•	\$2,560	\$490	\$950	\$925	\$1,125	_	Incl.	_	\$650
164	CITTI 6032 TRIO WITHOUT INSERT (Integrated tile flange) 60" x 32" x 20"	•	\$2,315	\$490	\$950	\$925	\$1,125	_	Incl.	_	\$650
	<b>ELEGANCIA®</b>										
166	ELEGANCIA 6636 <sup>††</sup> 66" x 36" x 21"	**	\$3,135	\$490 <sup>†</sup>	\$950°	\$925	\$1,125	\$370	Incl.	_	_
168	ELEGANCIA 6642 <sup>††</sup> 66" x 42" x 21"	**	\$3,205	\$490 <sup>†</sup>	\$950°	\$925	\$1,125	\$370	Incl.	_	_
170	ELEGANCIA 7236 <sup>††</sup> 72" x 36" x 21"	**	\$3,270	\$490 <sup>†</sup>	\$950°	\$925	\$1,125	\$370	Incl.	_	_
172	ELEGANCIA 7242 <sup>††</sup> 72" x 42" x 21"	**	\$3,420	\$490 <sup>†</sup>	\$950°	\$925	\$1,125	\$370	Incl.	_	_
	ESSENCIA®										
76	ESSENCIA 6838 (FS) 68" x 38" x 26"	•	\$7,985	\$490	\$950	\$925	\$1,125	_	Incl.	\$475	\$850
78	ESSENCIA DESIGN (FS) 72" x 36" x 24"	•	\$7,660	_	\$950	\$925	\$1,125	_	Incl.	\$475	\$850
80	ESSENCIA OVAL 7236 (FS) 72" x 36" x 27"	•	\$7,960	\$490	\$950	\$925	\$1,125	_	Incl.	_	_
174	ESSENCIA OVAL 7236 72" x 36" x 25"	•	\$4,525	\$490	\$950	\$925	\$1,125	_	Incl.	_	\$850
	ESTHESIA®										
82	ESTHESIA 6436 (FS) 64" x 36" x 25"	**	\$6,900	\$490	\$950	\$925	\$1,125	\$370	Incl.	\$835	\$1,025
176	ESTHESIA 6638 66" x 38" x 21"	**	\$2,975	\$490	\$950	\$925	\$1,125	\$370	Incl.	_	\$650
	<b>EVANESCENCE</b> ®										
84	EVANESCENCE 5936 (FS) 59" x 36" x 28"	•	\$6,735	_	\$950	\$925	\$1,125	_	Incl.	\$475	\$850
86	EVANESCENCE 6634 (FS) 66" x 34" x 28"	**	\$7,800	_	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
88	EVANESCENCE OVAL 6636 (FS) 66" x 36" x 28"	**	\$7,800	_	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
90	EVANESCENCE OVAL 7440 (FS) 74" × 40" × 28"	**	\$8,205	_	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850

Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

† When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.

†† All contours are available at the same price.

†† All contours are available at the same price.

\* Available with or without integrated tile flange.

\*\* Integrated tile flange & skirt.

† The MiaPlus® Control is included when purchasing this option.

When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.

						THERAPIES (+)			CONTROL (+)	OPTIO	ONS (+)
Page			TUB	Aroma- Cloud®	AromaFlow	Illuzio Chroma- therapy	Warm TouchShell WTS	2 <sup>nd</sup> WTS	DOT control	Colors	UltraVelour matte finish
	INUA® (Slim or standard deck)										
178	INUA 6036# 60" x 36" x 23"	•	\$4,930	\$490	\$950	\$925	\$1,125	_	Incl.	_	\$650
180	INUA 6636# 66" x 36" x 23"	•	\$4,955	\$490	\$950	\$925	\$1,125	_	Incl.	_	\$650
182	INUA 7240# 72" x 40" x 23"	**	\$5,470	\$490	\$950	\$925	\$1,125	\$370	Incl.	_	\$650
	LIBRA										
92	LIBRA 6632 (FS) 66" x 32" x 23"	**	\$6,500	_	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
94	LIBRA AURORA 6634 (FS) 66" x 34" x 24" new	**	\$6,980	_	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
96	LIBRA OVAL 6635 (FS) 66" x 35" x 27"	**	\$7,340	_	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$1,025
98	LIBRA STELLA 7038 (FS) 70" x 38" x 25" NEW	**	\$7,440	_	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$1,025
	MERIDIAN®										
184	ELLIPSE 6636 Flat or rolled deck 66" x 36" x 21"	**	\$2,690	\$490	\$950	\$925	\$1,125	\$370	Incl.	_	_
186	ELLIPSE 7240 Flat or rolled deck 72" x 40" x 21"	**	\$2,970	\$490	\$950	\$925	\$1,125	\$370	Incl.	_	_
188	MERIDIAN UNO** 60"×31"×21"	•	\$2,260	\$490 <sup>†</sup>	\$950	\$925	\$1,125	_	Incl.	_	_
190	MERIDIAN DUO** 60" x 31" x 21"	•	\$2,260	\$490†	\$950	\$925	\$1,125	_	Incl.	_	_
192	MERIDIAN 6030* 60" x 30" x 21"	•	\$1,875	\$490†	\$950	\$925	\$1,125	_	Incl.	_	_
194	MERIDIAN 6032* 60" x 32" x 21"	•	\$1,900	\$490†	\$950	\$925	\$1,125	_	Incl.	_	_
196	MERIDIAN 50 60" x 36" x 20"	•	\$2,190	\$490†	\$950	\$925	\$1,125	_	Incl.	_	_
198	MERIDIAN 6042 60" x 42" x 21"	•	\$2,680	\$490 <sup>†</sup>	\$950	\$925	\$1,125	_	Incl.	_	_
200	MERIDIAN 55 66" x 36" x 20"	**	\$2,775	\$490 <sup>†</sup>	\$950	\$925	\$1,125	\$370	Incl.	_	_
202	MERIDIAN 60 72" x 36" x 21"	**	\$2,990	\$490†	\$950	\$925	\$1,125	\$370	Incl.	_	_
204	PRO-MERIDIAN 55 66" x 34" x 20"	•	\$2,780	\$490†	\$950	\$925	\$1,125	_	Incl.	_	_
206	PRO-MERIDIAN 60 72" x 36" x 20"	Ť	\$3,000	\$490†	\$950	\$925	\$1,125	_	Incl.	_	_

Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

† When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.

†† All contours

†† Optional deck color Black, Crystal Rock, and Copper.

# Slim deck available at same price.

\* Available wi

\* The MiaPlus® Control is included when purchasing this option. †† All contours are available at the same price.

\* Available with or without integrated tile flange.

<sup>♦</sup> When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.

						THERAPIES (+)			CONTROL (+)	OPTI	ONS (+)
Dago			TUB	Aroma- Cloud®	AromaFlow	Illuzio Chroma-	Warm TouchShell	2 <sup>nd</sup> WTS	DOT control	Colors	UltraVelour matte
Page	MONARCH					therapy	WTS				finish
208	MONARCH 6032 Standard or Grand Luxury 60" x 32" x 20"	•	s <b>\$3,595</b> GL <b>\$7,185</b>	_	\$950	\$925	\$1,125	_	Incl.	_	\$650
210	MONARCH 6036 Standard or Grand Luxury 60" x 36" x 20"	•	S <b>\$3,740</b> GL <b>\$7,470</b>	_	\$950	\$925	\$1,125	_	Incl.	_	\$650
212	MONARCH 6636 Standard or Grand Luxury 66" x 36" x 20"	**	s <b>\$3,840</b> GL <b>\$7,960</b>	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$650
214	MONARCH 6638F Standard or Grand Luxury 66" x 38" x 20"	**	s <b>\$3,940</b> GL <b>\$7,890</b>	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$650
216	MONARCH 7236 Standard or Grand Luxury 72" x 36" x 21"	**	s <b>\$4,100</b> GL <b>\$8,385</b>	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$650
218	MONARCH 7238F Standard or Grand Luxury 72" x 38" x 21"	**	s <b>\$4,165</b> GL <b>\$8,480</b>	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$650
220	MONARCH 7240 Standard or Grand Luxury 72" x 40" x 21"	**	s <b>\$4,230</b> GL <b>\$8,745</b>	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$650
	NOKORI®										
100	NOKORI 6331 (FS) 63" x 31" x 24"	•	\$7,840	_	\$950	\$925	\$1,125	_	Incl.	_	\$850
102	NOKORI 6429 (FS) 64" x 29" x 23"	•	\$7,445	_	\$950	\$925	\$1,125	_	Incl.	_	\$850
104	NOKORI OVAL 6737 (FS) 67" × 37" × 24"	**	\$7,445	_	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
106	NOKORI 6935 (FS) 69" x 35" x 24"	**	\$8,255	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$850
108	NOKORI 7131 (FS) 71" × 31" × 24"	**	\$8,015	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$850
	OPALIA®										
110	OPALIA 6839 CENTERED ELLIPSE (FS) 68" x 39" x 25"	**	\$6,220	\$490	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
112	OPALIA 6839 OFF-CENTERED ELLIPSE - LEFT (FS) 68" x 39" x 25"	**	\$6,220	\$490	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
114	OPALIA 6839 OFF-CENTERED ELLIPSE - RIGHT (FS) 68" x 39" x 25"	**	\$6,220	\$490	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
116	OPALIA 6839 OBLIQUE ELLIPSE - LEFT (FS) 68" x 39" x 25"	**	\$6,220	\$490	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
118	OPALIA 6839 OBLIQUE ELLIPSE - RIGHT (FS) 68" x 39" x 25"	**	\$6,220	\$490	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850

Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

† When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.

††† Optional deck color Black, Crystal Rock, and Copper. # Slim deck available at same price. †† All contours are available at the same price.

\* Available with or without integrated tile flange.

<sup>\*\*</sup> Integrated tile flange & skirt. ‡ The MiaPlus® Control is included when purchasing this option. ♦ When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.

						THERAPIES (+)			CONTROL (+)	OPTIO	ONS (+)
Page			TUB	Aroma- Cloud®	AromaFlow	Illuzio Chroma- therapy	Warm TouchShell WTS	2 <sup>nd</sup> WTS	DOT control	Colors	UltraVelour matte finish
	ORIGAMI®										
222	ORIGAMI 6030 (2" deck height only) Original Series 60" x 30" x 21"	•	\$3,025	\$490 <sup>†</sup>	\$950	\$925	\$1,125	_	Incl.	_	\$650
224	ORIGAMI 6032# Original Series 60" x 32" x 21"	•	\$3,090	\$490 <sup>†</sup>	\$950	\$925	\$1,125	_	Incl.	_	\$650
226	ORIGAMI 6632# Original Series 66" x 32" x 21"	•	\$3,340	\$490 <sup>†</sup>	\$950	\$925	\$1,125	_	Incl.	_	\$650
228	ORIGAMI 6636# Original Series 66" x 36" x 22"	•	\$3,370	\$490 <sup>†</sup>	\$950	\$925	\$1,125	_	Incl.	_	\$650
230	ORIGAMI 7236# Original Series 72" x 36" x 22"	**	\$3,635	\$490 <sup>†</sup>	\$950	\$925	\$1,125	\$370	Incl.	_	\$650
232	ORIGAMI 7242# Original Series 72" x 42" x 22"	**	\$3,890	\$490 <sup>†</sup>	\$950	\$925	\$1,125	\$370	Incl.	_	\$650
	SCALA										
120	SCALA 6638 (FS) 66" x 38" x 25"	**	\$8,750	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$850
122	SCALA 7242 (FS) 72" x 42" x 25"	**	\$9,050	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$850
	THALASSA										
234	<b>SENSATION</b> 54" × 54" × 20"	**	\$2,380	\$490	\$950	\$925	\$1,125	\$370	Incl.	_	_
	VIBE®										
124	VIBE 5828 (FS) 58" x 28" x 21"	•	\$6,430	_	\$950	\$925	\$1,125	_	Incl.	\$475	\$850
126	VIBE BACK TO WALL 5828 (FS) 58" x 28" x 21"	•	\$6,705	_	\$950	\$925	\$1,125	_	Incl.	\$475	\$850
128	VIBE OVAL 5830 (FS) 58" x 30" x 21"	•	\$6,430	_	\$950	\$925	\$1,125	_	Incl.	\$475	\$850
236	VIBE 6030 (Integrated tile flange) 60" x 30" x 19"	•	\$2,435	_	\$950	\$925	\$1,125	_	Incl.	_	\$650
130	VIBE DESIGN 6033 (FS) 60" x 33" x 21"	*	\$6,430	_	\$950	\$925	\$1,125	_	Incl.	\$475	\$850

#### Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

- † When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.
  †† All contours are available at the same price.
  †† Optional deck color Black, Crystal Rock, and Copper.

  # Slim deck available at same price.

  \* Available with or without integrated tile flange.

  \* Integrated tile flange & skirt.

  † The MiaPlus® Control is included when purchasing this option.

### THERMOMASSEUR® (TMU) – SUMMARY PRICE LIST

#### **BY SIZE**

					THERAPIES (+)					CONTR		-)	OPTIC	)NS (+)
Page			Thermo- Masseur TMU	Aroma- Cloud®	Aroma- Flow	Illuzio Chroma- therapy	Heated Backrest	2 <sup>nd</sup> Heated Backrest	Heated Headrest	Mia®	MiaPlus®	BU- Touch App <sup>‡‡</sup>	Colors	Ultra- Velour matte finish
	4639 FREESTANDING													
68	BEONE 4639 (FS) 46" × 39" × 30"	•	\$9,360	_	_	\$925	Incl.	_	_	_	Incl.	Incl.	\$475	\$850
	5736 FREESTANDING													
70	CHARISM 5736 (FS) 57" x 36" x 23"	•	\$9,655	_	\$950	\$925	Incl.	_	_	_	Incl.	Incl.	\$250***	\$850
	5828 FREESTANDING													
124	VIBE 5828 (FS) 58" x 28" x 21"	•	\$8,655	_	\$950	\$925	Incl.	_	_	_	Incl.	\$430	\$475	\$850
126	VIBE BACK TO WALL 5828 (FS) 58" x 28" x 21"	•	\$9,155	_	\$950	\$925	Incl.	_	_	_	Incl.	\$430	\$475	\$850
	5830 FREESTANDING													
128	VIBE OVAL 5830 (FS) 58" x 30" x 21"	•	\$8,655	_	\$950	\$925	Incl.	_	_	_	Incl.	\$430	\$475	\$850
	5936 FREESTANDING													
84	EVANESCENCE 5936 (FS) 59" x 36" x 28"	•	\$9,325	_	\$950	\$925	Incl.	_	Incl.	_	Incl.	Incl.	\$475	\$850
	6033 FREESTANDING													
130	VIBE DESIGN 6033 (FS) 60" x 33" x 21"	•	\$8,655	_	\$950	\$925	Incl.	_	_	_	Incl.	\$430	\$475	\$850
	6331 FREESTANDING													
100	NOKORI 6331 (FS) 63" x 31" x 24"	•	\$10,160	_	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$850
	6429 FREESTANDING													
102	NOKORI 6429 (FS) 64" x 29" x 23"	•	\$9,790	_	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$850
	6434 FREESTANDING													
72	CHARISM 6434 (FS) 64" x 34" x 24"	**	\$11,000	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	\$250†††	\$850
46	OPUS 6434 (FS) 64" x 34" x 25" NEW TMU	**	\$11,750	_	_	_	Incl.	_	_	_	Incl.	Incl.	_	_
	6436 FREESTANDING			ı										
74	CHARISM OVAL 6436 (FS) 64" x 36" x 24"	**	\$11,000	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	\$250†††	\$850
82	ESTHESIA 6436 (FS) 64" x 36" x 25"	**	\$9,510	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	\$835	\$1,025
	6632 FREESTANDING													
92	LIBRA 6632 (FS) 66" x 32" x 23"	**	\$8,850	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	\$475	\$850
	6634 FREESTANDING													
86	EVANESCENCE 6634 (FS) 66" x 34" x 28"	**	\$10,420	_	\$950	\$925	Incl.	\$1,125	Incl.	_	Incl.	Incl.	\$475	\$850
94	LIBRA AURORA 6634 (FS) 66" x 34" x 24"	**	\$9,330	_	\$950	\$925	Incl.	\$1,125	Incl.	_	Incl.	Incl.	\$475	\$850

Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

† When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.

†† All contours are available at the same price.

†† All contours are available at the same price.

\* Available with or without integrated tile flange.

\* Available with or without integrated tile flange.

† The MiaPlus® Control is included when purchasing this option.

Made with FineStone®

When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.

### THERMOMASSEUR® (TMU) - SUMMARY PRICE LIST

				THERAF			APIES (+)			CONTROLS (+)		)	OPTIONS (+)	
Page			Thermo- Masseur TMU	Aroma- Cloud®	Aroma- Flow	Illuzio Chroma- therapy	Heated Backrest	2 <sup>nd</sup> Heated Backrest	Heated Headrest	Mia®	MiaPlus®	BU- Touch App <sup>‡‡</sup>	Colors	Ultra- Velour matte finish
	6635 FREESTANDING													
96	LIBRA OVAL 6635 (FS) 66" x 35" x 27"	**	\$9,750	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	\$475	\$1,025
	6636 FREESTANDING													
56	CELLA 6636 (FS) 66" x 36" x 27"	**	\$10,145	\$490	_	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	_	_
60	NAOS 6636 (FS) 66" × 36" × 25"	**	\$11,240	\$490	_	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	_	_
64	SANOS 6636 (FS) 66" x 36" x 24"	**	\$9,880	\$490	_	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	_	_
88	EVANESCENCE OVAL 6636 (FS) 66" x 36" x 28"	**	\$10,420	_	\$950	\$925	Incl.	\$1,125	Incl.	_	Incl.	Incl.	\$475	\$850
	6638 FREESTANDING													
120	SCALA 6638 (FS) 66" x 38" x 25"	**	\$10,875	_	\$950	\$925	Incl.	\$1,125	Incl.	_	Incl.	Incl.	_	\$850
	6737 FREESTANDING													
104	NOKORI OVAL 6737 (FS) 67" × 37" × 24"	**	\$10,380	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	\$475	\$850
	6838 FREESTANDING													
76	ESSENCIA 6838 (FS) 68" x 38" x 26"	•	\$11,035	\$490	\$950	\$925	Incl.	_	Incl.	_	Incl.	Incl.	\$475	\$850
	6839 FREESTANDING													
110	OPALIA 6839 CENTERED ELLIPSE (FS) 68" x 39" x 25"	**	\$8,815	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	\$475	\$850
112	OPALIA 6839 OFF-CENTERED ELLIPSE - LEFT (FS) 68" x 39" x 25"	**	\$8,815	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	\$475	\$850
114	OPALIA 6839 OFF-CENTERED ELLIPSE - RIGHT (FS) 68" x 39" x 25"	**	\$8,815	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	\$475	\$850
116	OPALIA 6839 OBLIQUE ELLIPSE - LEFT (FS) 68" x 39" x 25"	**	\$8,815	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	\$475	\$850
118	OPALIA 6839 OBLIQUE ELLIPSE - RIGHT (FS) 68" x 39" x 25"	**	\$8,815	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	\$475	\$850
	6935 FREESTANDING													
106	NOKORI 6935 (FS) 69" x 35" x 24"	**	\$10,620	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$850
	7038 FREESTANDING													
98	LIBRA STELLA 7038 (FS) 70" x 38" x 25" <b>NEW</b>	**	\$9,910	_	\$950	\$925	Incl.	\$1,125	Incl.	_	Incl.	Incl.	\$475	\$1,025

Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

† When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.

†† Optional deck color Black, Crystal Rock, and Copper. # Slim deck available at same price.

\*\* Integrated tile flange & skirt. ‡ The MiaPlus® Control is included when processing the state of the flange.

<sup>††</sup> All contours are available at the same price.

<sup>#</sup> Slim deck available at same price. \* Available w

† The MiaPlus® Control is included when purchasing this option.

<sup>##</sup> The BU-Touch Application is available with the purchase of a ThermoMasseur bath with Mia® or MiaPlus® Control.

 $<sup>{\</sup>color{blue} \Diamond} \quad \text{When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.}$ 

				THERAPIES (+)							CONTROLS (+)			OPTIONS (+)	
Page			Thermo- Masseur TMU	Aroma- Cloud®	Aroma- Flow	Illuzio Chroma- therapy	Heated Backrest	2 <sup>nd</sup> Heated Backrest	Heated Headrest	Mia®	MiaPlus®	BU- Touch App <sup>‡‡</sup>	Colors	Ultra- Velour matte finish	
	7131 FREESTANDING														
108	NOKORI 7131 (FS) 71" × 31" × 24"	**	\$10,485	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$850	
	7236 FREESTANDING														
78	ESSENCIA DESIGN (FS) 72" x 36" x 24"	•	\$10,535	_	\$950	\$925	Incl.	_	_	_	Incl.	Incl.	\$475	\$850	
80	ESSENCIA OVAL 7236 (FS) 72" × 36" × 27"	•	\$10,995	\$490	\$950	\$925	Incl.	_	Incl.	_	Incl.	Incl.	_	_	
	7240 FREESTANDING														
58	CELLA 7240 (FS) 72" × 40" × 27"	**	\$11,100	\$490	_	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	_	_	
62	NAOS 7240 (FS) 72" × 40" × 25"	**	\$12,055	\$490	_	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	_	_	
66	SANOS 7240 (FS) 72" × 40" × 24"	**	\$10,560	\$490	_	\$925	Incl.	\$1,125	_	_	Incl.	Incl.	_	_	
	7242 FREESTANDING														
52	AMMA OVAL 7242 (FS) Narrow base, raised or flat deck 72" x 42" x 24"	**	\$11,255	\$490	\$950°	\$925	Incl.	Incl.	Incl.	_	Incl.	\$430	_	_	
54	AMMA OVAL 7242 (FS) Raised or flat deck 72" x 42" x 28"	**	\$12,645	\$490	\$950°	\$925	Incl.	Incl.	Incl.	_	Incl.	\$430	_	_	
122	SCALA 7242 (FS) 72" × 42" × 25"	**	\$11,750	_	\$950	\$925	Incl.	\$1,125	Incl.	_	Incl.	Incl.	_	\$850	
	7440 FREESTANDING														
90	EVANESCENCE OVAL 7440 (FS) $74" \times 40" \times 28"$	**	\$10,685	_	\$950	\$925	Incl.	\$1,125	Incl.	_	Incl.	Incl.	\$475	\$850	
	5454														
234	<b>SENSATION</b> 54" × 54" × 20"	**	\$5,100	\$490	\$950	\$925‡	Incl.	\$1,125	Incl.	Incl.	\$285	\$430	_	_	
	6030														
136	AMMA 6030 (Integrated tile flange) 60" × 30" × 21"	•	\$6,545	\$490†	\$950	\$925	Incl.	_	Incl.	_	Incl.	\$430	_	_	
152	BAIN DE VILLE 6030** 60" × 30" × 17"	•	\$3,595	\$490†	\$950	\$925‡	Incl.	_	_	Incl.	\$285	\$430	_	\$650	
192	MERIDIAN 6030* 60" x 30" x 21"	•	\$4,265	\$490†	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	_	
222	ORIGAMI 6030 (2" deck height only) Original Series 60" x 30" x 21"	•	\$5,725	\$490 <sup>†</sup>	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650	
236	VIBE 6030 (Integrated tile flange) 60" x 30" x 19"	•	\$4,895	_	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650	
	6031														
188	MERIDIAN UNO** 60" x 31" x 21"	•	\$4,265	\$490†	\$950	\$925‡	Incl.	_	_	Incl.	\$285	\$430	_	_	
190	MERIDIAN DUO** 60" x 31" x 21"	•	\$4,265	\$490†	\$950	\$925‡	Incl.	_	_	Incl.	\$285	\$430	_	_	

- Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

  † When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.

  †† All contours

  †† All contours

  †† All contours

  \* Available wi

  \*\* Integrated tile flange & skirt.

  † The MiaPlus® Control is included when purchasing this option. †† All contours are available at the same price.

  \* Available with or without integrated tile flange.
- ‡‡ The BU-Touch Application is available with the purchase of a ThermoMasseur bath with Mia® or MiaPlus® Control.
- When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.

### THERMOMASSEUR® (TMU) - SUMMARY PRICE LIST

						THERA	PIES (+)			(	CONTROLS (+	·)	OPTIC	NS (+)
Page			Thermo- Masseur TMU	Aroma- Cloud®	Aroma- Flow	Illuzio Chroma- therapy	Heated Backrest	2 <sup>nd</sup> Heated Backrest	Heated Headrest	Mia®	MiaPlus®	BU- Touch App <sup>‡‡</sup>	Colors	Ultra- Velour matte finish
	6032													
138	AMMA 6032 60" x 32" x 21"	•	\$6,545	\$490 <sup>†</sup>	\$950°	\$925	Incl.	_	Incl.	_	Incl.	\$430	_	_
156	<b>CITTI 17**</b> 60" x 32" x 17"	•	\$3,700	\$490 <sup>†</sup>	\$950	\$925 <sup>‡</sup>	Incl.	_	_	Incl.	\$285	\$430	_	\$650
158	CITTI 6032 WITH INSERT** 60" x 32" x 20"	•	\$4,935	\$490	\$950	\$925 <sup>‡</sup>	Incl.	_	_	Incl.	\$285	\$430	_	\$650
160	CITTI 6032 WITHOUT INSERT** 60" x 32" x 20"	•	\$4,670	\$490	\$950	\$925 <sup>‡</sup>	Incl.	_	_	Incl.	\$285	\$430	_	\$650
162	CITTI 6032 TRIO WITH INSERT (Integrated tile flange) 60" x 32" x 20"	•	\$4,920	\$490	\$950	\$925 <sup>‡</sup>	Incl.	_	_	Incl.	\$285	\$430	_	\$650
164	CITTI 6032 TRIO WITHOUT INSERT (Integrated tile flange) $60^{\circ} \times 32^{\circ} \times 20^{\circ}$	•	\$4,665	\$490	\$950	\$925‡	Incl.	_	_	Incl.	\$285	\$430	_	\$650
194	MERIDIAN 6032* 60" x 32" x 21"	•	\$4,885	\$490 <sup>†</sup>	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	_
208	MONARCH 6032 Standard or Grand Luxury 60" x 32" x 20"	•	S \$5,805 GL \$9,440	_	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650
224	ORIGAMI 6032# Original Series 60" x 32" x 21"	•	\$5,820	\$490 <sup>†</sup>	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650
	6036													
140	AMMA 6036 60" x 36" x 21"	•	\$7,455	\$490†	\$950°	\$925	Incl.	_	Incl.	_	Incl.	\$430	_	_
178	INUA 6036# 60" x 36" x 23"	•	\$7,930	\$490	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650
196	MERIDIAN 50 60" × 36" × 20"	•	\$5,045	\$490†	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	_
210	MONARCH 6036 Standard or Grand Luxury 60" x 36" x 20"	•	S <b>\$5,990</b> GL <b>\$9,715</b>	_	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650
	6042													
198	MERIDIAN 6042 60" x 42" x 21"	•	\$5,440	\$490 <sup>†</sup>	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	_
	6632													
154	BAIN DE VILLE 6632** 66" x 32" x 20"	•	\$5,085	\$490†	\$950	\$925‡	Incl.	_	_	Incl.	\$285	\$430	_	\$650
226	ORIGAMI 6632# Original Series 66" x 32" x 21"	•	\$6,180	\$490†	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650
	6634													
204	PRO-MERIDIAN 55 66" x 34" x 20"	•	\$5,405	\$490†	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	_

<sup>††</sup> All contours are available at the same price.

\* Available with or without integrated tile flange.

Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

† When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.

†† All contours

†† Optional deck color Black, Crystal Rock, and Copper.

# Slim deck available at same price.

\* Available wi

\*\* Integrated tile flange & skirt.

† The MiaPlus® Control is included when purchasing this option.

‡ The BU-Touch Application is available with the purchase of a ThermoMasseur bath with Mia® or MiaPlus® Control.

When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.

#### **BY SIZE**

						THERA	PIES (+)				CONTROLS (+	-)	OPTIC	)NS (+)
Page			Thermo- Masseur TMU	Aroma- Cloud®	Aroma- Flow	Illuzio Chroma- therapy	Heated Backrest	2 <sup>nd</sup> Heated Backrest	Heated Headrest	Mia®	MiaPlus®	BU- Touch App <sup>‡‡</sup>	Colors	Ultra- Velour matte finish
	6636													
142	AMMA 6636 66" x 36" x 21"	•	\$7,680	\$490†	\$950°	\$925	Incl.	_	Incl.	_	Incl.	\$430	_	_
166	ELEGANCIA 6636 <sup>††</sup> 66" x 36" x 21"	**	\$6,330	\$490†	\$950°	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	_
180	INUA 6636# 66" x 36" x 23"	•	\$7,975	\$490	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650
184	ELLIPSE 6636 Flat or rolled deck 66" x 36" x 21"	**	\$6,080	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	_
200	MERIDIAN 55 66" x 36" x 20"	**	\$5,490	\$490†	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	_
212	MONARCH 6636 Standard or Grand Luxury 66" x 36" x 20"	**	S \$6,050 GL \$10,140	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650
228	ORIGAMI 6636# Original Series 66" x 36" x 22"	•	\$6,425	\$490†	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	\$650
	6638													
144	AMMA OVAL 6638 66" x 38" x 21"	*	\$7,680	\$490	\$950°	\$925	Incl.	_	Incl.	_	Incl.	\$430	_	_
176	ESTHESIA 6638 66" x 38" x 21"	**	\$5,875	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650
214	MONARCH 6638F Standard or Grand Luxury 66" x 38" x 20"	**	S \$6,100 GL \$10,255	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650
	6642													
168	ELEGANCIA 6642 <sup>††</sup> 66" x 42" x 21"	**	\$6,455	\$490†	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	_
	7236													
146	AMMA 7236 72" x 36" x 21"	**	\$7,965	\$490†	\$950°	\$925	Incl.	Incl.	Incl.	_	Incl.	\$430	_	_
170	ELEGANCIA 7236 <sup>††</sup> 72" x 36" x 21"	**	\$6,500	\$490†	\$950°	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	_
174	ESSENCIA OVAL 7236 72" x 36" x 25"	•	\$6,425	\$490	\$950	\$925	Incl.	_	Incl.	_	Incl.	\$430	_	\$850
202	MERIDIAN 60 72" x 36" x 21"	**	\$5,600	\$490†	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	_
206	PRO-MERIDIAN 60 72" x 36" x 20"	•	\$5,770	\$490†	\$950	\$925	Incl.	_	_	_	Incl.	\$430	_	_
216	MONARCH 7236 Standard or Grand Luxury 72" x 36" x 21"	**	S <b>\$6,285</b> GL <b>\$10,600</b>	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650
230	ORIGAMI 7236# Original Series 72" x 36" x 22"	**	\$6,700	\$490 <sup>†</sup>	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650
	7238													
218	MONARCH 7238F Standard or Grand Luxury 72" x 38" x 21"	**	S <b>\$6,340</b> GL <b>\$10,705</b>	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650

#### Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

- When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.
- †† All contours are available at the same price. \* Available with or without integrated tile flange.
- # Slim deck color Black, Crystal Rock, and Copper. # Slim deck available at same price. \* Available with the purchasing this option.

  \*\* The MiaPlus® Control is included when purchasing this option.

  \*\* The BU-Touch Application is available with the purchase of a ThermoMasseur bath with Mia® or MiaPlus® Control.

  \*\* When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.

### THERMOMASSEUR® (TMU) - SUMMARY PRICE LIST

			THERAPIES (+)							CONTROLS (+	OPTIONS (+)			
Page			Thermo- Masseur TMU	Aroma- Cloud®	Aroma- Flow	Illuzio Chroma- therapy	Heated Backrest	2 <sup>nd</sup> Heated Backrest	Heated Headrest	Mia®	MiaPlus®	BU- Touch App <sup>‡‡</sup>	Colors	Ultra- Velour matte finish
	7240													
186	ELLIPSE 7240 Flat or rolled deck 72" x 40" x 21"	**	\$6,420	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	_
182	INUA 7240# 72" × 40" × 23"	**	\$8,500	\$490	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650
220	MONARCH 7240 Standard or Grand Luxury 72" x 40" x 21"	**	S <b>\$6,470</b> GL <b>\$10,955</b>	_	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650
	7242													
148	AMMA 7242 72" × 42" × 22"	**	\$8,105	\$490†	\$950°	\$925	Incl.	Incl.	Incl.	_	Incl.	\$430	_	_
150	AMMA OVAL 7242 Raised or flat deck 72" x 42" x 22"	**	\$7,965	\$490	\$950°	\$925	Incl.	Incl.	Incl.	_	Incl.	\$430	_	_
172	ELEGANCIA 7242 <sup>††</sup> 72" x 42" x 21"	**	\$6,585	\$490†	\$950°	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	_
232	ORIGAMI 7242# Original Series 72" x 42" x 22"	**	\$7,105	\$490†	\$950	\$925	Incl.	\$1,125	_	_	Incl.	\$430	_	\$650

- †† All contours are available at the same price.

  \* Available with or without integrated tile flange.
- Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

  † When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.

  †† All contours

  †† Optional deck color Black, Crystal Rock, and Copper.

  # Slim deck available at same price.

  \* Available wi

  \*\* Integrated tile flange & skirt.

  † The MiaPlus® Control is included when purchasing this option.

  ‡ The BU-Touch Application is available with the purchase of a ThermoMasseur bath with Mia® or MiaPlus® Control.
- ♦ When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.

#### **BY SIZE**

						THERAPIES (+)			CONTROL (+)	OPTI	ONS (+)
Page			TUB	Aroma- Cloud®	AromaFlow	Illuzio Chroma- therapy	Warm TouchShell WTS	2 <sup>nd</sup> WTS	DOT control	Colors	UltraVelour matte finish
	4639 FREESTANDING										
68	BEONE 4639 (FS) 46" x 39" x 30"	•	\$7,280	_	_	\$925	\$1,125	_	Incl.	\$475	\$850
	5736 FREESTANDING										
70	CHARISM 5736 (FS) 57" x 36" x 23"	•	\$7,050	_	\$950	\$925	\$1,125	_	Incl.	\$250†††	\$850
	5828 FREESTANDING										
124	VIBE 5828 (FS) 58" x 28" x 21"	•	\$6,430	_	\$950	\$925	\$1,125	_	Incl.	\$475	\$850
126	VIBE BACK TO WALL 5828 (FS) 58" x 28" x 21"	•	\$6,705	_	\$950	\$925	\$1,125	_	Incl.	\$475	\$850
	5830 FREESTANDING										
128	VIBE OVAL 5830 (FS) 58" x 30" x 21"	•	\$6,430	_	\$950	\$925	\$1,125	_	Incl.	\$475	\$850
	5936 FREESTANDING										
84	EVANESCENCE 5936 (FS) 59" x 36" x 28"	•	\$6,735	_	\$950	\$925	\$1,125	_	Incl.	\$475	\$850
	6033 FREESTANDING										
130	VIBE DESIGN 6033 (FS) 60" x 33" x 21"	•	\$6,430	_	\$950	\$925	\$1,125	_	Incl.	\$475	\$850
	6233 FREESTANDING										
42	CELESTIA 6233 (FS) 62" x 33" x 24"	•	\$8,000	_	_	_	_	_	_	_	_
	6331 FREESTANDING										
100	NOKORI 6331 (FS) 63" x 31" x 24"	•	\$7,840	_	\$950	\$925	\$1,125	_	Incl.	_	\$850
	6429 FREESTANDING										
102	NOKORI 6429 (FS) 64" x 29" x 23"	•	\$7,445	_	\$950	\$925	\$1,125	_	Incl.	_	\$850
	6434 FREESTANDING										
72	CHARISM 6434 (FS) 64" x 34" x 24"	**	\$8,525	_	\$950	\$925	\$1,125	\$370	Incl.	\$250†††	\$850
46	OPUS 6434 (FS) 64" x 34" x 25" NEW TMU	**	\$8,900	_	_	_	_	_	_	_	_
	6436 FREESTANDING										
74	CHARISM OVAL 6436 (FS) 64" x 36" x 24"	**	\$8,525	_	\$950	\$925	\$1,125	\$370	Incl.	\$250†††	\$850
82	ESTHESIA 6436 (FS) 64" x 36" x 25"	**	\$6,900	\$490	\$950	\$925	\$1,125	\$370	Incl.	\$695	\$1,025
	6632 FREESTANDING										
92	LIBRA 6632 (FS) 66" x 32" x 23"	**	\$6,500	_	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
	6634 FREESTANDING										
86	EVANESCENCE 6634 (FS) 66" x 34" x 28"	**	\$7,800	_	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
94	LIBRA AURORA 6634 (FS) 66" x 34" x 24" new	**	\$6,980	_	\$950	\$925	\$1,125	\$360	Incl.	\$475	\$850

- Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

  † When tilling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.
  †† All contours are available at the same price.
  †† All contours are available at the same price.
  †† All contours are available at the same price.
  †† Available with or without integrated tile flange.
  †† All contours are available at the same price.
  †\* Available with or without integrated tile flange.
  †† When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.

Made with FineStone®

#### **BY SIZE**

					THERAPIES (+)		CONTROL (+) OPTIONS (+)				
Page			TUB	Aroma- Cloud®	AromaFlow	Illuzio Chroma- therapy	Warm TouchShell WTS	2 <sup>nd</sup> WTS	DOT control	Colors	UltraVelour matte finish
	6635 FREESTANDING										
44	CELESTIA 6635 (FS) 66" x 35" x 25"	**	\$8,600	_	_	_	_	_	_	_	_
96	LIBRA OVAL 6635 (FS) 66" x 35" x 27"	**	\$7,340	_	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$1,025
	6636 FREESTANDING										
56	CELLA 6636 (FS) 66" x 36" x 27"	**	\$7,260	\$490	_	\$925	\$1,125	\$370	Incl.	_	_
60	NAOS 6636 (FS) 66" x 36" x 25"	**	\$8,195	\$490	_	\$925	\$1,125	\$370	Incl.	_	_
64	SANOS 6636 (FS) 66" x 36" x 24"	**	\$7,230	\$490	_	\$925	\$1,125	\$370	Incl.	_	_
88	EVANESCENCE OVAL 6636 (FS) 66" x 36" x 28"	**	\$7,800	_	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
	6638 FREESTANDING										
120	SCALA 6638 (FS) 66" × 38" × 25"	**	\$8,750	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$850
	6737 FREESTANDING										
104	NOKORI OVAL 6737 (FS) 67" × 37" × 24"	**	\$7,445	_	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
	6838 FREESTANDING										
76	ESSENCIA 6838 (FS) 68" x 38" x 26"	•	\$7,985	\$490	\$950	\$925	\$1,125	_	Incl.	\$475	\$850
	6839 FREESTANDING										
110	OPALIA 6839 CENTERED ELLIPSE (FS) 68" x 39" x 25"	**	\$6,220	\$490	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
112	OPALIA 6839 OFF-CENTERED ELLIPSE - LEFT (FS) 68" x 39" x 25"	**	\$6,220	\$490	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
114	OPALIA 6839 OFF-CENTERED ELLIPSE - RIGHT (FS) 68" x 39" x 25"	**	\$6,220	\$490	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
116	OPALIA 6839 OBLIQUE ELLIPSE - LEFT (FS) 68" x 39" x 25"	**	\$6,220	\$490	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
118	OPALIA 6839 OBLIQUE ELLIPSE - RIGHT (FS) 68" x 39" x 25"	**	\$6,220	\$490	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
	6935 FREESTANDING										
106	NOKORI 6935 (FS) 69" x 35" x 24"	**	\$8,255	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$850
	7038 FREESTANDING										
98	LIBRA STELLA 7038 (FS) 70" × 38" × 25" <b>NEW</b>	**	\$7,440	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$1,025
	7131 FREESTANDING										
108	NOKORI 7131 (FS) 71" x 31" x 24"	**	\$8,015	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$850

Made with FineStone®



Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

† When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.

†† Optional deck color Black, Crystal Rock, and Copper. # Slim deck available at same price.

\*\* Integrated tile flange & skirt. ‡ The MiaPlus® Control is included when processed in the processed of the flange.

<sup>††</sup> All contours are available at the same price. \* Available with or without integrated tile flange.

<sup>#</sup> Slim deck available at same price. \* Available w ‡ The MiaPlus® Control is included when purchasing this option.

 $<sup>\</sup>diamond \quad \text{When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.}$ 

						THERAPIES (+)			CONTROL (+)	OPTI	ONS (+)
Page			TUB	Aroma- Cloud®	AromaFlow	Illuzio Chroma- therapy	Warm TouchShell WTS	2 <sup>nd</sup> WTS	DOT control	Colors	UltraVelour matte finish
	7236 FREESTANDING										
78	ESSENCIA DESIGN (FS) 72" x 36" x 24"	•	\$7,660	_	\$950	\$925	\$1,125	_	Incl.	\$475	\$850
80	ESSENCIA OVAL 7236 (FS) 72" × 36" × 27"	•	\$7,960	\$490	\$950	\$925	\$1,125	_	Incl.	_	_
	7240 FREESTANDING										
58	CELLA 7240 (FS) 72" × 40" × 27"	**	\$8,485	\$490	_	\$925	\$1,125	\$370	Incl.	_	_
62	NAOS 7240 (FS) 72" × 40" × 25"	**	\$9,040	\$490	_	\$925	\$1,125	\$370	Incl.	_	_
66	SANOS 7240 (FS) 72" × 40" × 24"	**	\$7,925	\$490	_	\$925	\$1,125	\$370	Incl.	_	_
	7242 FREESTANDING										
52	AMMA OVAL 7242 (FS) Narrow base, raised or flat deck 72" x 42" x 24"	**	\$8,780	\$490	\$950°	\$925	\$1,125	\$370	Incl.	_	_
54	AMMA OVAL 7242 (FS) Raised or flat deck 72" x 42" x 28"	**	\$9,725	\$490	\$950°	\$925	\$1,125	\$370	Incl.	_	_
122	SCALA 7242 (FS) 72" × 42" × 25"	**	\$9,050	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$850
	7440 FREESTANDING										
90	EVANESCENCE OVAL 7440 (FS) 74" × 40" × 28"	**	\$8,205	_	\$950	\$925	\$1,125	\$370	Incl.	\$475	\$850
	5454										
234	SENSATION 54" x 54" x 20"	**	\$2,380	\$490	\$950	\$925	\$1,125	\$370	Incl.	_	_
	6030										
136	AMMA 6030 (Integrated tile flange) 60" x 30" x 21"	•	\$4,055	\$490†	\$950°	\$925	\$1,125	_	Incl.	_	_
152	BAIN DE VILLE 6030** 60" × 30" × 17"	•	\$1,930	\$490 <sup>†</sup>	\$950	\$925	\$1,125	_	Incl.	_	\$650
192	MERIDIAN 6030* 60" x 30" x 21"	•	\$1,875	\$490 <sup>†</sup>	\$950	\$925	\$1,125	_	Incl.	_	_
222	ORIGAMI 6030 (2" deck height only) Original Series 60" x 30" x 21"	•	\$3,025	\$490†	\$950	\$925	\$1,125	_	Incl.	_	\$650
236	VIBE 6030 (Integrated tile flange) 60" × 30" × 19"	•	\$2,435	_	\$950	\$925	\$1,125	_	Incl.	_	\$650
	6031										
188	MERIDIAN UNO** 60" x 31" x 21"	•	\$2,260	\$490†	\$950	\$925	\$1,125	_	Incl.	_	_
190	MERIDIAN DUO** 60" x 31" x 21"	•	\$2,260	\$490†	\$950	\$925	\$1,125	_	Incl.	_	_

Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

† When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.

††† Optional deck color Black, Crystal Rock, and Copper. # Slim deck available at same price.

<sup>††</sup> All contours are available at the same price. \* Available with or without integrated tile flange.

<sup>‡</sup> The MiaPlus® Control is included when purchasing this option. \*\* Integrated tile flange & skirt.

<sup>♦</sup> When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.

Tub	ONS (+)	OPTIC	CONTROL (+)			THERAPIES (+)						
38   AMMA 6032	UltraVelour matte finish	Colors		2 <sup>nd</sup> WTS	TouchShell	Chroma-	AromaFlow		TUB			Page
Section   Sec											6032	
Section   Sect	_	_	Incl.	_	\$1,125	\$925	\$950°	\$490†	\$4,055	•		138
160   CITTI 6032 WITHOUT INSERT**	\$650	_	Incl.	_	\$1,125	\$925	\$950	\$490†	\$2,015	•		156
September   Sept	\$650	_	Incl.	_	\$1,125	\$925	\$950	\$490	\$2,590	•		158
(integrated tile flange)	\$650	_	Incl.	_	\$1,125	\$925	\$950	\$490	\$2,315	•		160
INSERT (Integrated tile flange)	\$650	_	Incl.	_	\$1,125	\$925	\$950	\$490	\$2,560	•	(Integrated tile flange)	162
Solution	\$650	_	Incl.	_	\$1,125	\$925	\$950	\$490	\$2,315	•	INSERT (Integrated tile flange)	164
Standard or Grand Luxury 60" x 32" x 20"  QRIGAMI 6032# Original Series 60" x 32" x 21"  \$3,090  \$490! \$950  \$925  \$1,125  — Incl. —  6036  140  AMMA 6036 60" x 36" x 21"  \$100  AMMA 6036 60" x 36" x 21"  \$100  \$490! \$950  \$925  \$1,125  — Incl. —  6036  140  AMMA 6036 60" x 36" x 21"  \$100  AMMA 6036 60" x 36" x 21"  \$100  \$100  AERIDIAN 50 60" x 36" x 20"  \$100	_	_	Incl.	_	\$1,125	\$925	\$950	\$490†	\$1,900	•		194
Sample	\$650	_	Incl.	_	\$1,125	\$925	\$950	_		•	Standard or Grand Luxury	208
AMMA 6036 60" x 36" x 21"	\$650	_	Incl.	_	\$1,125	\$925	\$950	\$490†	\$3,090	•	Original Series	224
60" x 36" x 21"    178   INUA 6036#											6036	
60" x 36" x 23"    MERIDIAN 50	_	_	Incl.	_	\$1,125	\$925	\$950°	\$490 <sup>†</sup>	\$4,685	•		140
60" x 36" x 20"  MONARCH 6036 Standard or Grand Luxury 60" x 36" x 20"  MERIDIAN 6042 60" x 42" x 21"  MERIDIAN 6042 60" x 42" x 21"  MERIDIAN 6632*  BAIN DE VILLE 6632**  66" x 32" x 20"  \$490†  \$950  \$925  \$1,125  — Incl. —  Incl. —  CORIGAMI 6632#	\$650	_	Incl.	_	\$1,125	\$925	\$950	\$490	\$4,930	•		178
Standard or Grand Luxury 60" x 36" x 20"  6042  198 MERIDIAN 6042 60" x 42" x 21"  \$2,680 \$490† \$950 \$925 \$1,125 — Incl. —  6632  154 BAIN DE VILLE 6632** 66" x 32" x 20"  \$2,760 \$490† \$950 \$925 \$1,125 — Incl. —	_	_	Incl.	_	\$1,125	\$925	\$950	\$490 <sup>†</sup>	\$2,190	•		196
MERIDIAN 6042 60" x 42" x 21"  \$2,680 \$490† \$950 \$925 \$1,125 — Incl. —  6632  154 BAIN DE VILLE 6632** 66" x 32" x 20"  \$2,760 \$490† \$950 \$925 \$1,125 — Incl. —	\$650	_	Incl.	_	\$1,125	\$925	\$950	_		•	Standard or Grand Luxury	210
60" x 42" x 21"											6042	
BAIN DE VILLE 6632**  \$ \$2,760 \$490† \$950 \$925 \$1,125 — Incl. —	_	_	Incl.	_	\$1,125	\$925	\$950	\$490 <sup>†</sup>	\$2,680	•		198
66" x 32" x 20" \$490" \$950 \$925 \$1,125 — IIId. —											6632	
226 ORIGAMI 6632#	\$650	_	Incl.	_	\$1,125	\$925	\$950	\$490 <sup>†</sup>	\$2,760	•		154
Original Series \$ \$3,340 \$490° \$950 \$925 \$1,125 — Incl. — 66" x 32" x 21"	\$650	_	Incl.	_	\$1,125	\$925	\$950	\$490 <sup>†</sup>	\$3,340	•	Original Series	226
6634											6634	
PRO-MERIDIAN 55 66" x 34" x 20"  \$2,780 \$490 <sup>†</sup> \$950 \$925 \$1,125 — Incl. —	_	_	Incl.	_	\$1,125	\$925	\$950	\$490 <sup>†</sup>	\$2,780	•		204

Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

† When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.

††† Optional deck color Black, Crystal Rock, and Copper. # Slim deck available at same price.

\*\* Integrated tile flange & skirt. ‡ The MiaPlus® Control is included when processed in the flange of the flange will be a same price.

<sup>††</sup> All contours are available at the same price.

\* Available with or without integrated tile flange.

<sup>‡</sup> The MiaPlus® Control is included when purchasing this option.

<sup>♦</sup> When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.

						THERAPIES (+)			CONTROL (+)	OPTI	ONS (+)
Page			TUB	Aroma- Cloud®	AromaFlow	Illuzio Chroma- therapy	Warm TouchShell WTS	2 <sup>nd</sup> WTS	DOT control	Colors	UltraVelour matte finish
	6636										
142	AMMA 6636 66" x 36" x 21"	•	\$4,790	\$490†	\$950°	\$925	\$1,125	_	Incl.	_	_
166	ELEGANCIA 6636 <sup>††</sup> 66"×36"×21"	**	\$3,135	\$490 <sup>†</sup>	\$950°	\$925	\$1,125	\$370	Incl.	_	_
180	INUA 6636# 66" x 36" x 23"	•	\$4,955	\$490	\$950	\$925	\$1,125	_	Incl.	_	\$650
184	ELLIPSE 6636 Flat or rolled deck 66" x 36" x 21"	**	\$2,690	\$490	\$950	\$925	\$1,125	\$370	Incl.	_	_
200	MERIDIAN 55 66" x 36" x 20"	**	\$2,775	\$490†	\$950	\$925	\$1,125	\$370	Incl.	_	_
212	MONARCH 6636 Standard or Grand Luxury 66" x 36" x 20"	**	S <b>\$3,840</b> GL <b>\$7,960</b>	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$650
228	ORIGAMI 6636# Original Series 66" x 36" x 22"	•	\$3,370	\$490†	\$950	\$925	\$1,125	_	Incl.	_	\$650
	6638										
144	AMMA OVAL 6638 66" x 38" x 21"	•	\$4,930	\$490	\$950°	\$925	\$1,125	_	Incl.	_	_
176	ESTHESIA 6638 66" x 38" x 21"	**	\$2,975	\$490	\$950	\$925	\$1,125	\$370	Incl.	_	\$650
214	MONARCH 6638F Standard or Grand Luxury 66" x 38" x 20"	**	s \$3,940 GL \$7,890	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$650
	6642										
168	ELEGANCIA 6642 <sup>††</sup> 66" x 42" x 21"	**	\$3,205	\$490†	\$950°	\$925	\$1,125	\$370	Incl.	_	_
	7236										
146	AMMA 7236 72" x 36" x 21"	**	\$4,930	\$490†	\$950°	\$925	\$1,125	\$370	Incl.	_	_
170	ELEGANCIA 7236 <sup>††</sup> 72" × 36" × 21"	**	\$3,270	\$490†	\$950°	\$925	\$1,125	\$370	Incl.	_	_
174	ESSENCIA OVAL 7236 72" x 36" x 25"	•	\$4,525	\$490	\$950	\$925	\$1,125	_	Incl.	_	\$850
202	MERIDIAN 60 72" x 36" x 21"	**	\$2,990	\$490†	\$950	\$925	\$1,125	\$370	Incl.	_	_
206	PRO-MERIDIAN 60 72" x 36" x 20"	**	\$3,000	\$490†	\$950	\$925	\$1,125	_	Incl.	_	_
216	MONARCH 7236 Standard or Grand Luxury 72" x 36" x 21"	•	S <b>\$4,100</b> GL <b>\$8,385</b>	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$650
230	ORIGAMI 7236# Original Series 72" x 36" x 22"	**	\$3,635	\$490†	\$950	\$925	\$1,125	\$370	Incl.	_	\$650
	7238										
218	MONARCH 7238F Standard or Grand Luxury 72" x 38" x 21"	**	s <b>\$4,165</b> GL <b>\$8,480</b>	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$650

Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

† When tilling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.
†† All contours are available at the same price.
†† All contours are available at the same price.
†† All contours are available at the same price.
†† Available with or without integrated tile flange.
†\* Available with or without integrated tile flange.
†\* The MiaPlus® Control is included when purchasing this option.
†\* When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.

						THERAPIES (+)			CONTROL (+)	OPTIO	ONS (+)
Page			TUB	Aroma- Cloud®	AromaFlow	Illuzio Chroma- therapy	Warm TouchShell WTS	2 <sup>nd</sup> WTS	DOT control	Colors	UltraVelour matte finish
	7240										
186	ELLIPSE 7240 Flat or rolled deck 72" x 40" x 21"	**	\$2,970	\$490	\$950	\$925	\$1,125	\$370	Incl.	_	_
182	INUA 7240# 72" × 40" × 23"	**	\$5,470	\$490	\$950	\$925	\$1,125	\$370	Incl.	_	\$650
220	MONARCH 7240 Standard or Grand Luxury 72" x 40" x 21"	**	s <b>\$4,230</b> GL <b>\$8,745</b>	_	\$950	\$925	\$1,125	\$370	Incl.	_	\$650
	7242										
148	AMMA 7242 72" × 42" × 22"	**	\$5,060	\$490†	\$950◊	\$925	\$1,125	\$370	Incl.	_	_
150	AMMA OVAL 7242 Raised or flat deck 72" x 42" x 22"	**	\$5,060	\$490	\$950°	\$925	\$1,125	\$370	Incl.	_	_
172	ELEGANCIA 7242 <sup>††</sup> 72" x 42" x 21"	**	\$3,420	\$490†	\$950◊	\$925	\$1,125	\$370	Incl.	_	_
232	ORIGAMI 7242# Original Series 72" x 42" x 22"	**	\$3,890	\$490†	\$950	\$925	\$1,125	\$370	Incl.	_	\$650

- Note: Geysair® technology is included in all BainUltra ThermoMasseurs®.

  † When tiling flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.

  ††† Optional deck color Black, Crystal Rock, and Copper. # Slim deck available at same price. †† All contours are available at the same price.

  \* Available with or without integrated tile flange.
- ††† Optional deck color Black, Crystal Rock, and Copper.

  \*\* Integrated tile flange & skirt. ‡ The MiaPlus® Control is included when purchasing this option.
- ♦ When purchasing an AromaFlow on Amma and Elegancia models, the Grab Bars can not be installed.

# THERAPEUTIC CARE UNIT

# **VEDANA®**

Model	Dimensions	MiaPlus® Control	Price
Vedana (White 01, Biscuit 02) BVEDANA	21" x 80" x 9 <sup>1/2</sup> "	Incl.	\$11,200

# COMPLEMENTARY PRODUCTS

# **AKAŜA®**

Model	Price
Bath Pillow BPILLOW	\$240
Datif Fillow Brittow	\$240
Comfort Cushion (Grey 05, Black 06) BCUSHION-XX	\$540
Nordic Spirit Essential Oils (15 ml bottle) Essential oils blend for the AromaCloud® and AromaFlow essential oil diffusers, and the Vedana®.	\$25

# **ACCESSORIES**

# **QUARTZ SKIRTS**

Quartz skirts are available in the same colors as the Monarch deck.

When ordering a Quartz skirt, it is essential to specify the model and color. Quartz skirts are optional.

Model	SKIRT 6018 60" x 18 7/8" BSM6018-XX	SKIRT 6618 66" x 18 5/8" BSM6618-XX	<b>SKIRT 7220 72" x 20"</b> BSM7220-XX
Grey Expo 21	\$1,195	\$1,315	\$1,500
Jet Black 23, Lagos Blue 24	\$1,315	\$1,380	\$1,620
Quasar Light 25	\$1,860	\$1,980	\$2,275
Piatra Grey 26, Bianco Drift 31, Woodlands 30	\$1,915	\$2,100	\$2,395
Statuario Maximus 29	\$2,700	\$2,940	\$3,350

# **SKIRTS (OPTION)**

Model	Sold wi	th bath	Sold separately	
MultiFit (Adjustable, 2 pieces, skirt panel and toe kick) Fits most rectangular bath models with standard 1 1/2" deck (White 01, Biscuit 02)	BSMUL-XX	\$600	BSSMUL60-XX BSSMUL66-XX BSSMUL72-XX	\$670
SJ-1 (1 piece) Fits most rectangular bath models (White 01, Biscuit 02)	BSJ1-XX	\$715	BSSJ160-XX BSSJ166-XX BSSJ172-XX	\$785
SJ-3 SE (6 pieces) Sensation (White 01, Biscuit 02)	BSJ3SE-XX	\$1,310	BSSJ3SE-XX	\$1,385

# **WASTE & OVERFLOW**

Finish	Integrated wast	e and overflow*	16" X 35"	D13 (Balneo®)	D14 (Elegancia®)
	BOVERIN-XX	BOVERINI-XX	BOVER16-XX	BOVERD13-XX	BOVERD14-XX
White 01, Biscuit 02	\$235	\$0	\$290	N/A	\$265
Chrome 07	\$235	\$0	\$260	\$490	\$250
Brushed Nickel 09, Polished Nickel 10	\$235	\$0	\$400	\$500	\$270
Oil-rubbed Bronze 11	N/A	\$0	\$400	\$500	N/A
Matte Black 19, Satin Brass 18	\$355	\$120	N/A	N/A	N/A
Unplated 00	N/A	N/A	N/A	\$500	N/A
If required by construction code:	Brass waste and ove Brass waste kit BDRCB Cable driven brass w		POVERED		\$240 \$60 \$240

<sup>\*</sup> Factory installed only and available as an option on collections Inua, Amma, Origami, and the Essencia 6838 model.



# ACCESSORIES (Cont'd)

# **ULTRAVELOUR FINISH (OPTION)**

Description	Price
UltraVelour Finish   Drop-in and Alcove baths BVEL1	\$650
UltraVelour Finish   Freestanding baths* BVEL2	\$850
UltraVelour Finish   Freestanding Baths: Esthesia 6436, Libra Oval 6635 and Libra Stella 7038 BVEL3	\$1,025

<sup>\*</sup> And Essencia Oval 7236 (Drop-in)

# **OTHER ACCESSORIES**

Model	Price
Island Tub Drain™ BISLDD	\$260
Air Intake* BAIRINT	\$120
Air Intake and Island Tub Drain™ BAIRISLD	\$350
Cast Iron Island Tub Drain™ BISLDDCI	\$310
Air Intake installation	\$285 net

<sup>\*</sup> For Nokori rectangular bath models only

GRAB BARS

OPTIONAL COLOR (upcharge applicable)

8
Clear Acrylic BGBG10-XX
Chrome 07 or ushed Nickel 09 inserts
\$60
\$60
\$60
\$60
\$60
\$60

ARMRESTS & FEET	COLOR (upcharge applicable)			
Model	White 01 Chrome 07, Brushed Satin Brass Nickel 09, Polished Nickel 10 Matte Black			
Scala armrests (2) BGBSG-XX	N/A	\$1,950	\$1,300	
Scala feet BFEETSC-XX	N/A	\$1,100	Incl.	
Universal Armrests* BGBGU-XX	\$750	N/A	N/A	

<sup>\*</sup> Available for Bain de Ville, Balneo, Charism, Citti, Esthesia, Evanescence, Libra, Nokori, Opalia, Origami, & Vibe Collections except the Libra Oval 6635, and Origami 6030 bath models.

# ACCESSORIES (Cont'd)

# OTHER - BALNEO® COLLECTION ONLY For exposed air pipe. (For air supply)

Model	Price
Decorative pipe (1 1/2" x 6") BPIPE6-XX	\$55
Decorative pipe (1 1/2" x 24") BPIPE24-XX	\$200
Pipe concealer (3" x 5 1/4") for Cella only BPIPEC-XX	\$105
Elbow (45°) BELB45-XX	\$80
Elbow (90°) BELB90-XX	\$105

# **TILE FLANGE**

Model	Price
Ordered with bath OR Sold separately for Nokori bath (not installed) BTILEN	\$79
Sold separately BTILEA	\$95
Factory-installed. Front BTILEF, Back BTILEB, Right BTILER, Left BTILEL, Special installation BTILEO	\$155

# **REPLACEMENT PARTS**

Model	Price	
DOT CONTROL		
Dot only - For TUB [soaker] only (sold separately) BSDOT	\$130	
MIA® CONTROL & TURBINE		
Mia®. Standard color: White 01, Biscuit 02 (sold separately) BSMIA-XX	\$165	
MiaPlus®. Standard color: White 01, Biscuit 02 (sold separately) BSMIAP-XX	\$410	
Turbine for Mia® and MiaPlus® (with Geysair) TUR4STD-JETS	\$665	
Turbine for MiaPlus® – 1 heated backrest (without Geysair) TUR4STD	\$665	
Turbine for 2 heated backrests (without Geysair) TUR4DDC	\$910	


# **OTHER COMPONENTS**

15' extension cord for MiaPlus® & Vedana® #15303015	\$90
15' replacement cord for MiaPlus® & Vedana® #15201520	\$75
15' Geysair® extension cord #22000131	\$45





# FINESTONE® SOLID SURFACE THERAPEUTIC BATHS



REFINEMENT BEYOND COMPARE

# CELESTIA 6233

62" x 33" x 24" (FREESTANDING)

Celestia™ is feminine, ethereal and strong. As a beautiful work of art in a museum, Celestia is the center piece of any bathroom, a jewel that captures attention and pleases the eye.



Source				,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
FEATURES				
Installation type			F	reestanding
No. of bathers	•	Imp. gallo	ns	47
US gallons	57	Armrests		2
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
Matte White** 32, Chrome 07, Brushed Nickel 09, Polished Nickel 10		Installed & Included		
<b>STANDARD COLOR</b> p.	13			
White 01			Included	
FINISH				

OPTIONS (UPCHARGE APPLICABLE)		
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10		
Matte Black 19, Satin Brass 18	\$120	
ISLAND TUB DRAIN™* p.11		
Island Tub Drain™ BISLDD	\$260	
Cast Iron Island Tub Drain™ BISLDDCI	\$310	
IF REQUIRED BY CONSTRUCTION CODE OR INSTALLED WITH ITD*		
Brass waste kit BDRCBF Matte White** 32, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte Black 19, Satin Brass 18	\$60	



Don't forget to indicate the finish for the Integrated waste & overflow and, if needed, for the Brass waste kit.

- \* An Island Tub Drain  $\!^{\mathsf{TM}}$  and the Brass waste kit are required when there is **no access under the bath**.
  \*\* On a FineStone bath, the white Integrated waste & overflow
- has a Matte Finish.

# TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com



Satin Finish

Made with FineStone®

FineStone® is a high quality solid surface material composed of refined minerals and pure acrylic. Designed with care, this material is non porous, hygienic, and thermal insulant. Its satin finish is easy to clean and will maintain its properties through time.

Included


\$8,000


XWX





# INSTALLATION







LETTER	DESCRIPTION	MEASURE
Α	Total length	62"
В	Total width	33"
С	Bathing well length	42 7/8"
D	Bathing well width	22 3/16"
E	Deck width	3/4"
F	Deck width	3/4"
G	Total maximal height	24"
н	Total minimal height	22"
ı	Maximum water level	16 1/2"
J	Slope of backrest	28°
K	Base length	36 3/4"
L	Base width	20"
М	Outer edge to center of drain	17 5/16"

TECHNICAL SPECIFICATIONS				
Other	Faucet must be freestanding or wall-mounted.	Cutting template	# 90000084	
Our products must be installed by certified professionals only and according to our Installation Instructions as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).		Approx. shipping weight	300 lb	
		WARRANTY		
		Bath*	20 years	

 $<sup>\</sup>hbox{* Some restrictions apply} \mid \hbox{www.bainultra.com/warranty}$ 

The specifications shown indicate the outer edge dimension and the inside bathing capacity. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.

# CELESTIA 6635

66" x 35" x 25" (FREESTANDING)

Celestia™ is feminine, ethereal and strong. As a beautiful work of art in a museum, Celestia is the center piece of any bathroom, a jewel that captures attention and pleases the eye.



Freestanding	BCEHOF00F
TUB Soaker	\$8,600

FEATURES					
Installation type			F	Freestanding	
No. of bathers	* *	Imp. gallo	ns	61	
US gallons	74	Armrests		2	
INTEGRATED WASTE 8	OVERFLO	<b>W</b> BOVERINI-	xx p. 10		
Matte White** 32, Chrome 07, Brushed Nickel 09, Polished Nickel 10			Installed & Included		
STANDARD COLOR p. 13					
White 01				Included	
FINISH					
Satin Finish				Included	

OPTIONS (UPCHARGE APPLICABLE)		
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10		
Matte Black 19, Satin Brass 18	\$120	
ISLAND TUB DRAIN™* p.11		
Island Tub Drain™ BISLDD	\$260	
Cast Iron Island Tub Drain™ BISLDDCI	\$310	
IF REQUIRED BY CONSTRUCTION CODE OR INSTALLED WITH ITD*		
Brass waste kit BDRCBF Matte White** 32, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte Black 19, Satin Brass 18	\$60	

Don't forget to indicate the finish for the Integrated waste & overflow and, if needed, for the Brass waste kit.

- \* An Island Tub Drain™ and the Brass waste kit are required when there is **no access under the bath**.
  \*\* On a FineStone bath, the white Integrated waste & overflow
- has a Matte Finish.

# TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com





Made with FineStone®

FineStone® is a high quality solid surface material composed of refined minerals and pure acrylic. Designed with care, this material is non porous, hygienic, and thermal insulant. Its satin finish is easy to clean and will maintain its properties through time.









LETTER	DESCRIPTION	MEASURE
Α	Total length	66"
В	Total width	35"
С	Bathing well length	47"
D	Bathing well width	25 1/2"
E	Deck width	3/4"
F	Deck width	3/4"
G	Total maximal height	25"
н	Total minimal height	23"
ı	Maximum water level	17 1/2"
J	Slope of backrest	28 1/2°
K	Base length	41 1/4"
L	Base width	22 1/2"
М	Slope of backrest (overflow side)	29 1/2°

TECHNICAL SPECIFICATIONS				
Other	Faucet must be freestanding or wall-mounted.	Cutting template	# 90000085	
Our products	must be installed by certified professionals only and according to our Installation Instructions as well as federal, the and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	Approx. shipping weight 330 lb		
provinciai/stat	e and local building codes and regulations (www.balnuitra.com/dealers/dealer-documentation-and-catalog).	WARRANTY		
		Bath*	20 years	

 $<sup>\</sup>hbox{* Some restrictions apply} \mid \hbox{www.bainultra.com/warranty}$ 

The specifications shown indicate the outer edge dimension and the inside bathing capacity. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.



PRODUCT NO.					
MODEL	тми	TUB			
Freestanding	BOS2RF00S	BOS2RF00F			

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$11,750
Jets	42
1 heated backrest	Included
MiaPlus® Control (not installed)	Included
BU-Touch Control Application BUTOUCH	Included

<b>TUB</b> Soaker		\$	8,9	000

FEATURES						
Installation type					Free	estanding
No. of bathers		* *	Imp. gallo	ns	тми 62	тив 68
US gallons	тми 74	тив 81	Armrests			2
INTEGRATED WA	STE & C	VERFLO	W BOVERINI-	xx p. 10	)	
Matte White** 32, Chrome 07, Brushed Nickel 09, Polished Nickel 10		In	nstalled & Included			
STANDARD COLOR p.13						
White 01						Included
FINISH						
Satin Finish				Included		

OPTIONS (UPCHARGE APPLICABLE)	
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™* p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE OR INSTALLED	WITH ITD*
Brass waste kit BDRCBF Matte White** 32, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte Black 19, Satin Brass 18	\$60

Don't forget to indicate the finish for the Integrated waste & overflow and, if needed, for the Brass waste kit.
\* An Island Tub Drain™ and the Brass waste kit are required

- when there is **no access under the bath**.
- \*\* On a FineStone bath, the white Integrated waste & overflow has a Matte Finish.

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com





Made with FineStone®

FineStone® is a high quality solid surface material composed of refined minerals and pure acrylic. Designed with care, this material is non porous, hygienic, and thermal insulant. Its satin finish is easy to clean and will maintain its properties through time.









		MEASURE		
LETTER	DESCRIPTION	TMU	TUB	
Α	Total length	64"	64"	
В	Total width	34"	34"	
С	Bathing well length	48 15/16"	47 15/16"	
D	Bathing well width	22 1/16"	23 1/8"	
E	Deck width	1 5/8"	3/4"	
F	Deck width	3/4"	3/4"	
G	Total maximal height	24 3/4"	24 3/4"	
Н	Total minimal height	24"	24"	
I	Base length	45 5/16"	43 1/16"	
J	Slope of backrest	19°	23°	
K	Maximum water level	18"	18 1/4"	
L	Base width	23"	20 1/16"	

Indicates heated backrest (TMU)

Hot water supply required  The hot water supply should be 70% or more of the bath's total water capacity.		Cuttin
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is a 15A, 120 V, 60 Hz</b> ,	Approx.
Turbine	dedicated lines with a GFCI. Air vent necessary: 2" x 4" minimum.	Turbin
Others	- The turbine must be <b>remotely installed</b> .	
	- Faucet must be freestanding or wall-mounted Controls cannot be installed on the deck of the bath.	WARR
	be installed by certified professionals only and according to our Installation Instructions as well as federal,	Contro
provincial/state and	d local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	Bath &

TMU	TUB
# 90000089	# 90000088
380 lb	285 lb
	550 W
	600 W
	5 years
	20 years
	# 90000089

<sup>\*</sup> Some restrictions apply | www.bainultra.com/warranty

The specifications shown indicate the outer edge dimension and the inside bathing capacity. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.



# FREESTANDING THERAPEUTIC BATHS




A SOPHISTICATED LINE OF PRODUCTS











# AMMA OVAL 7242 NARROW BASE

72" x 42" x 27" (FREESTANDING)

Amma takes its origin in the word "massage" as represented by two Chinese characters, AN and MO, meaning "calm through touch."

# PRODUCT NO.

MODEL	TMU	TUB	
Flat deck	BAMVOFS0T-XX	BAMVOFS0N-XX	
Raised deck	BAMVOFR0T-XX	BAMVOFR0N-XX	
***************************************			

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$11,255
Jets	58
2 heated backrests & headrests*	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®** BAROMAC	\$490
AromaFlow**** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$8,780
AromaCloud®** BAROMAC	\$490
AromaFlow***** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			F	reestanding
No. of bathers	* *	Inverted V		2
US gallons	65	Armrests		4
Imp. gallons	54	Grab bars (	color match)	2
Raised seats	2			

### WASTE & OVERFLOW 16" x 35" BOVER16I-XX p. 10

White 01, Biscuit 02, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11

Installed & Included

STANDARD COLOR P	. 13	
White 01 Biscuit 02		Included
STANDARD BASE COI	OR BAMBASE-XX	
Same as bath color XX		Included

With flat deck

OPTIONS (UPCHARGE APPLICABLE)	
CLEAR ACRYLIC GRAB BARS BGBG10-XX p.12	
With Chrome 07 or Brushed Nickel 09 inserts	\$60
INTEGRATED WASTE & OVERFLOW (installed) BOVERIN-XX p	.10
White 01, Biscuit 02, Chrome 07, Brushed Nickel 09, Polished Nickel 10	\$235
Matte Black 19, Satin Brass 18	\$355
ISLAND TUB DRAIN™*** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit**** BDRCOB	\$240
Brass waste kit**** BDRCB	\$60
16" x 35" Cable driven brass waste & overflow kit BOVERBR	\$240



Don't forget to indicate raised or flat deck. Specify the finish for the waste & overflow. The turbine must be remotely installed.

\* Independently controlled.

\*\* The AromaCloud® is built into the deck (factory installed). \*\*\* An Island Tub Drain™ is required when there is **no access under the bath**. ITD is available only with the 16" x 35" Cable driven brass waste & overflow kit.

\*\*\*\* When ordered with integrated waste & overflow.

\*\*\*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste. With the AromaFlow, the included Grab Bars can not be installed.

### TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

# FOR THE INSTALLER

**SCAN** TO VIEW INSTALLATION VIDEO (3:20 MIN)












AMMA OVAL 7242 NARROW BASE (FREESTANDING)

Flat deck

### INSTALLATION

Available with raised or flat deck.



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	13 1/2"
В	Outside edge to overflow	5 3/8"
С	Total length	72"
D	Total width	42"
E	Bathing well length	52 1/4"
F	Bathing well width at center zone	21 3/8"
G	Raised seat length	18 5/8"
Н	Raised seat width	24"
I	Flat surface width	3 7/8"
J	Deck width	5 1/4"
K	Height from bottom of bath to top deck	26 3/8"
L	Height from bottom of bath to top deck	24 1/8"
М	Height from bottom of lip to top deck	2"
N	Height from bottom of drain to center of overflow	18 1/8"
0	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	16 3/8" 17 3/8" 16 3/4"
P	Slope of backrests	18°
Q	Base Width	28 1/2"
R	Base Length	40 1/8"
S	Height from bottom of bath to floor	3/4"

- ⚠ AromaCloud® position
- Control position when factory-installed (Mia® or DOT)
- Indicates heated backrest (TMU)

# 90000059

290 lb 550 W 600 W

5 years 20 years

Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is two (2) dedicated breakers: One is 20A, 120 V, 60 Hz, and the other 15A, 120 V, 60 Hz,</b> dedicated lines with a GFCI. Air vent necessary: 2" x 4" minimum.	
Others	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access). There is a height difference for the flat deck (see drawing Detail A). Faucets may be installed on deck of bath on the drain & overflow side. Overflow preinstalled for easier in-home fitting. The turbine must be remotely installed. The water level will vary when an AromaFlow is installed.	

th a GFCI.	Turbine power		
	Air heater		
	WARRANTY		
	Controls-LED-Geysair		
	Bath & turhine*		

**Cutting template** 

Approx. shipping weight

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

The specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.

<sup>\*</sup> Some restrictions apply | www.bainultra.com/warranty

# AMMA OVAL 7242

72" x 42" x 28" (FREESTANDING)

Amma takes its origin in the word "massage" as represented by two Chinese characters, AN and MO, meaning "calm through touch."



MODEL	ТМИ	TUB	
Flat deck	BAMVOFN0T-XX	BAMVOFN0N-XX	
Raised deck	BAMVOFP0T-XX	BAMVOFP0N-XX	
THERMOMASSEUR (TI Hydro-thermo massag	\$12,645		
Jets		58	
2 heated backrests & hea	adrests*	Included	
MiaPlus® Control		Included	
BU-Touch Control Application BUTOUCH		\$430	
Geysair <sup>®</sup>		Included	
AromaCloud®** BAROMAC		\$490	
AromaFlow***** BAROMAF NEW		\$950	
Illuzio Chromatherapy BCHRO6		\$925	
<b>TUB</b> Soaker		\$9,725	

Juakei	+ - / /
AromaCloud®** BAROMAC	\$490
AromaFlow***** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			F	reestanding
No. of bathers	* *	Inverted V		2
US gallons	65	Armrests		4
Imp. gallons	54	Grab bars	(color match)	2
Raised seats	2			
WASTE & OVERFLOW 16" x 35" BOVER16I-XX p. 10				
White 01, Biscuit 02, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11		d & Included		
STANDARD COLOR p.13				
White 01 Biscuit 02				Included
STANDARD BASE COLOR BAMBASE-XX				
Same as bath color XX				Included

OPTIONS (UPCHARGE APPLICABLE)	
CLEAR ACRYLIC GRAB BARS BGBG10-XX p. 12	
With Chrome 07 or Brushed Nickel 09 inserts	\$60
INTEGRATED WASTE & OVERFLOW (installed) BOVERIN-XX	(p.10
White 01, Biscuit 02, Chrome 07, Brushed Nickel 09, Polished Nickel 10	\$235
Matte Black 19, Satin Brass 18	\$355
ISLAND TUB DRAIN™*** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit**** BDRCOB	\$240
Brass waste kit**** BDRCB	\$60
16" x 35" Cable driven brass waste & overflow kit BOVERBR	\$240



With flat deck

Don't forget to indicate raised or flat deck. Specify the finish for the waste & overflow.

\* Independently controlled.

\*\* The AromaCloud® is built into the deck (factory installed).

\*\*\* An Island Tub Drain™ is required when there is **no access under** the bath.

\*\*\*\* When ordered with integrated waste & overflow.

\*\*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste. With the AromaFlow, the included Grab Bars can not be installed.

### TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

# FOR THE INSTALLER

**SCAN** TO VIEW INSTALLATION VIDEO (3:20 MIN)











Raised deck




AMMA OVAL 7242 (FREESTANDING)

Flat deck

### INSTALLATION

Available with raised or flat deck.



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	13 1/2"
В	Outside edge to overflow	5 3/8"
С	Total length	72"
D	Total width	42"
E	Bathing well length	52 1/4"
F	Bathing well width at foot area	21 3/8"
G	Raised seat length	18 5/8"
Н	Raised seat width	24"
1	Flat surface width	3 7/8"
J	Deck width	5 1/4"
K	Total height to headrest	29 7/8"
L	Height from bottom of bath to top deck	27 5/8"
М	Height from bottom of lip to top deck	2"
N	Height from bottom of drain to center of overflow	18 1/8"
0	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	16 3/8" 17 3/8" 16 3/4"
P	Slope of backrests	18°
Q	Base length	42 5/8"
R	Base width	28 5/8"

⚠ AromaCloud® position

Control position when factory-installed (Mia® or DOT)

- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is two (2) dedicated</b>	Approx. shipping wei
Turbine breakers:	breakers: One is 20A, 120 V, 60 Hz, and the other 15A, 120 V, 60 Hz, dedicated lines with a GFCI.	Turbine power
	Air vent necessary: 2" x 4" minimum.	Air heater
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).</li> <li>There is a height difference for the flat deck (see drawing Detail A).</li> <li>Turbine located under bath and accessible by a removable base cover.</li> <li>Faucets may be installed on deck of bath. Overflow preinstalled for easier in-home fitting.</li> <li>Specify flat or raised dock. The water level will vary when an AromaFlow is installed</li> </ul>	WARRANTY
		Controls-LED-Geysair*
		Bath & turbine*

- Specify flat or raised deck The water level will vary when an AromaFlow is installed.		
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).		

Cutting template	# 90000036
Approx. shipping weight	290 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years


<sup>\*</sup> Some restrictions apply  $\mid$  www.bainultra.com/warranty

The specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.

# **CELLA** 6636

66" x 36" x 27" (FREESTANDING)

The name Balneo evokes the art of bathing. For BainUltra, a bath is an important ritual, part of a lifestyle that encourages you to slow down and take time for yourself.



MODEL	тми	TUB
Flat deck	BBCLOFN0T-XX	BBCLOFN0N-XX
Rolled deck	BBCLOFP0T-XX	BBCLOFP0N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$10,145
Jets	38
1 heated backrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®** BAROMAC	\$490
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$7,260
AromaCloud®** BAROMAC	\$490
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			F	reestanding
No. of bathers	♥♥ Imp. gallo		ns	40
US gallons	48			
STANDARD COLOR p.13				
White 01 Biscuit 02				Included
CLAW FEET (specify finish) BFEET-XX p.12				
Chrome 07, Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11, Unplated 00				Included

OPTIONS (UPCHARGE APPLICABLE)		
UNIVERSAL ARMRESTS BGBGU-XX p.12		
White 01	\$750	
FOR AIR SUPPLY ONLY		
Decorative pipe (1 1/2" x 6")	\$55	
Decorative pipe (1 1/2" x 24")	\$200	
Pipe concealer (3" x 5 1/4")	\$105	
Elbow (45°)	\$80	
Elbow (90°)	\$105	
WASTE & OVERFLOW D13 (exposed) BOVERD13-XX p. 10		
Chrome 07	\$490	
Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11 Unplated 00	\$500	

Don't forget to indicate **flat or rolled deck**, as well as the selected **finish** for the claw feet.

- \* For TMU, control must be wall-mounted. Faucets must be freestanding or wall-mounted.

  \*\* The AromaCloud® is built into the deck (factory installed).

# TO ORDER

Complete the  ${\bf ORDER}$   ${\bf FORM}$  in the  ${\bf bainultra.com/interactive-price-list}$  or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com







# **CELLA** 6636 (FREESTANDING)

Detail A

# Available with flat or rolled deck. Air intake AromaCloud\*\* modified deck Rolled deck Waste

LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11 1/2"
В	Outside edge to overflow	4 5/8"
С	Total length	66"
D	Total width	36"
E	Bathing well length	42 3/8"
F	Bathing well width	22 1/4"
G	Deck width	4 1/4"
Н	Flat surface width	3"
I	Rolled deck width	4 3/4"
J	Height from bottom of lip to top deck	2 1/2"
K	Height from clawfoot to top of lip	27 3/4"
L	Height from clawfoot to top of lip	26 3/4"
М	Height from bottom of drain to center of overflow	16 5/8"
N	Maximum water level	14 7/8"
0	Slope of backrests	25°
P	Length between clawfeet	34 5/8"
Q	Width between clawfeet	23 1/2"
R	Center drain to center air intake	3 1/4"
S	Clearance from floor to bottom of bath	4 1/2"

Cutting template
Approx. shipping weight

A AromaCloud® position

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

# 90000055

285 lb

TECHNICAL SPECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	
Others	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access). There is a height difference for the rolled deck (see drawing Detail A). Faucets must be freestanding or wall-mounted. The turbine must be remotely installed. TMU: Control must be wall-mounted. TIUB: Dot controls are located on either sides of the AromaCloud® (see page 9, position of DOT control).	

Air intake

Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years

 $<sup>\</sup>mbox{*}$  Some restrictions apply | www.bainultra.com/warranty

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

The specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.

# **ELLA** 7240

72" x 40" x 27" (FREESTANDING)

The name Balneo evokes the art of bathing. For BainUltra, a bath is an important ritual, part of a lifestyle that encourages you to slow down and take time for yourself.



MODEL		тми	TUB
	Flat deck	BBCUOFN0T-XX	BBCUOFN0N-XX
	Rolled deck	BBCUOFP0T-XX	BBCUOFP0N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$11,100
Jets	40
1 heated backrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®** BAROMAC	\$490
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$8,485
AromaCloud®** BAROMAC	\$490
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			F	reestanding
No. of bathers	* *	Imp. gallo	ns	49
US gallons	59			
STANDARD COLOR p.13				
White 01 Biscuit 02				Included
CLAW FEET (specify finish) BFEET-XX p.12				
Chrome 07, Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11, Unplated 00				Included

OPTIONS (UPCHARGE APPLICABLE)	
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
FOR AIR SUPPLY ONLY	
Decorative pipe (1 1/2" x 6")	\$55
Decorative pipe (1 1/2" x 24")	\$200
Pipe concealer (3" x 5 1/4")	\$105
Elbow (45°)	\$80
Elbow (90°)	\$105
WASTE & OVERFLOW D13 (exposed) BOVERD13-XX p.10	
Chrome 07	\$490
Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11 Unplated 00	\$500

Don't forget to indicate **flat or rolled deck**, as well as the selected **finish** for the claw feet.

- \* For TMU, control must be wall-mounted. Faucets must be freestanding or wall-mounted.

  \*\* The AromaCloud® is built into the deck (factory installed).

### TO ORDER

Complete the  ${\bf ORDER}$   ${\bf FORM}$  in the  ${\bf bainultra.com/interactive-price-list}$  or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com








# **CELLA** 7240 (FREESTANDING)

### INSTALLATION

Available with flat or rolled deck.



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11 3/4"
В	Outside edge to overflow	4 3/8"
С	Total length	72"
D	Total width	40"
E	Bathing well length	46 1/8"
F	Bathing well width	24 3/4"
G	Deck width	4 5/8"
Н	Flat surface width	3 3/8"
I	Rolled deck width	5 3/8"
J	Height from bottom of lip to top deck	2 1/2"
K	Height from clawfoot to top of lip	27 3/4"
L	Height from clawfoot to top of lip	26 3/4"
М	Height from bottom of drain to center of overflow	16 5/8"
N	Maximum water level	14 7/8"
0	Slope of backrests	27°
P	Length between clawfeet	40 3/4"
Q	Width between clawfeet	24"
R	Center drain to center air intake	5"
s	Clearance from floor to bottom of bath	4 1/2"

⚠ AromaCloud® position

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS				
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000001	
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	297 lb	
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power	550 W	
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W	
	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	WARRANTY		
Others	There is a height difference for the rolled deck (see drawing Detail A).     Faucets must be freestanding or wall-mounted.	Controls-LED-Geysair*	5 years	
	- The turbine must be <b>remotely installed</b> TMU: Control must be wall-mounted.	Bath & turbine*	20 years	
	- TUB: Dot controls are located on either sides of the AromaCloud® (see page 9, position of DOT control).	* Some restrictions apply   www.bainul	tra.com/warranty	

The specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

# **NAOS** 6636

66" x 36" x 25" (FREESTANDING)

The name Balneo evokes the art of bathing. For BainUltra, a bath is an important ritual, part of a lifestyle that encourages you to slow down and take time for yourself.



MODEL	TMU	TUB	
Flat deck	BBNLOFN0T-XX	BBNLOFN0N-XX	
Rolled deck	BBNLOFP0T-XX	BBNLOFP0N-XX	

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$11,240
Jets	38
1 heated backrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®** BAROMAC	\$490
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$8,195
AromaCloud®** BAROMAC	\$490
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES					
Installation type	ation type			Freestanding	
No. of bathers	* *	Imp. gallor	าร	40	
US gallons	48				
STANDARD COLOR p.	13				
White 01 Biscuit 02				Included	

OPTIONS (UPCHARGE APPLICABLE)	
UNIVERSAL ARMRESTS BGBGU-XX p. 12	
White 01	\$750
FOR AIR SUPPLY ONLY	
Decorative pipe (1 1/2" x 6")	\$55
Decorative pipe (1 1/2" x 24")	\$200
Pipe concealer (3" x 5 1/4")	\$105
Elbow (45°)	\$80
Elbow (90°)	\$105
WASTE & OVERFLOW D13 (exposed) BOVERD13-XX p.10	
Chrome 07	\$490
Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11 Unplated 00	\$500

Don't forget to indicate flat or rolled deck.

\* For TMU, control must be wall-mounted. Faucets must be freestanding or wall-mounted.
\*\*The AromaCloud® is built into the deck (factory installed).

# TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com










# NAOS 6636 (FREESTANDING)

# INSTALLATION

Available with flat or rolled deck.









LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11 1/2"
В	Outside edge to overflow	4 5/8"
С	Total length	66"
D	Total width	36"
E	Bathing well length	42 3/8"
F	Bathing well width	22 1/4"
G	Deck width	4 1/4"
Н	Flat surface width	3"
I	Rolled deck width	4 3/4"
J	Height from bottom of lip to top deck	2 1/2"
K	Height from bottom of bath to top deck	26 3/4"
L	Height from bottom of bath to top deck	25 3/4"
М	Height from bottom of drain to center of overflow	16 5/8"
N	Maximum water level	14 7/8"
0	Slope of backrests	25°
P	Base length	59 1/8"
Q	Base width	32 1/4"
R	Center drain to center air intake	3 1/4"

⚠ AromaCloud® position

Indicates heated backrest (TMU)

 Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.		
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.		
Others	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access). There is a height difference for the rolled deck (see drawing Detail A). Faucets must be freestanding or wall-mounted. The turbine must be remotely installed. TMU: Control must be wall-mounted. TIUB: Dot controls are located on either sides of the AromaCloud® (see page 9, position of DOT control).	* S	

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

Cutting template	# 90000055
Approx. shipping weight	265 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years

Some restrictions apply | www.bainultra.com/warranty

The specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.

# **NAOS** 7240

72" x 40" x 25" (FREESTANDING)

The name Balneo evokes the art of bathing. For BainUltra, a bath is an important ritual, part of a lifestyle that encourages you to slow down and take time for yourself.



MODEL	тми	TUB
Flat deck	BBNUOFN0T-XX	BBNUOFN0N-XX
Rolled deck	BBNUOFP0T-XX	BBNUOFP0N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$12,055
Jets	40
1 heated backrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®** BAROMAC	\$490
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$9,040
AromaCloud®** BAROMAC	\$490
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type	Installation type			reestanding
No. of bathers	* *	Imp. gallor	าร	49
US gallons	59			
STANDARD COLOR p.	13			
				Included
White 01 Biscuit 02				

OPTIONS (UPCHARGE APPLICABLE)	
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
FOR AIR SUPPLY ONLY	
Decorative pipe (1 1/2" x 6")	\$55
Decorative pipe (1 1/2" x 24")	\$200
Pipe concealer (3" x 5 1/4")	\$105
Elbow (45°)	\$80
Elbow (90°)	\$105
WASTE & OVERFLOW D13 (exposed) BOVERD13-XX p.10	
Chrome 07	\$490
Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11 Unplated 00	\$500

Don't forget to indicate flat or rolled deck.

\* For TMU, control must be wall-mounted. Faucets must be freestanding or wall-mounted.

\*\* The AromaCloud® is built into the deck (factory installed).

# TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com








# NAOS 7240 (FREESTANDING)

### INSTALLATION

Available with flat or rolled deck.



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11 3/4"
В	Outside edge to overflow	4 3/8"
С	Total length	72"
D	Total width	40"
E	Bathing well length	46 1/8"
F	Bathing well width	24 7/8"
G	Deck width	4 5/8"
Н	Flat surface width	3 3/8"
I	Rolled deck width	5 5/8"
J	Height from bottom of lip to top deck	2 1/2"
K	Height from bottom of bath to top deck	26 3/4"
L	Height from bottom of bath to top deck	25 3/4"
М	Height from bottom of drain to center of overflow	16 5/8"
N	Maximum water level	14 7/8"
o	Slope of backrests	27°
P	Base length	64 1/4"
Q	Base width	35 3/8"
R	Center drain to center air intake	5"

⚠ AromaCloud® position

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000001
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	285 lb
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Turbine power	550 W
		Air heater	600 W
It mu	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	WARRANTY	
Others	- There is a height difference for the rolled deck (see drawing Detail A).  Others - Faucets must be freestanding or wall-mounted.	Controls-LED-Geysair*	5 years
- The turbine must be <b>remotely installed</b> TMU: Control must be wall-mounted.		Bath & turbine*	20 years
	- TUB: Dot controls are located on either sides of the AromaCloud® (see page 9, position of DOT control).	* Some restrictions apply   www.bainul	tra.com/warranty

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

The specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.

63

# **SANOS** 6636

66" x 36" x 24" (FREESTANDING)

The name Balneo evokes the art of bathing. For BainUltra, a bath is an important ritual, part of a lifestyle that encourages you to slow down and take time for yourself.



# PRODUCT NO.

MODEL	тми	TUB
Flat deck	BBSLOFN0T-XX	BBSLOFN0N-XX
Rolled deck	BBSLOFP0T-XX	BBSLOFP0N-XX

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$9,880
Jets	38
1 heated backrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®** BAROMAC	\$490
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$7,230
AromaCloud®** BAROMAC	\$490
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			F	reestanding
No. of bathers	* *	Imp. gallor	าร	40
US gallons	48			
STANDARD COLOR p.	13			
White 01 Biscuit 02				Included
White 01 Biscuit 02				

OPTIONS (UPCHARGE APPLICABLE)	
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
FOR AIR SUPPLY ONLY	
Decorative pipe (1 1/2" x 6")	\$55
Decorative pipe (1 1/2" x 24")	\$200
Elbow (45°)	\$80
Elbow (90°)	\$105
WASTE & OVERFLOW D13 (exposed) BOVERD13-XX p.10	
Chrome 07	\$490
Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11 Unplated 00	\$500



With flat deck

Don't forget to indicate **flat or rolled deck**.

- \* For TMU, control must be wall-mounted. Faucets must be freestanding or wall-mounted.
- \*\* The AromaCloud® is built into the deck (factory installed).

# TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

# FOR THE INSTALLER

**SCAN** TO VIEW INSTALLATION VIDEO (3:20 MIN)







# SANOS 6636 (FREESTANDING)

INSTALLATION
Available with flat or rolled deck.
Air intake  AromaCloud modified dec
Flat deck  A  K  J  M
Rolled deck  V  Detail A  Air intake

LETTER	DESCRIPTION	MEASURE
LETTER	DESCRIPTION	WEASURE
Α	Outside edge to center drain	11 1/2"
В	Outside edge to overflow	4 5/8"
С	Total length	66"
D	Total width	36"
E	Bathing well length	42 3/8"
F	Bathing well width	22 1/4"
G	Deck width	4 1/4"
Н	Flat surface width	3"
ı	Height from bottom of bath to top deck	24 1/2"
J	Height from bottom of drain to center of overflow	16 5/8"
K	Maximum water level	14 7/8"
L	Slope of backrests	25°
М	Base length	50 7/8"
N	Base width	24 7/8"
0	Center drain to center air intake	3 1/4"
Т	Rolled deck width	4 3/4"
U	Height from bottom of lip to top deck	2 1/2"
V	Height from bottom of bath to top deck	25 1/2"

⚠ AromaCloud® position

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)


TECHNICAL SP	ECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000055
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	240 lb
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power	550 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W
	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	WARRANTY	
Others	- Faucets must be freestanding or wall-mounted The turbine must be <b>remotely installed</b> .	Controls-LED-Geysair*	5 years
	- There is a height difference for the rolled deck (see Detail A) TMU: Control must be wall-mounted.	Bath & turbine*	20 years
	- TUB: Dot controls are located on either sides of the AromaCloud® (see page 9, position of DOT control).	* Some restrictions apply   www.bainultra.c	om/warranty
	t be installed by certified professionals only and according to our Owner's Manual as well as federal, d local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).		

The specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.

# **SANOS** 7240

72" x 40" x 24" (FREESTANDING)

The name Balneo evokes the art of bathing. For BainUltra, a bath is an important ritual, part of a lifestyle that encourages you to slow down and take time for yourself.



MODEL	тми	TUB	I
Flat deck	BBSUOFN0T-XX	BBSUOFN0N-XX	
Rolled deck	BBSUOFP0T-XX	BBSUOFP0N-XX	

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$10,560
Jets	40
1 heated backrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®** BAROMAC	\$490
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$7,925
AromaCloud®** BAROMAC	\$490
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			Free	estanding
No. of bathers	**	Imp. gallor	ns	49
US gallons	59			
STANDARD COLOR p.	13			
White 01 Biscuit 02				Included

OPTIONS (UPCHARGE APPLICABLE)	
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
FOR AIR SUPPLY ONLY	
Decorative pipe (1 1/2" x 6")	\$55
Decorative pipe (1 1/2" x 24")	\$200
Elbow (45°)	\$80
Elbow (90°)	\$105
WASTE & OVERFLOW D13 (exposed) BOVERD13-XX p.10	
Chrome 07	\$490
Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11 Unplated 00	\$500



- Don't forget to indicate flat or rolled deck.

  - \* The AromaCloud\* is built into the deck (factory installed).
    \*\* For TMU, control must be wall-mounted. Faucets must be freestanding or wall-mounted.

# TO ORDER

Complete the  ${\bf ORDER}$   ${\bf FORM}$  in the  ${\bf bainultra.com/interactive-price-list}$  or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com







# **SANOS** 7240 (FREESTANDING)

# 

LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11 3/4"
В	Outside edge to overflow	4 3/8"
С	Total length	72"
D	Total width	40"
E	Bathing well length	46 1/8"
F	Bathing well width	24 3/4"
G	Deck width	4 5/8"
Н	Flat surface width	3 3/8"
1	Rolled deck width	5 3/8"
J	Height from bottom of lip to top deck	2 1/2"
K	Height from bottom of bath to top deck	25 1/2"
L	Height from bottom of bath to top deck	24 1/2"
М	Height from bottom of drain to center of overflow	16 5/8"
N	Maximum water level	14 7/8"
0	Slope of backrests	27°
P	Base length	55 7/8"
Q	Base width	27 7/8"
R	Center drain to center air intake	5"

TECHNICAL SPECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	
Others	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access). There is a height difference for the rolled deck (see drawing Detail A). Faucets must be freestanding or wall-mounted. The turbine must be remotely installed. TMU: Control must be wall-mounted. TUB: Dot controls are located on either sides of the AromaCloud® (see page 9, position of DOT control).	

Detail A

# 90000001
200 lb
260 lb
550 W
600 W
5 years
20 years

Indicates WarmTouchShell®

position (TUB)

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

The specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.

⚠ AromaCloud® position


Indicates heated backrest (TMU)

 $<sup>\</sup>mbox{*}$  Some restrictions apply | www.bainultra.com/warranty

# **BEONE** 4639

46" x 39" x 30" (FREESTANDING)

The first of its kind, a Japanese style bathtub, BeOne provides an extraordinarily unique bathing experience. The air jets coupled with its circular design create a powerful massage that is unlike any other offered by traditional Air System.



MODEL	тми	TUB	
Freestanding	BBODOF00T-XX	BBODOF00N-XX	

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$9,360
Jets	40
1 heated backrest	Included
MiaPlus® Control* (not installed)	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®	N/A
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$7,280
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type			F	reestanding
No. of bathers	No. of bathers † Imp. gallo			44
US gallons	53	Raised sea	it	1
INTEGRATED WASTE 8	OVERFLO	W BOVERINI-	<b>x</b> p. 10	
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32			Installed & Included	
STANDARD COLOR p.13				
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)	
COLOR p.13	
Black / White 66	\$475
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60



- Don't forget to specify the **finish of the integrated waste & overflow**.
- \* Control must be wall-mounted. Faucets must be freestanding or wall-mounted.
- \*\* An Island Tub Drain™ is required when there is **no access under the bath**, and turbine is installed under the bath.

### TO ORDER

Complete the  ${\bf ORDER\ FORM\ }$  in the  ${\bf bainultra.com/interactive\text{-}price\text{-}list\ }$  or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com












## INSTALLATION



LETTER	DESCRIPTION	MEASURE
Α	Total length	46"
В	Total width	38 3/4"
С	Bathing well length	30 3/4"
D	Bathing well width	27 1/4"
E	Deck width	1 3/8"
F	Outer edge to center of waste	12 3/8"
G	Depth of seat	16 1/4"
Н	Height of seat	5 3/16"
I	Total height at headrest	30"
J	Total height at overflow	27"
K	Slope of backrest	16°
L	Top to seat height	20 5/8"
М	Maximum water level	21 1/2"
N	Base length	41 1/8"
0	Base width	33 7/8"
P	Height from drain to floor	3 5/8"


- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)
- Turbine position (TMU)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000083
supply required		Approx. shipping weight	240 lb
Turbine	Turbine is factory installed, so access to the pump must be at least 18" x 22". Standard connection is 20 A. 120 V, 60 Hz, dedicated line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Turbine power	550 W
		Air heater	600 W
	- The Geysair® is located on the same side as the heated backrest. It must <b>NOT be relocated</b> .	WARRANTY	
Others	It must be <b>connected to the hot water supply</b> and be accessible (provide access).  - Faucet must be freestanding or wall-mounted.	Controls-LED-Geysair*	5 years
	- The turbine can be <b>remotely installed</b> Controls cannot be installed on the deck of the bath.	Bath & turbine*	20 years
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).		* Some restrictions apply   www.bainult	ra.com/warranty

# CHARISM 5736

57" x 36" x 23" (FREESTANDING)

Charism has broken the mold, transcending conventional approaches to therapeutic baths.



MODEL	TMU	TUB
Freestanding	BCH4OF00T-XX	BCH4OF00N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$9,655
Jets	35
1 heated backrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$7,050
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type			F	reestanding
No. of bathers	*	Imp. gallo	ns	41
US gallons	49			
INTEGRATED WASTE &	OVERFLO	N BOVERINI-	xx p. 10	
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installed & Included		
STANDARD COLOR p.13				
White 01				Included
STANDARD DECK COLOR BDECKCO-XX p.13				
White 01			Included	

OPTIONS (UPCHARGE APPLICABLE)		
FINISH p.6		
UltraVelour Matte Finish (white only) BVEL2	\$850	
DECK COLOR BDECKCO-XX p.13		
Black 06 Copper 13 Crystal Rock 17	\$250	
UNIVERSAL ARMRESTS BGBGU-XX p.12		
White 01	\$750	
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10		
Matte Black 19, Satin Brass 18 \$12		
ISLAND TUB DRAIN™** p.11		
Island Tub Drain™ BISLDD	\$260	
Cast Iron Island Tub Drain™ BISLDDCI	\$310	
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit BDRCOB	\$240	
Brass waste kit BDRCB	\$60	

Don't forget that this model is available in White only with choice of deck color. Don't forget to specify the finish of the integrated waste & overflow.

- \* For TMU, control and faucets cannot be installed on deck of the bath.
  \*\* An Island Tub Drain™ is required when there is **no access under** the bath.
- \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

#### TO ORDER

Complete the  $\mathbf{ORDER}$   $\mathbf{FORM}$  in the  $\mathbf{bainultra.com/interactive\text{-}price\text{-}list}$  or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

## FOR THE INSTALLER

**SCAN** TO VIEW INSTALLATION VIDEO (3:20 MIN)






Copper deck color (optional)

# **CHARISM** 5736 (FREESTANDING)



# INSTALLATION E В Air intake F M



LETTER	DESCRIPTION	MEASURE
Α	Total length	57 1/4"
В	Total width	35 7/8"
С	Bathing well length	41 1/2"
D	Bathing well width	23 7/8"
E	Deck width at headrest	2 5/8"
F	Deck width (drain end)	1 1/8"
G	Deck width	1 1/8"
Н	Center bath drain to air intake	3 1/2"
1	Center bath drain to drain hole	4 1/4"
J	Center bath drain to air intake	6 1/2"
K	Outside edge to center bath drain	10 3/4"
L	Total height	23 1/4"
М	Slope at drain end	12°
N	Slope of backrest	31°
0	Base length	47 3/8"
P	Base width	26 7/8"
Q	Maximum water level Maximum water level with AromaFlow	15 7/8" 14 7/8"

- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000070
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	210 lb
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Turbine power	550 W
		Air heater	600 W
	- The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access) Faucet must be freestanding or wall-mounted The turbine must be remotely installed Controls cannot be installed on the bath The water level will be lower when an AromaFlow is installed.	WARRANTY	
Others		Controls-LED-Geysair*	5 years
		Bath & turbine*	20 years

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

\* Some restrictions apply | www.bainultra.com/warranty

# CHARISM 6434

64" x 34" x 24" (FREESTANDING)

Charism has broken the mold, transcending conventional approaches to therapeutic baths.



MODEL	тми	TUB	
Freestanding	BCH2RF00T-XX	BCH2RF00N-XX	

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$11,000
Jets	38
1 heated backrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$8,525
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			F	reestanding
No. of bathers	* *	Imp. gallo	ns	46
US gallons	55			
INTEGRATED WASTE 8	k OVERFLO	W BOVERINI-	xx p. 10	
White 01, Chrome 07, Brus Nickel 10, Matte White w			Installe	d & Included
<b>STANDARD COLOR</b> p.	13			
White 01				Included
STANDARD DECK COL	OR BDECKCO	o-xx p.13		
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)	
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
DECK COLOR BDECKCO-XX p.13	
Black 06 Copper 13 Crystal Rock 17	\$250
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60

Don't forget that this model is available in White only with choice of deck color. Don't forget to specify the finish of the integrated

- waste & overflow.

  \* For TMU, control and faucets cannot be installed on deck of the bath.

  \*\* An Island Tub Drain™ is required when there is **no access under** the bath.
- \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.


#### TO ORDER








## INSTALLATION





LETTER	DESCRIPTION	MEASURE
Α	Total length	64 1/8"
В	Total width	33 7/8"
С	Bathing well length	41 7/8"
D	Bathing well width	21 1/2"
E	Deck width	1 1/8"
F	Deck width at headrest	1 7/8"
G	Center drain to center air intake	3 7/8"
Н	Total height	24 3/4"
I	Maximum water level Maximum water level with AromaFlow	15 7/8" 14 7/8"
J	Slope of backrest	31°
K	Base length	50"
L	Base width	24 1/4"
М	Center drain to center air intake	4 1/4"

- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SP	PECIFICATIONS	
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cuttir
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Appro Turbi
	- The Geysair* is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).	WARI
Others	- Faucet must be freestanding or wall-mounted The turbine must be remotely installed Controls cannot be installed on the deck of the bath The water level will be lower when an AromaFlow is installed.	Contro Bath 8

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

Cutting template	# 90000068
Approx. shipping weight	230 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years

<sup>\*</sup> Some restrictions apply | www.bainultra.com/warranty

# CHARISM OVAL 6436

64" x 36" x 24" (FREESTANDING)

Charism has broken the mold, transcending conventional approaches to therapeutic baths.

BCH3OF00N-XX

# PRODUCT NO. MODEL TUB

BCH3OF00T-XX

Freestanding

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$11,000
Jets	35
1 heated backrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$8,525
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			F	reestanding
No. of bathers	**	Imp. gallo	ns	42
US gallons	51			
INTEGRATED WASTE 8	OVERFLO	N BOVERINI-	xx p.10	
White 01, Chrome 07, Bru Nickel 10, Matte White w			Installe	d & Included
STANDARD COLOR p.	13			
White 01				Included
STANDARD DECK COL	OR BDECKCO	o-xx p.13		
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)		
FINISH p.6		
UltraVelour Matte Finish (white only) BVEL2	\$850	
DECK COLOR BDECKCO-XX p.13		
Black 06 Copper 13 Crystal Rock 17	\$250	
UNIVERSAL ARMRESTS BGBGU-XX p.12		
White 01	\$750	
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10		
Matte Black 19, Satin Brass 18	\$120	
ISLAND TUB DRAIN™** p.11		
Island Tub Drain™ BISLDD	\$260	
Cast Iron Island Tub Drain™ BISLDDCI	\$310	
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit BDRCOB	\$240	
Brass waste kit BDRCB	\$60	

Don't forget that this model is available in White only with choice of deck color. Don't forget to specify the finish of the integrated waste & overflow.

- \* For TMU, control and faucets cannot be installed on deck of the bath.
- \*\* An Island Tub Drain™ is required when there is **no access under** the bath.

  \*\*\* When ordering an AromaFlow, an Integrated waste & overflow
- is mandatory (Included). Specify the finish of the waste.

#### TO ORDER










# **CHARISM OVAL** 6436 (FREESTANDING)

## INSTALLATION



LETTER	DESCRIPTION	MEASURE
Α	Total length	64 1/8"
В	Total width	35 7/8"
С	Bathing well length	41 3/4"
D	Bathing well width	23 5/8"
E	Deck width	1 1/8"
F	Deck width at headrest	2"
G	Center drain to center air intake	3 7/8"
н	Total height	24 3/4"
I	Maximum water level Maximum water level with AromaFlow	15 7/8" 14 7/8"
J	Slope of backrest	31°
К	Base length	50"
L	Base width	26 1/4"
М	Center drain to center air intake	4 1/4"

- Indicates heated backrest (TMU)
- (TUB) Indicates WarmTouchShell® position (TUB)

Hot water supply required The hot water supply should be 70% or more of the bath's total water capacity.	
Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	

The Geysair\* is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).
Faucet must be freestanding or wall-mounted.
The turbine must be remotely installed.
Controls cannot be installed on the deck of the bath.
The water level will be lower when an AromaFlow is installed.

Others

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

Cutting template	# 90000067
Approx. shipping weight	230 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years

<sup>\*</sup> Some restrictions apply | www.bainultra.com/warranty

# ESSENCIA 6838

68" x 38" x 26" (FREESTANDING)

Essencia evokes essence—the elemental aspects of the inner being.



MODEL	тми	TUB
Freestanding	BESPRF00T-XX	BESPRF00N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$11,035
Jets	59
1 heated backrest & headrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®** BAROMAC	\$490
AromaFlow**** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$7,985
AromaCloud®** BAROMAC	\$490
AromaFlow***** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type			F	reestanding
No. of bathers	*	Inverted V		1
US gallons	67	Armrests		2
Imp. gallons	56	Grab bars	(color match)	2
Raised seats	1	Footrest		1
WASTE & OVERFLOW 16" x 35" BOVER16I-XX p. 10				
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11		Installe	d & Included	
STANDARD COLOR p.13				
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)		
COLOR p.13		
Black / White 66	\$475	
FINISH p.6		
UltraVelour Matte Finish (white only) BVEL2	\$850	
CLEAR ACRYLIC GRAB BARS BGBG10-XX p.12		
With Chrome 07 or Brushed Nickel 09 inserts	\$60	
INTEGRATED WASTE & OVERFLOW BOVERIN-XX p. 10		
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32	\$235	
Matte Black 19, Satin Brass 18	\$355	
ISLAND TUB DRAIN™*** p.11		
Island Tub Drain™ BISLDD	\$260	
Cast Iron Island Tub Drain™ BISLDDCI	\$310	
IF REQUIRED BY CONSTRUCTION CODE OR INSTALLED WITH ITD		
Brass waste & overflow kit**** BDRCOB	\$240	
Brass waste kit**** BDRCB	\$60	
16" x 35" Cable driven brass waste & overflow kit BOVERBR	\$240	



Don't forget to specify the  ${\bf finish}~{\bf of}~{\bf the}~{\bf integrated}~{\bf waste}~{\bf \&}~{\bf overflow}.$ \* For TMU, control must be wall-mounted. Faucets must be freestanding or wall-mounted.

- \*\* The AromaCloud® is built into the deck (factory installed).
- \*\*\* An Island Tub Drain™ is required when there is **no access under** the bath. ITD requires the Brass waste kit (BDRCB) if ordered with the Integrated waste & overflow. ITD requires the 16 x 35 Cable driven brass waste & overflow kit (BOVERBR) if ordered with
- the 16 x 35 waste & overflow.

  \*\*\*\* When ordered with integrated waste & overflow.

  \*\*\*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste. With the AromaFlow, the included Grab Bars can not be installed.

#### TO ORDER








# **ESSENCIA** 6838 (FREESTANDING)

# INSTALLATION



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	28 1/4"
В	Deck width	3 3/4"
С	Total length	68"
D	Total width	38"
E	Bathing well length	42"
F	Bathing well width	22 3/8"
G	Bottom bathing well length	32 3/8"
Н	Raised seat length	16 5/8"
I	Height from bottom of bath to top deck	26"
J	Height from bottom of drain to center of overflow	19 3/8"
к	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	17 5/8" 18 9/16" 17 9/16"
L	Slope of backrest	30°
М	Base length	54 1/8"
N	Base width	29 1/4"
S	Minimum spout reach	7 3/4"
Т	Outside edge to overflow	4"
U	Height of footrest	5 1/2"

⚠ AromaCloud® position

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

## FOR THE INSTALLER

SCAN TO VIEW INSTALLATION VIDEO (3:20 MIN)



TECHNICAL SPECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	
Others	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access). Faucet must be freestanding or wall-mounted. The turbine must be remotely installed. TMU: Control must be wall-mounted. The water level will be lower when an AromaFlow is installed. TUB: Dot controls are located on either sides of the AromaCloud®.	

Our products must be installed by certified professionals only and according to our Owner's Manual as well a	s federal,
provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation	and-catalog).

Cutting template	# 90000057
Approx. shipping weight	290 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years

<sup>\*</sup> Some restrictions apply | www.bainultra.com/warranty

# **ESSENCIA DESIGN**

72" x 36" x 24" (FREESTANDING)

Essencia evokes essence—the elemental aspects of the inner being.

## PRODUCT NO.

MODEL	тми	TUB	
Freestanding	BESSOFN0T-XX	BESSOFN0N-XX	

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$10,535
Jets	46
1 heated backrest	Included
MiaPlus® Control* (not installed)	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$7,660
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type			ı	Freestanding
No. of bathers	*	Imp. gallo	ns	46
US gallons	55			
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01			Included	

Essencia Design 7236 with Illuzio Chromatherapy

OPTIONS (UPCHARGE APPLICABLE)		
COLOR p.13		
Black / White 66	\$475	
FINISH p.6		
UltraVelour Matte Finish (white only) BVEL2	\$850	
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10		
Matte Black 19, Satin Brass 18	\$120	
ISLAND TUB DRAIN™** p.11		
Island Tub Drain™ BISLDD	\$260	
Cast Iron Island Tub Drain™ BISLDDCI	\$310	
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit BDRCOB	\$240	
Brass waste kit BDRCB	\$60	



- Don't forget to specify the **finish of the integrated waste & overflow**.

  \* For TMU, control must be wall-mounted. Faucets must be freestanding
  - or wall-mounted.
  - \*\* An Island Tub Drain™ is required when there is **no access under** the bath.

    \*\*\* When ordering an AromaFlow, an Integrated waste & overflow
  - is mandatory (Included). Specify the finish of the waste.

## TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

#### FOR THE INSTALLER

**SCAN** TO VIEW INSTALLATION VIDEO (3:20 MIN)










# ESSENCIA DESIGN (FREESTANDING)

## INSTALLATION



-Q

LETTER	DESCRIPTION	MEASURE
Α	Total length	72"
В	Total width	36"
С	Bathing well length (at jets height)	44 7/8"
D	Bathing well width (at jets height)	22 5/8"
E	Deck width (top)	1 5/8"
F	Deck width (backrest round edge)	3 1/2"
G	Deck width (side round edge)	3 1/8"
н	Center drain to center air intake (long axis)	3 1/2"
ı	Center drain to center air intake (trans axis)	3 1/2"
J	Center drain to deck edge	30 1/2"
К	Bath height	24"
L	Height from bottom of drain to top of deck	19 1/4"
М	Maximum water level Maximum water level with AromaFlow	16 3/4" 13 3/4"
N	Slope	40°
0	Slope of backrest	29°
P	Base length	32 3/8"
Q	Base width	19"

- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000071
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	305 lb
Turbine line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is		Turbine power	550 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W
	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.     It must be connected to the hot water supply and be accessible (provide access).</li> <li>Faucet must be freestanding or wall-mounted.</li> <li>The turbine must be remotely installed.</li> </ul>	WARRANTY	
Others		Controls-LED-Geysair*	5 years
	- TMU: Control must be wall-mounted The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years


Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

\* Some restrictions apply  $\mid$  www.bainultra.com/warranty

# ESSENCIA OVAL 7236

72" x 36" x 27" (FREESTANDING)

Essencia evokes essence—the elemental aspects of the inner being.



MODEL	тми	TUB
Freestanding	BESSOF00T-XX	BESSOF00N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$10,995
Jets	46
1 heated backrest & headrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®** BAROMAC	\$490
AromaFlow**** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$7,960
AromaCloud®** BAROMAC	\$490
AromaFlow**** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type			F	reestanding
No. of bathers	*	Inverted V		1
US gallons	61	Armrests		2
Imp. gallons	51	Grab bars	(color match)	2
Raised seat	1	Footrest		Included
WASTE & OVERFLOW 16" x 35" BOVER16I-XX p. 10				
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11		Installe	d & Included	
STANDARD COLOR p.13				
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)	
CLEAR ACRYLIC GRAB BARS BGBG10-XX p.12	
With Chrome 07 or Brushed Nickel 09 inserts	\$60
ISLAND TUB DRAIN™*** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE OR INSTALLED WITH ITD	
16" x 35" Cable driven brass waste & overflow kit BOVERBR	\$240



- Don't forget that this model is available in **White only**.

  Don't forget to specify the **finish of the waste & overflow**.

  \* For TMU, control must be wall-mounted. Faucets must be freestanding or wall-mounted.
  - \*\* The AromaCloud® is built into the deck (factory installed).
  - \*\*\* An Island Tub Drain™ is required when there is **no access under the bath**. ITD is compatible only with the 16" x 35" Cable driven brass waste & overflow kit.
  - \*\*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.

#### TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

#### FOR THE INSTALLER

**SCAN** TO VIEW INSTALLATION VIDEO (3:20 MIN)










# **ESSENCIA OVAL** 7236 (FREESTANDING)



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	30 1/2"
В	Outside edge to overflow	20 1/2"
С	Total length	72"
D	Total width	36"
E	Bathing well length	45 1/4"
F	Bathing well width	21"
G	Bottom bathing well length	38"
Н	Raised seat length	22 5/8"
1	Total height to headrest	27 3/8"
J	Height from bottom of bath to top deck	26"
К	Height from bottom of drain to center of overflow	18 3/8"
L	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	16 5/8" 16 9/16"
М	Slope of backrest	30°
N	Base length	32 3/8"
0	Base width	19"
P	Center drain to center air intake	7 7/16"
Q	Center drain to center air intake	2 1/2"
U	Minimum spout reach	6 3/8"
V	Height of footrest	5 1/2"

⚠ AromaCloud® position Indicates heated backrest (TMU) Indicates WarmTouchShell® position (TUB)

Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.
Others	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).  Faucet must be freestanding or wall-mounted. The turbine must be remotely installed.  TMU: Control must be wall-mounted. The water level will be lower when an AromaFlow is installed.  TUB: Dot controls are located on the side of the AromaCloud®.

Cutting template	# 90000056
Approx. shipping weight	305 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years

 $<sup>\</sup>mbox{*}$  Some restrictions apply | www.bainultra.com/warranty

# ESTHESIA 6436

64" x 36" x 25" (FREESTANDING)

Esthesia, the new expression of beauty in the world of therapeutic baths. Neoclassically inspired Esthesia baths boast clean, purely geometric designs. Their elegant, luxurious pedigree means they're right at home in almost any cultural or architectural setting.



MODEL	тми	TUB
Freestanding	BEA3RF00T-XX	BEA3RF00N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$9,510
Jets	38
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$6,900
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			Freestanding	
No. of bathers	**	Imp. gallor	ns	49
US gallons	59			
INTEGRATED WASTE &	INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10			
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)	
COLOR p.13	
Black / White 66	\$835
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL3	\$1,025
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60

- Don't forget to specify the **finish of the integrated waste & overflow**.
  - \* The AromaCloud® is built into the deck (factory installed).
  - \*\* An Island Tub Drain™ is required when there is no access under
  - the bath.
    \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

#### TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com



82










# ESTHESIA 6436 (FREESTANDING)

## INSTALLATION







LETTER	DESCRIPTION	MEASURE
Α	Total length	64"
В	Total width	36"
С	Bathing well length	47 3/8"
D	Bathing well width	23"
E	Deck width	1 5/8"
F	Deck width at headrest	1 5/8"
G	Center drain to center air intake	3 1/2"
Н	Total height	25"
ı	Slope of backrest	26°
J	Slope of backrest	21°
К	Base length	49 5/8"
L	Base width	23 7/8"
М	Maximum water level Maximum water level with AromaFlow	15 7/8" 15 1/8"
N	Center drain to center air intake	2 3/4"

- ⚠ AromaCloud® position
- **ⓒ** Control position when factory-installed (Mia® or DOT)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000066
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	240 lb
Turbine line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is		Turbine power	550 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W
	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	WARRANTY	
	- Faucet must be freestanding or wall-mounted The turbine must be <b>remotely installed</b> .	Controls-LED-Geysair*	5 years
	- The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years


Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

 $\mbox{*}$  Some restrictions apply | www.bainultra.com/warranty

# **EVANESCENCE** 5936

59" x 36" x 28" (FREESTANDING)

Evanescence means "state of transformation." The collection is an invitation to turn your relaxation space into a sanctuary of luxury and wellness.



MODEL	тми	TUB
Freestanding	BEVFOF00T-XX	BEVFOF00N-XX

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$9,325
Jets	35
1 heated backrest & headrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$6,735
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type			F	reestanding
No. of bathers	*	Imp. gallo	ns	41
US gallons	49	Raised hea	adrest	1
INTEGRATED WASTE 8	INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10			
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)	
COLOR p.13	
Black / White 66	\$475
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60

- Don't forget to specify the **finish of the integrated waste & overflow**.
  - \* For TMU, control must be wall-mounted. Faucets must be freestanding or wall-mounted.
  - \*\* An Island Tub Drain<sup>™</sup> is required when there is  $\mathbf{no}$  access under
  - the bath.

    \*\*\* When ordering an AromaFlow, an Integrated waste & overflow

    \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

#### TO ORDER












# **EVANESCENCE** 5936 (FREESTANDING)

## INSTALLATION



LETTER	DESCRIPTION	MEASURE
Α	Total length	59"
В	Total width	36"
С	Bathing well length	41 1/2"
D	Bathing well width	23 7/8"
E	Deck width at drain end	1"
F	Deck width at headrest	1 1/8"
G	Deck width	1 1/8"
н	Center bath drain to air intake	3 1/2"
ı	Center bath drain to air intake	6 1/2"
J	Outside edge to center bath drain	11"
К	Total height	24 1/2"
L	Minimum height of bath	23 1/2"
М	Total height to headrest	28 1/2"
N	Slope at drain end	12°
0	Slope of backrest	31°
P	Base length	47 3/8"
Q	Base width	26 7/8"
R	Maximum water level Maximum water level with AromaFlow	15 7/8" 15 5/16"

- Indicates heated backrest (TMU)
- (TUB) Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000069
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz,</b> dedicated	Approx. shipping weight	220 lb
Turbine	Turbine line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Turbine power	550 W
		Air heater	600 W
Others It mu - Fauc - The t - Cont	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).</li> <li>Faucet must be freestanding or wall-mounted.</li> <li>The turbine must be remotely installed.</li> <li>Controls cannot be installed on the bath.</li> <li>The water level will vary when an AromaFlow is installed.</li> </ul>	WARRANTY	
		Controls-LED-Geysair*	5 years
		Bath & turbine*	20 years


Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

\* Some restrictions apply | www.bainultra.com/warranty

# EVANESCENCE 6634

66" x 34" x 28" (FREESTANDING)

Evanescence means "state of transformation." The collection is an invitation to turn your relaxation space into a sanctuary of luxury and wellness.



MODEL	TMU	TUB
Freestanding	BEVKRF00T-XX	BEVKRF00N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$10,420
Jets	38
1 heated backrest & headrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$7,800
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			Freestanding	
No. of bathers	* *	Imp. gallo	ns	46
US gallons	55	Raised hea	adrests	2
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01			Included	

OPTIONS (UPCHARGE APPLICABLE)		
COLOR p.13		
Black / White 66	\$475	
FINISH p.6		
UltraVelour Matte Finish (white only) BVEL2	\$850	
UNIVERSAL ARMRESTS BGBGU-XX p.12		
White 01	\$750	
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10		
Matte Black 19, Satin Brass 18	\$120	
ISLAND TUB DRAIN™** p.11		
Island Tub Drain™ BISLDD	\$260	
Cast Iron Island Tub Drain™ BISLDDCI	\$310	
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit BDRCOB	\$240	
Brass waste kit BDRCB	\$60	

- Don't forget to specify the **finish of the integrated waste & overflow**. \* For TMU, control must be wall-mounted. Faucets must be freestanding or wall-mounted.
  - \*\* An Island Tub Drain<sup>™</sup> is required when there is  $\mathbf{no}$  access under
  - the bath.

    \*\*\* When ordering an AromaFlow, an Integrated waste & overflow

    \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

#### TO ORDER













# 

LETTER	DESCRIPTION	MEASURE
Α	Total length	66"
В	Total width	34"
С	Bathing well length	41 7/8"
D	Bathing well width	21 1/2"
E	Deck width	1 1/4"
F	Center drain to center air intake	3 7/8"
G	Total height to headrest	28"
Н	Minimum height to center	25"
ı	Maximum water level Maximum water level with AromaFlow	15 7/8" 15 5/16"
J	Base length	50"
К	Base width	24 1/4"
L	Slope of backrest	31°
М	Center drain to center air intake	4 1/4"

- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000065
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	230 lb
Turbine	irrbine line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Turbine power	550 W
		Air heater	600 W
Others   It n   - Fau   - The   - Col	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).</li> <li>Faucet must be freestanding or wall-mounted.</li> <li>The turbine must be remotely installed.</li> <li>Controls cannot be installed on the deck of the bath.</li> <li>The water level will vary when an AromaFlow is installed.</li> </ul>	WARRANTY	
		Controls-LED-Geysair*	5 years
		Bath & turbine*	20 years

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

 $\mbox{\tt *}$  Some restrictions apply | www.bainultra.com/warranty

# EVANESCENCE OVAL 6636

66" x 36" x 28" (FREESTANDING)

Evanescence means "state of transformation." The collection is an invitation to turn your relaxation space into a sanctuary of luxury and wellness.

## PRODUCT NO.

MODEL	тми	TUB		
Freestanding	BEVLOF00T-XX	BEVLOF00N-XX		

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$10,420
Jets	35
1 heated backrest & headrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$7,800
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			Freestanding	
No. of bathers	**	Imp. gallo	ns	42
US gallons	51	Raised hea	adrests	2
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01			Included	

OPTIONS (UPCHARGE APPLICABLE)	
COLOR p.13	
Black / White 66	\$475
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60



- Don't forget to specify the **finish of the integrated waste & overflow**. \* For TMU, control must be wall-mounted. Faucets must be freestanding or wall-mounted.
  - \*\* An Island Tub Drain<sup>™</sup> is required when there is  $\mathbf{no}$  access under the bath.
  - \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

#### TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

## FOR THE INSTALLER **SCAN** TO VIEW INSTALLATION VIDEO (3:20 MIN)









# Air intake M E INSTALLATION A D B G H

LETTER	DESCRIPTION	MEASURE
Α	Total length	66"
В	Total width	36"
С	Bathing well length	41 3/4"
D	Bathing well width	23 5/8"
E	Deck width	1 1/4"
F	Center drain to center air intake	3 7/8"
G	Total height to headrest	28"
Н	Minimum height to center	25"
I	Maximum water level Maximum water level with AromaFlow	15 7/8" 15 5/16"
J	Base length	50"
K	Base width	26 1/4"
L	Slope of backrests	31°
М	Center drain to center air intake	4 1/4"

- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000064
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	230 lb
Turbine	irrbine line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Turbine power	550 W
		Air heater	600 W
	- The Geysair® is located on the same side as the heated backrest. It must <b>NOT be relocated</b> .  It must be <b>connected to the hot water supply</b> and be accessible (provide access).	WARRANTY	
		Controls-LED-Geysair*	5 years
	- Controls cannot be installed on the bath The water level will vary when an AromaFlow is installed.	Bath & turbine*	20 years

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

 $\hbox{* Some restrictions apply} \mid \hbox{www.bainultra.com/warranty}$ 

# EVANESCENCE OVAL 7440

74" x 40" x 28" (FREESTANDING)

Evanescence means "state of transformation." The collection is an invitation to turn your relaxation space into a sanctuary of luxury and wellness.



MODEL	тми	TUB
MODEL	TIMO	IUB
Freestanding	BEVUOF00T-XX	BEVUOF00N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$10,685
Jets	41
1 heated backrest & headrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$8,205
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			Freestanding	
No. of bathers	* *	Imp. gallo	ns	57
US gallons	68	68 Raised headrests		2
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)	
COLOR p.13	
Black / White 66	\$475
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60



- Don't forget to specify the **finish of the integrated waste & overflow**. \* For TMU, control must be wall-mounted. Faucets must be freestanding or wall-mounted.
  - \*\* An Island Tub Drain<sup>™</sup> is required when there is  $\mathbf{no}$  access under the bath.
  - \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.


#### TO ORDER







# **EVANESCENCE OVAL** 7440 (FREESTANDING)



K

LETTER	DESCRIPTION	MEASURE
Α	Total length	74"
В	Total width	40"
С	Bathing well length	49 1/2"
D	Bathing well width	27 5/8"
E	Deck width	1 1/4"
F	Center drain to center air intake	3 7/8"
G	Total height to headrest	28"
Н	Minimum height to center	24"
I	Maximum water level Maximum water level with AromaFlow	15 7/8" 15 5/16"
J	Base length	58"
К	Base width	30 5/8"
L	Slope of backrests	29°
M	Center drain to center air intake	4 1/4"

- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS				
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000074	
supply required			260 lb	
Turbine			550 W	
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W	
Others It r	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).</li> <li>Faucet must be freestanding or wall-mounted.</li> <li>The turbine must be remotely installed.</li> </ul>	WARRANTY		
		Controls-LED-Geysair*	5 years	
	- Controls cannot be installed on the bath The water level will vary when an AromaFlow is installed.	Bath & turbine*	20 years	
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).		* Some restrictions apply   www.bainul	tra.com/warranty	

Libra's symmetrical lines and universal look will be a perfect fit in any style bathroom. The identical soft slope of the interior walls brings comfort and relaxation for one or two bathers.



## PRODUCT NO.

MODEL	тми	TUB
Freestanding	BLIIRF00T-XX	BLIIRF00N-XX

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$8,850
Jets	42
1 heated backrest	Included
MiaPlus® Control* (not installed)	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$6,500
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			F	reestanding
No. of bathers	* *	Imp. gallo	ns	52
US gallons	63			
INTEGRATED WASTE &	OVERFLO	W BOVERINI-)	<b>X</b> p. 10	
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01				Included

COLOR p.13		

**OPTIONS (UPCHARGE APPLICABLE)** 

Black / White 66	\$475
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60



- Don't forget to specify the **finish of the integrated waste & overflow**.
  - \* Control must be wall-mounted. Faucets must be freestanding
  - or wall-mounted. \*\*\* An Island Tub Drain™ is recommended when there is **no access under** the bath.
  - \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.


Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

#### FOR THE INSTALLER

**SCAN** TO VIEW INSTALLATION VIDEO (3:20 MIN)













# LIBRA 6632 (FREESTANDING)

## INSTALLATION





LETTER	DESCRIPTION	MEASURE
Α	Total length	66"
В	Total width	32"
С	Bathing well length	47 1/2"
D	Bathing well width	21 1/2"
E	Deck width	1 3/8"
F	Center waste to air intake (side)	3 1/8"
G	Center waste to air intake (front)	3 1/2"
Н	Total height	23"
ı	Maximum water level Maximum water level with AromaFlow	16 3/8" 14 3/4"
J	Slope of backrests	26°
К	Base length	57 1/4"
L	Base width	26 1/4"
М	The outer edge to center of waste	16 3/8"
N	Height from drain to floor	3 1/2"

- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	
Turbine	Turbine is remotely installed; access to to the pump must be at least 18" x 22". <b>Standard connection</b> is 20 A. 120 V, 60 Hz, dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option</b> , a <b>second line is needed 15 A. 120 V</b> , <b>60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	
Others	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access). Faucet must be freestanding or wall-mounted. The turbine must be remotely installed. Controls cannot be installed on the deck of the bath. The water level will be lower when an AromaFlow is installed.	

onal	Turbine power
	Air heater
	WARRANTY
	Controls-LED-Geysair*
	Bath & turbine*

**Cutting template** 

Approx. shipping weight

Bath & turbine\* 20 years

\* Some restrictions apply | www.bainultra.com/warranty

# 90000082

240 lb

550 W 600 W

5 years

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

# IBRA AURORA 6634

66" x 34" x 24" (FREESTANDING)

Libra's symmetrical lines and universal look will be a perfect fit in any style bathroom. The identical soft slope of the interior walls brings comfort and relaxation for one or two bathers.



TRODUCTINO.				
MODEL	тми	TUB		
Freestanding	BLAKOF00T-XX	BLAKOF00N-XX		

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$9,330
Jets	40
1 heated backrest	Included
MiaPlus® Control* (not installed)	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$6,980
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			F	reestanding
No. of bathers	* *	Imp. gallo	ns	48
US gallons	58			
INTEGRATED WASTE 8	OVERFLO	W BOVERINI-)	<b>X</b> p. 10	
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)	
COLOR p.13	
Black / White 66	\$475
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60

- Don't forget to specify the **finish of the integrated waste & overflow**.
  - \* Control must be wall-mounted. Faucets must be freestanding or wall-mounted. \*\*\* An Island Tub Drain™ is recommended when there is **no access under**
  - the bath.
  - \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.








# LIBRA AURORA 6634 (FREESTANDING)

## INSTALLATION



LETTER	DESCRIPTION	MEASURE
Α	Total length	66"
В	Total width	34"
С	Bathing well length	44 1/16"
D	Bathing well width	21"
E	Deck width	1 7/16"
F	Center waste to air intake (side)	4 1/2"
G	Maximum total height	24"
Н	Height of deck upper lip	3"
I	Base length	55"
J	Slope of backrests	30°
K	Maximum water level Maximum water level with AromaFlow	17 5/16" 15 15/16"
L	Base width	27"
М	Height from drain to floor	3 1/2"

- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS				
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.			
Turbine	Turbine is remotely installed; access to to the pump must be at least 18" x 22". <b>Standard connection</b> is 20 A. 120 V, 60 Hz, dedicated line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.			
Others	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access). Faucet must be freestanding or wall-mounted. The turbine must be remotely installed. Controls cannot be installed on the deck of the bath. The water level will be lower when an AromaFlow is installed.			

Cutting template	# 90000087
Approx. shipping weight	230 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years

 $<sup>\</sup>mbox{*}$  Some restrictions apply | www.bainultra.com/warranty

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

# LIBRA OVAL 6635

66" x 35" x 27" (FREESTANDING)

Libra's symmetrical lines and universal look will be a perfect fit in any style bathroom. The identical soft slope of the interior walls brings comfort and relaxation for one or two bathers.



THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$9,750
Jets	34
1 heated backrest	Included
MiaPlus® Control* (not installed)	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$7,340
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type	Installation type		Freestanding	
No. of bathers	* *	Imp. gallo	ns	46
US gallons	56	Armrests		2
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)	
COLOR p.13	
Black / White 66	\$475
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL3	\$1,025
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60



- Don't forget to specify the **finish of the integrated waste & overflow**.
- \* Control must be wall-mounted. Faucets must be freestanding or wall-mounted.
- \*\* An Island Tub Drain™ is recommended when there is **no access under** the bath.
- \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.


#### TO ORDER







#### EIDITA OVAL 0000 (I KEESTANDII



\	K
o	
-1	

Total langth	
rotal length	66"
Total width	35"
Bathing well length	42 3/8"
Bathing well width	23 3/16"
Deck width	1 1/2"
Center waste to air intake (side)	3 1/2"
Center waste to air intake (front)	3 1/2"
Maximum total height	27"
Minimum total height	24"
Maximum water level Maximum water level with AromaFlow	17 3/8" 15 3/4"
Slope of backrests	31°
Base length	44"
Base width	18"
The outer edge to center of waste	17 1/2"
Height from drain to floor	3 1/2"
	Bathing well length Bathing well width Deck width Center waste to air intake (side) Center waste to air intake (front) Maximum total height Minimum total height Maximum water level Maximum water level with AromaFlow Slope of backrests Base length Base width The outer edge to center of waste

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SP	ECIFICATIONS	
Hot water	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting templat
supply required  Turbine	Turbine is remotely installed; access to to the pump must be at least 18" x 22". <b>Standard connection</b> is <b>20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional</b>	Approx. shippin
		Turbine power
	option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater
Others	- The Geysair® is located on the same side as the heated backrest. It must <b>NOT be relocated</b> .	WARRANTY
	It must be <b>connected to the hot water supply</b> and be accessible (provide access).  - Faucet must be freestanding or wall-mounted.	Controls-LED-Ge
	- The turbine must be <b>remotely installed</b> Controls cannot be installed on the deck of the bath.	Bath & turbine*
	- Controls cannot be installed on the deck of the bath.  The water level will be lower when an AromaFlow is installed	* Como rostrictions an

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

Cutting template	# 90000086
Approx. shipping weight	230 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years

 $<sup>\</sup>mbox{*}$  Some restrictions apply | www.bainultra.com/warranty

NEW

# LIBRA STELLA 7038

70" x 38" x 25" (FREESTANDING)

Libra's symmetrical lines and universal look will be a perfect fit in any style bathroom. The identical soft slope of the interior walls brings comfort and relaxation for one or two bathers.



MODEL	тми	TUB	
Freestanding	BLIZRF00T-XX	BLIZRF00N-XX	

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$9,910
Jets	40
1 heated backrest	Included
MiaPlus® Control* (not installed)	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$7,440
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type		Freestanding		
No. of bathers	* *	Imp. gallo	ns	53
US gallons	63	63 Armrests		2
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installed	d & Included	
STANDARD COLOR p.13				
White 01			Included	

OPTIONS (UPCHARGE APPLICABLE)		
COLOR p.13		
Black / White 66	\$475	
FINISH p.6		
UltraVelour Matte Finish (white only) BVEL3	\$1,025	
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10		
Matte Black 19, Satin Brass 18	\$120	
ISLAND TUB DRAIN™** p.11		
Island Tub Drain™ BISLDD	\$260	
Cast Iron Island Tub Drain™ BISLDDCI	\$310	
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit BDRCOB	\$240	
Brass waste kit BDRCB	\$60	



- Don't forget to specify the **finish of the integrated waste & overflow**.
  - \* Control must be wall-mounted. Faucets must be freestanding or wall-mounted.
  - \*\* An Island Tub Drain™ is recommended when there is  $\mathbf{no}$  access under the bath.
  - \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

#### TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

## FOR THE INSTALLER **SCAN** TO VIEW INSTALLATION VIDEO (3:20 MIN)










# INSTALLATION



LETTER	DESCRIPTION	MEASURE
Α	Total length	70"
В	Total width	38"
С	Bathing well length	47"
D	Bathing well width	21 1/4"
E	Deck width (side)	4 3/16"
F	Deck width (end)	1 1/2"
G	Center waste to air intake	3 1/2"
Н	Maximum total height	25"
I	Minimum total height	23"
J	Slope of backrests	30°
K	Base length	43 3/16"
L	Base width	23 3/16"
М	Maximum water level Maximum water level with AromaFlow	16 5/16" 14 5/8"
N	Height from drain to floor	3 1/2"

- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.		
Turbine is remotely installed; access to to the pump must be at least 18" x 22". Standard connection is 20 A. 120 V, 60 Hz, dedicated line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.			
Others	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access). Faucet must be freestanding or wall-mounted. The turbine must be remotely installed. Controls cannot be installed on the deck of the bath.		

Turbine power	550 W
rurbine power	330 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years

# 90000086

230 lb

20 years

**Cutting template** 

Bath & turbine\*

Approx. shipping weight

- The water level will be lower when an AromaFlow is installed.

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

* Some restrictions apply	www.bainultra.com/warranty
---------------------------	----------------------------

# **NOKORI** 6331

63" x 31" x 24" (FREESTANDING)

Nokori's sleek and delicate lines inspire peace and calm-offering an authentic invitation to unwind.



Freestanding	BNOLRF00T-XX	BNOLRF00N-XX
THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system		\$10,160
Jets		40
1 heated backrest		Included
MiaPlus® Control* (not installed)		Included
BU-Touch Control Application BUTOUCH		\$430
Geysair®		Included
AromaCloud®		N/A
AromaFlow**** BAROMAF NEW		\$950
Illuzio Chromatherapy BCHRO6		\$925

TUB Soaker	\$7,840
AromaCloud®	N/A
AromaFlow**** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control (not installed)	Included with therapy

FEATURES				
Installation type Freestandir			reestanding	
No. of bathers	*	Imp. gallo	ns	56
US gallons	68	Brass was	te kit	Included
INTEGRATED WASTE &	OVERFLO	W BOVERINI-)	xx p. 10	
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p. 13				
White 01			Included	

OPTIONS (UPCHARGE APPLICABLE)	
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
TILE FLANGE (specify position) p.11	
Ordered with bath (not installed) BTILEN	\$79
Factory-installed. Right BTILER, Left BTILEL, Front BTILEF, Back BTILEB, Special installation BTILEO	\$155
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
AIR INTAKE** & ISLAND TUB DRAIN™*** p.11	
Air intake & Island Tub Drain™ BAIRISLD	\$350
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
Air intake BAIRINT	\$120
Air intake installation	\$285 net
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240



Don't forget that this bath is available in **White only**. If turbine is installed under the bath, please follow the installation instructions specified in the Nokori Installation Manual.

- \* For TMU, control must be wall-mounted. Faucets must be freestanding or wall-mounted.
- \*\* Air Intake is required if turbine is installed under the bath.
- \*\*\* An Island Tub Drain™ is required when there is no access under the bath.
- \*\*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.

#### TO ORDER









# **NOKORI** 6331 (FREESTANDING)

## INSTALLATION







LETTER	DESCRIPTION	MEASURE
Α	Total length	63"
В	Bathing well length	47 1/4"
С	Total width	31"
D	Bathing well width	22 1/4"
E	Deck width	1 7/8"
F	Deck width at drain end	2"
G	Deck width at backrest	1 1/2"
Н	Slope of backrest	24°
ı	Outside edge to center of drain	10"
J	Height from bottom of drain to top of deck	20 7/8"
K	Maximum water level Maximum water level with AromaFlow	17" 16 1/2"
L	Total height	24"

- Turbine position (TMU)
- Indicates heated backrest (TMU)

## FOR THE INSTALLER **SCAN**

TO VIEW INSTALLATION VIDEO (3:20 MIN)



TECHNICAL SE	PECIFICATIONS	
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Turbine power
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Air heater
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 8 sq. in. minimum.	WARRANTY
The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).  Faucet must be freestanding or wall-mounted.  Others  Controls cannot be installed on the bath.	It must be <b>connected to the hot water supply</b> and be accessible (provide access).	Controls-LED-Geysair*
		Bath & turbine*
	The turbine should be <b>remotely installed</b> .     The turbine can also be installed under the bath. <b>Please refer to the Nokori Installation Instructions</b> .     The water level will be lower when an Aroma Flow is installed.	* Some restrictions apply   www.bair

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).


Approx. shipping weight	260 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years

ainultra.com/warranty

# **NOKORI** 6429

64" x 29" x 23" (FREESTANDING)

Nokori's sleek and delicate lines inspire peace and calm-offering an authentic invitation to unwind.



rreestariding	BITOIN 001 700	BITCH COIT 700
THERMOMASSEUR (TN Hydro-thermo massag		\$9,790
Jets		44
1 heated backrest		Included
MiaPlus® Control* (not ins	stalled)	Included
BU-Touch Control Applic	ation BUTOUCH	\$430
Geysair®		Included
AromaCloud®		N/A
AromaFlow**** BAROMA	NEW	\$950
Illuzio Chromatherapy Bo	CHRO6	\$925

<b>TUB</b> Soaker	\$7,445
AromaCloud®	N/A
AromaFlow**** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type		F	Freestanding	
No. of bathers	*	Imp. gallons		46
US gallons	55	Brass waste kit		Included
INTEGRATED WASTE 8	k OVERFLO	N BOVERINI-)	<b>x</b> p. 10	
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)	
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
TILE FLANGE (specify position) p. 11	
Ordered with bath (not installed) BTILEN	\$79
Factory-installed. Right BTILER, Left BTILEL, Front BTILEF, Back BTILEB, Special installation BTILEO	\$155
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
AIR INTAKE** & ISLAND TUB DRAIN™*** p.11	
Air intake & Island Tub Drain™ BAIRISLD	\$350
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
Air intake BAIRINT	\$120
Air intake installation	\$285 net
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240



Don't forget that this bath is available in **White only**. If turbine is installed under the bath, please follow the installation instructions specified in the Nokori Installation Manual.

- \* Control must be wall-mounted. Faucets must be freestanding or wall-mounted.
- \*\* Air Intake is required if turbine is installed under the bath.
- \*\*\* An Island Tub Drain™ is required when there is no access under the bath.
- \*\*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

#### TO ORDER









# **NOKORI** 6429 (FREESTANDING)

## INSTALLATION







LETTER	DESCRIPTION	MEASURE
Α	Total length	64"
В	Bathing well length	49 1/2"
С	Total width	29"
D	Bathing well width	20 7/8"
E	Deck width	2 1/8"
F	Deck width at drain end	2 1/8"
G	Deck width at backrest	7/8"
Н	Slope of backrest	24°
1	Outside edge to center of drain	9 3/4"
J	Height from bottom of drain to top of deck	19"
K	Maximum water level Maximum water level with AromaFlow	15" 14 1/2"
L	Total height	23"

- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

# FOR THE INSTALLER SCAN





TECHNICAL SPECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 8 sq. in. minimum.	
Others	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access). Faucet must be freestanding or wall-mounted. Controls cannot be installed on the bath. The turbine should be remotely installed. The turbine can also be installed under the bath. Please refer to the Nokori Installation Instructions. The water level will be lower when an Aroma-Flow is installed.	

Approx. shipping weight	250 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years
C	

<sup>\*</sup> Some restrictions apply | www.bainultra.com/warranty

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

# NOKORI OVAL 6737

67" x 37" x 24" (FREESTANDING)

Nokori's sleek and delicate lines inspire peace and calm-offering an authentic invitation to unwind.



#### PRODUCT NO.

MODEL	тми	TUB
Freestanding	BNOPOF00T-XX	BNOPOF00N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$10,380
Jets	40
1 heated backrest	Included
MiaPlus® Control* (not installed)	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$7,445
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control (not installed)	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES						
Installation type		Freestanding				
No. of bathers	* *	Imp. gallons		55		
US gallons	66	Brass waste kit		Included		
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10						
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installed & Included				
STANDARD COLOR p.13						
White 01				Included		

OPTIONS (UPCHARGE APPLICABLE)			
COLOR p.13			
Black / White 66	\$475		
FINISH p.6			
UltraVelour Matte Finish (white only) BVEL2	\$850		
UNIVERSAL ARMRESTS BGBGU-XX p.12			
White 01	\$750		
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10			
Matte Black 19, Satin Brass 18	\$120		
ISLAND TUB DRAIN™** p.11			
Island Tub Drain™ BISLDD	\$260		
Cast Iron Island Tub Drain™ BISLDDCI	\$310		
IF REQUIRED BY CONSTRUCTION CODE			
Brass waste & overflow kit BDRCOB	\$240		




- \* Control must be wall-mounted. Faucets must be freestanding or wall-mounted.
  - \*\* An Island Tub Drain™ is required when there is no access under
  - the bath.

    \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

## TO ORDER


Complete the  ${\bf ORDER\ FORM\ }$  in the  ${\bf bainultra.com/interactive\text{-}price\text{-}list\ }$  or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com












#### INSTALLATION



LETTER	DESCRIPTION	MEASURE
Α	Total length	66 1/2"
В	Total width	37"
С	Bathing well length	45 3/4"
D	Bathing well width	26 1/4"
E	Deck width	2 7/8"
F	Air intake to center of drain (long axis)	21 3/4"
G	Air intake to center of drain (trans axis)	10 3/8"
Н	Center of drain to deck side	9 3/4"
I	Total height	24"
J	Height from bottom of drain to top of deck	20 1/2"
K	Maximum water level Maximum water level with AromaFlow	16 1/8" 15 5/8"
L	Slope of backrests	24°
М	Base length	60 3/4"
N	Base width	32"

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000072
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	270 lb
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power	550 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 8 sq. in. minimum.	Air heater	600 W
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).</li> <li>Faucet must be freestanding or wall-mounted.</li> <li>Controls cannot be installed on the bath.</li> <li>The turbine should be remotely installed Detailed plan available on bainultra.com.</li> <li>The water level will be lower when an AromaFlow is installed.</li> </ul>	WARRANTY	
		Controls-LED-Geysair*	5 years
		Bath & turbine*	20 years
	be installed by certified professionals only and according to our Owner's Manual as well as federal, d local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainult	ra.com/warranty

# **NOKORI** 6935

69" x 35" x 24" (FREESTANDING)

Nokori's sleek and delicate lines inspire peace and calm-offering an authentic invitation to unwind.



MODEL	тми	TUB	
Freestanding	BNOVRF00T-XX	BNOVRF00N-XX	

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$10,620
Jets	44
1 heated backrest	Included
MiaPlus® Control* (not installed)	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud <sup>®</sup>	N/A
AromaFlow**** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$8,255
AromaCloud®	N/A
AromaFlow**** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control (not installed)	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES					
Installation type	F	reestanding			
No. of bathers	No. of bathers			65	
US gallons	US gallons 78 Brass wast		te kit	Included	
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10					
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32			Installe	d & Included	
STANDARD COLOR p. 13					
White 01				Included	

OPTIONS (UPCHARGE APPLICABLE)	
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
TILE FLANGE (specify position) p.11	
Ordered with bath (not installed) BTILEN	\$79
Factory-installed. Right BTILER, Left BTILEL, Front BTILEF, Back BTILEB, Special installation BTILEO	\$155
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
AIR INTAKE** & ISLAND TUB DRAIN™*** p.11	
Air intake & Island Tub Drain™ BAIRISLD	\$350
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
Air intake BAIRINT	\$120
Air intake installation	\$285 net
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240



Don't forget that this model is available in **White only**. If turbine is installed under the bath, please follow the installation instructions specified in the Nokori Installation Manual.

- \* Control must be wall-mounted. Faucets must be freestanding
- or wall-mounted.
  \*\* Air Intake is required if turbine is installed under the bath.
- \*\*\* An Island Tub Drain™ is required when there is no access under
- \*\*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.









#### **NOKORI** 6935 (FREESTANDING)

#### INSTALLATION





LETTER	DESCRIPTION	MEASURE
Α	Total length	69"
В	Bathing well length	45"
С	Total width	35"
D	Bathing well width	26 1/4"
E	Deck width	2"
F	Deck width at backrest ends	1 5/8"
G	Slope of backrests	24°
Н	Outside edge to center of drain	8 3/4"
I	Height from bottom of drain to top of deck	21"
J	Maximum water level Maximum water level with AromaFlow	16 3/4" 16 1/4"
K	Total height	24"

Turbine position (TMU)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

#### FOR THE INSTALLER

SCAN TO VIEW INSTALLATION VIDEO (3:20 MIN)



TECHNICAL SE	PECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	300 lb
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Turbine power	550 W
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Air heater	600 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 8 sq. in. minimum.	WARRANTY	
Others	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access). Faucet must be freestanding or wall-mounted. Controls cannot be installed on the bath.	Controls-LED-Geysair*	5 years
		Bath & turbine*	20 years
	The turbine should be <b>remotely installed</b> .     The turbine can also be installed under the bath. <b>Please refer to the Nokori Installation Instructions</b> .     The water level will be lower when an AromaFlow is installed.	* Some restrictions apply   www.bainultra.co	om/warranty


The specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

## **NOKORI** 7131

71" x 31" x 24" (FREESTANDING)

Nokori's sleek and delicate lines inspire peace and calm-offering an authentic invitation to unwind.



THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$10,485
Jets	42
1 heated backrest	Included
MiaPlus® Control* (not installed)	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®	N/A
AromaFlow**** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$8,015
AromaCloud®	N/A
AromaFlow**** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control (not installed)	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			Freestanding	
No. of bathers	* *	Imp. gallo	ons	
US gallons	71	Brass was	te kit	Included
INTEGRATED WASTE &	OVERFLO	W BOVERINI-)	<b>x</b> p. 10	
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32			Installe	d & Included
STANDARD COLOR p.13				
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)	
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
TILE FLANGE (specify position) p.11	
Ordered with bath (not installed) BTILEN	\$79
Factory-installed. Right BTILER, Left BTILEL, Front BTILEF, Back BTILEB, Special installation BTILEO	\$155
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10	
Matte Black 19, Satin Brass 18	\$120
AIR INTAKE** & ISLAND TUB DRAIN™*** p.11	
Air intake & Island Tub Drain™ BAIRISLD	\$350
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
Air intake BAIRINT	\$120
Air intake installation	\$285 net
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240




Don't forget that this model is available in **White only**. If turbine is installed under the bath, please follow the installation instructions specified in the Nokori Installation Manual.

- \* Control must be wall-mounted. Faucets must be freestanding
- or wall-mounted.
  \*\* Air Intake is required if turbine is installed under the bath.
- \*\*\* An Island Tub Drain™ is required when there is no access under the bath.
- \*\*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

#### TO ORDER








#### **NOKORI** 7131 (FREESTANDING)

#### INSTALLATION





LETTER	DESCRIPTION	MEASURE
Α	Total length	70 1/2"
В	Bathing well length	48 1/8"
С	Total width	31"
D	Bathing well width	22"
E	Deck width	1 7/8"
F	Deck width at backrest ends	1 3/8"
G	Slope of backrests	24°
Н	Outside edge to center of drain	8 3/4"
I	Height from bottom of drain to top of deck	21"
J	Maximum water level Maximum water level with AromaFlow	17" 16 1/2"
К	Total height	24"

- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

#### FOR THE INSTALLER

SCAN TO VIEW INSTALLATION VIDEO (3:20 MIN)



TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Ī	
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 8 sq. in. minimum.	١	
Others	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access). Faucet must be freestanding or wall-mounted. Controls cannot be installed on the bath. The turbine should be remotely installed. The turbine can also be installed under the bath. Please refer to the Nokori Installation Instructions. The water level will be lower when an AromaFlow is installed.	*	

- The turbine should be <b>remotely installed</b> .
<ul> <li>The turbine can also be installed under the bath. Please refer to the Nokori Installation Instructions.</li> <li>The water level will be lower when an AromaFlow is installed.</li> </ul>
- The water level will be lower when an Aromanow is installed.

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

Approx. shipping weight	280 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years

<sup>\*</sup> Some restrictions apply  $\mid$  www.bainultra.com/warranty

# OPALIA 6839 CENTERED ELLIPSE

68" x 39" x 25" (FREESTANDING)

Presenting Opalia®, a collection of exquisitely crafted therapeutic baths with the bold, pure lines of a fascinating opal. Like so many magnificent jewels, Opalia oval baths play on elliptical perfection, with original deck designs that intrigue and delight.



MODEL	тми	TUB
Freestanding	BOPPOF00T-XX	BOPPOF00N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$8,815
Jets	35
1 heated backrest	Included
MiaPlus® Control (not installed)	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$6,220
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			F	reestanding
No. of bathers	* *	Imp. gallo	าร	42
US gallons	51			
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Chrome 07, Brus Polished Nickel 10, Matte UltraVelour finish 32		9,	Installe	d & Included
STANDARD COLOR p.13				
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)	
COLOR p.13	
Black / White 66	\$475
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310

Don't forget to specify the **finish of the integrated waste & overflow**.

Faucets must be freestanding or wall-mounted. \* The AromaCloud® is built into the deck (factory installed).

\*\* An Island Tub Drain™ is required when there is **no access under** 

the bath.

\*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.












#### INSTALLATION



J	
	† L
K	

LETTER	DESCRIPTION	MEASURE
Α	Total length	68"
В	Total width	39"
С	Bathing well length (at height of jets)	41 5/8"
D	Bathing well width (at height of jets)	23 5/8"
E	Deck width (backrests)	3 3/4"
F	Deck width (center)	2 3/8"
G	Air intake to center of drain (long axis)	4 1/4"
Н	Air intake to center of drain (trans. axis)	3 7/8"
I	Bath height	24 3/4"
J	Length of the base	43"
K	Width of the base	24"
L	Maximum water level Maximum water level with AromaFlow	15 7/8" 15 5/16"
М	Slope of backrests	31°

⚠ AromaCloud® position

**ⓒ** Control position when factory-installed (Mia® or DOT)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000073
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	230 lb
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI.	Turbine power	550 W
		Air heater	600 W
	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	WARRANTY	
	- Faucet must be freestanding or wall-mounted The turbine must be <b>remotely installed</b> .	Controls-LED-Geysair*	5 years
	- The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years


Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

\* Some restrictions apply | www.bainultra.com/warranty

## OPALIA 6839 OFF-CENTERED ELLIPSE - LEFT

68" x 39" x 25" (FREESTANDING)

Presenting Opalia®, a collection of exquisitely crafted therapeutic baths with the bold, pure lines of a fascinating opal. Like so many magnificent jewels, Opalia oval baths play on elliptical perfection, with original deck designs that intrigue and delight.



MODEL	TMU	TUB
		. • •
Freestanding	BOPPOF0LT-XX	BOPPOF0LN-XX

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$8,815
Jets	35
1 heated backrest	Included
MiaPlus® Control (not installed)	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$6,220
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			F	reestanding
No. of bathers	* *	Imp. gallo	าร	42
US gallons	51			
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01			Included	

OPTIONS (UPCHARGE APPLICABLE)		
COLOR p.13		
Black / White 66	\$475	
FINISH p.6		
UltraVelour Matte Finish (white only) BVEL2	\$850	
UNIVERSAL ARMRESTS BGBGU-XX p.12		
White 01	\$750	
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10		
Matte Black 19, Satin Brass 18	\$120	
ISLAND TUB DRAIN™** p.11		
Island Tub Drain™ BISLDD	\$260	
Cast Iron Island Tub Drain™ BISLDDCI	\$310	

Don't forget to specify the **finish of the integrated waste & overflow**. Faucets must be freestanding or wall-mounted.

\* The AromaCloud® is built into the deck (factory installed).

\*\* An Island Tub Drain™ is required when there is **no access under** the bath.

\*\*\* When ordering an AromaFlow, an Integrated waste & overflow

is mandatory (Included). Specify the finish of the waste.













#### INSTALLATION





	↑ N
- M	

LETTER	DESCRIPTION	MEASURE
Α	Total length	68"
В	Total width	39"
С	Bathing well length (at height of jets)	41 5/8"
D	Bathing well width (at height of jets)	23 5/8"
E	Deck width (backrest)	5 1/2"
F	Deck width (feet)	2"
G	Deck width (center)	2 3/8"
Н	Air intake to center of drain (long axis)	4 1/4"
I	Air intake to center of drain (trans. axis)	3 7/8"
J	Center of drain to edge of backrest	35 3/4"
J'	Center of drain to edge of backrest	32 1/4"
K	Bath height	24 3/4"
L	Length of the base	43"
М	Width of the base	24"
N	Maximum water level Maximum water level with AromaFlow	15 7/8" 15 5/16"
0	Slope of backrests	31°

⚠ AromaCloud® position

**●** Control position when factory-installed (Mia® or DOT)

Indicates heated backrest (TMU)


Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000073
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	230 lb
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power	550 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI.	Air heater	600 W
	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access). Faucet must be freestanding or wall-mounted. The turbine must be remotely installed.	WARRANTY	
Others		Controls-LED-Geysair*	5 years
	- The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years
	the installed by certified professionals only and according to our Owner's Manual as well as federal, docal building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainul	tra.com/warranty

## **OPALIA** 6839 off-centered ellipse - right

68" x 39" x 25" (FREESTANDING)

Presenting Opalia®, a collection of exquisitely crafted therapeutic baths with the bold, pure lines of a fascinating opal. Like so many magnificent jewels, Opalia oval baths play on elliptical perfection, with original deck designs that intrigue and delight.



MODEL	тми	TUB
Freestanding	BOPPOFORT-XX	BOPPOF0RN-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$8,815
Jets	35
1 heated backrest	Included
MiaPlus® Control (not installed)	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$6,220
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type		F	reestanding	
No. of bathers	**	Imp. gallo	ns	42
US gallons	51			
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)	
COLOR p.13	
Black / White 66	\$475
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310

Don't forget to specify the **finish of the integrated waste & overflow**.

Faucets must be freestanding or wall-mounted.

\* The AromaCloud® is built into the deck (factory installed).

\*\* An Island Tub Drain™ is required when there is **no access under** 

the bath.

\*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.



MEASURE











#### INSTALLATION





Α	Total length	68"
В	Total width	39"
С	Bathing well length (at height of jets)	41 5/8"
D	Bathing well width (at height of jets)	23 5/8"
E	Deck width (feet)	5 1/2"
F	Deck width (backrest)	2"
G	Deck width (center)	2 3/8"
Н	Air intake to center of drain (long axis)	4 1/4"
I	Air intake to center of drain (trans. axis)	3 7/8"
J	Center of drain to edge of backrest	35 3/4"
J'	Center of drain to edge of backrest	32 1/4"
K	Bath height	24 3/4"
L	Length of the base	43"
М	Width of the base	24"
N	Maximum water level Maximum water level with AromaFlow	15 7/8" 15 5/16"
0	Slope of backrests	31°

⚠ AromaCloud® position

LETTER DESCRIPTION

**●** Control position when factory-installed (Mia® or DOT)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SP	PECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000073
supply required	Access to the numb must be at least 19" v 22" Standard connection is 20.4. 120 V 60 Hz, dedicated	Approx. shipping weight	230 lb
Turbine	Access to the pump must be at least 18" x 22". Standard connection is 20 A. 120 V, 60 Hz, dedicated line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI.	Turbine power	550 W
		Air heater	600 W
<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	WARRANTY		
Others	- Faucet must be freestanding or wall-mounted The turbine must be <b>remotely installed</b> .	Controls-LED-Geysair*	5 years
- The water level will be lower when an AromaFlow is installed.	- The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years
Our products must	t be installed by certified professionals only and according to our Owner's Manual as well as federal.	***	

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

\* Some restrictions apply | www.bainultra.com/warranty he specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.

## OPALIA 6839 OBLIQUE ELLIPSE - LEFT

68" x 39" x 25" (FREESTANDING)

Presenting Opalia®, a collection of exquisitely crafted therapeutic baths with the bold, pure lines of a fascinating opal. Like so many magnificent jewels, Opalia oval baths play on elliptical perfection, with original deck designs that intrigue and delight.



#### PRODUCT NO.

MODEL	тми	TUB
Freestanding	BOPPOFXLT-XX	BOPPOFXLN-XX

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$8,815
Jets	35
1 heated backrest	Included
MiaPlus® Control (not installed)	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$6,220
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			Freestanding	
No. of bathers	* *	Imp. gallor	าร	42
US gallons	51			
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.	13			
White 01			Included	

OPTIONS (UPCHARGE APPLICABLE)	
COLOR p.13	
Black / White 66	\$475
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310



Don't forget to specify the **finish of the integrated waste & overflow**.

Faucets must be freestanding or wall-mounted. \* The AromaCloud® is built into the deck (factory installed).

\*\* An Island Tub Drain™ is required when there is **no access under** 

the bath.

\*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.












#### **OPALIA** 6839 OBLIQUE ELLIPSE - LEFT (FREESTANDING)

#### INSTALLATION



LETTER	DESCRIPTION	MEASURE
Α	Total length	68"
В	Total width	39"
С	Bathing well length (at height of jets)	41 5/8"
D	Bathing well width (at height of jets)	23 5/8"
E	Deck width (backrests)	3 7/8"
F	Deck width (center)	2 3/8"
G	Air intake to center of drain (long axis)	3 7/8"
Н	Air intake to center of drain (trans. axis)	4 1/4"
ı	Bath height	24 3/4"
J	Length of the base	43"
K	Width of the base	24"
L	Maximum water level Maximum water level with AromaFlow	15 7/8" 15 5/16"
М	Slope of backrests	31°

A AromaCloud® position

**ⓒ** Control position when factory-installed (Mia® or DOT)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SE	PECIFICATIONS	
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting templa
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shippi
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI.	Air heater
The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).  The turbine must be remotely installed. The water level will be lower when an AromaFlow is installed.	WARRANTY	
		Controls-LED-C
	- The water level will be lower when an AromaFlow is installed.	Bath & turbine*

Our products must be installed by certified professionals only and according to our Owner's Manual as well as fec	eral.
provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-	catalog).

Cutting template	# 90000073
Approx. shipping weight	230 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years

 $<sup>\</sup>hbox{* Some restrictions apply} \mid \hbox{www.bainultra.com/warranty}$ 

# OPALIA 6839 oblique ellipse - right

68" x 39" x 25" (FREESTANDING)

Presenting Opalia®, a collection of exquisitely crafted therapeutic baths with the bold, pure lines of a fascinating opal. Like so many magnificent jewels, Opalia oval baths play on elliptical perfection, with original deck designs that intrigue and delight.



MODEL	TMU	TUB	
Freestanding	BOPPOFXRT-XX	BOPPOFXRN-XX	

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$8,815
Jets	35
1 heated backrest	Included
MiaPlus® Control (not installed)	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$6,220
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			Freestanding	
No. of bathers	**	Imp. gallo	ns	42
US gallons	51			
INTEGRATED WASTE &	OVERFLO	W BOVERINI-)	<b>X</b> p. 10	
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)	
COLOR p.13	
Black / White 66	\$475
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310

Don't forget to specify the **finish of the integrated waste & overflow**.

Faucets must be freestanding or wall-mounted.

\* The AromaCloud® is built into the deck (factory installed).

\*\* An Island Tub Drain™ is required when there is **no access under** 

the bath.

\*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.













#### **OPALIA** 6839 oblique ellipse - right (freestanding)





LETTER	DESCRIPTION	MEASURE
Α	Total length	68"
В	Total width	39"
С	Bathing well length (at height of jets)	41 5/8"
D	Bathing well width (at height of jets)	23 5/8"
E	Deck width (backrests)	3 7/8"
F	Deck width (center)	2 3/8"
G	Air intake to center of drain (long axis)	3 7/8"
Н	Air intake to center of drain (trans. axis)	4 1/4"
ı	Bath height	24 3/4"
J	Length of the base	43"
К	Width of the base	24"
L	Maximum water level Maximum water level with AromaFlow	15 7/8" 15 5/16"
М	Slope of backrests	31°

A AromaCloud® position

**ⓒ** Control position when factory-installed (Mia® or DOT)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)


TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000073
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	230 lb
Turbine	ine line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI.	Turbine power	550 W
		Air heater	600 W
		WARRANTY	
<ul> <li>The turbine must be remotely installed.</li> </ul>		Controls-LED-Geysair*	5 years
	- The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

# **SCALA** 6638

66" x 38" x 25" (FREESTANDING)

Scala, this freestanding bath has an aesthetic refinement that translates into a contemporary version of the Rococo style bathtub on lion's feet.



MODEL	тми	TUB
Freestanding	BSCMOF00T-XX	BSCMOF00N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$10,875
Jets	38
1 heated backrest & headrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

TUB Soaker	\$8,750
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			Freestanding	
No. of bathers	* *	Imp. gallo	ns	51
US gallons	62			
INTEGRATED WASTE 8	k OVERFLO	W BOVERINI-)	<b>x</b> p. 10	
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installed & Included		
FEET (specify finish) BFEETSC-XX p.12				
Matte Black 19, Satin Brass 18		Installed & Included		
STANDARD COLOR p.13				
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)	
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
ARMRESTS (2) BGBSC-XX p.12	
Chrome 07, Brushed Nickel 09, Polished Nickel 10	\$1,950
Matte Black 19, Satin Brass 18	\$1,300
FEET (specify finish) BFEETSC-XX p. 12	
Chrome 07, Brushed Nickel 09, Polished Nickel 10	\$1,100
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60

Don't forget that this model is available in White only.
 Don't forget to specify the finish of the integrated waste & overflow, feet and armrests.

- \* Control and faucet cannot be installed on the deck of the bath.
- \*\* An Island Tub Drain™ is required when there is **no access under**
- the bath.

  \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

#### TO ORDER


Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

#### FOR THE INSTALLER **SCAN** TO VIEW INSTALLATION VIDEO (3:20 MIN)











#### SCALA 6638 (FREESTANDING)

INSTALLATION

# Air intake





LETTER	DESCRIPTION	MEASURE
Α	Total length	66"
В	Total width	38"
С	Bathing well length	44 1/2"
D	Bathing well width	23 1/8"
E	Deck width at sides	3 1/2"
F	Deck width at ends	1/2"
G	Center drain to air intake	3 1/4"
Н	Total height to headrest	25"
I	Maximum water level Maximum water level with AromaFlow	16 7/8" 15"
J	Base length	48 3/8"
K	Base width	22 5/8"
L	Slope of backrests	26°
М	Center drain to center air intake	3 1/4"

- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	
Others	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access). Faucet must be freestanding or wall-mounted. The turbine must be remotely installed. TMU: Control must be wall-mounted. TIMU: DOT control will be installed on TUB.	

Our products must	be installed by certified professionals only and according to our Owner's Manual as well as federal,
provincial/state and	l local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).


Cutting template	# 90000077
Approx. shipping weight	250 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years

 $<sup>\</sup>mbox{*}$  Some restrictions apply | www.bainultra.com/warranty

# **SCALA** 7242

72" x 42" x 25" (FREESTANDING)

Scala, this freestanding bath has an aesthetic refinement that translates into a contemporary version of the Rococo style bathtub on lion's feet.



MODEL	IMU	IOR
Freestanding	BSCVOF00T-XX	BSCVOF00N-XX
THERMOMASSEUR (TI	MU)	¢44 750
Hydro-thermo massage • Air jet system		\$11./50

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$11,750
Jets	41
1 heated backrest & headrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application	Included
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$9,050
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type		F	reestanding	
No. of bathers	* *	Imp. gallo	ns	63
US gallons	76			
INTEGRATED WASTE 8	OVERFLO	W BOVERINI-)	x p. 10	
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
FEET (specify finish) BFEETSC-XX p.12				
Matte Black 19, Satin Brass 18		Installe	d & Included	
STANDARD COLOR p.	13			
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)	
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
ARMRESTS (2) BGBSC-XX p. 12	
Chrome 07, Brushed Nickel 09, Polished Nickel 10	\$1,950
Matte Black 19, Satin Brass 18	\$1,300
FEET (specify finish) BFEETSC-XX p. 12	
Chrome 07, Brushed Nickel 09, Polished Nickel 10	\$1,100
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60

Onn't forget that this model is available in White only.
Don't forget to specify the finish of the integrated waste & overflow, feet and armrests.

- \* Control and faucet cannot be installed on the deck of the bath.
- \*\* An Island Tub Drain™ is required when there is **no access under**
- the bath.

  \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

#### TO ORDER








Armrests (2), offered in option

#### SCALA 7242 (FREESTANDING)



# Air intake A C B C C



LETTER	DESCRIPTION	MEASURE
Α	Total length	72"
В	Total width	42"
С	Bathing well length	50"
D	Bathing well width	26 1/2"
E	Deck width at sides	4 1/8"
F	Deck width at ends	1/2"
G	Center drain to air intake	3 5/8"
Н	Total height to headrest	25"
ı	Maximum water level Maximum water level with AromaFlow	16 7/8" 15"
J	Base length	54 3/8"
K	Base width	24 1/8"
L	Slope of backrests	27°

- Indicates heated backrest (TMU)
- (TUB) Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	
Others	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access). Faucet must be freestanding or wall-mounted. The turbine must be remotely installed. TMU: Control must be wall-mounted. TUB: DOT control will be installed on TUB. The water level will be lower when an AromaFlow is installed.	

Cutting template	# 90000076
Approx. shipping weight	300 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years


 $<sup>\</sup>mbox{*}$  Some restrictions apply | www.bainultra.com/warranty

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

# **IBE** 5828

58" x 28" x 21" (FREESTANDING)

Vibe is a collection of therapeutic bathtubs with minimalist and contemporary flair. The collection is perfect for urban city dwellers who want to bring value and refinement to smaller bathrooms.



THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$8,655
Jets	40
1 heated backrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$6,430
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type			Freestanding	
No. of bathers	*	Imp. gallo	ns	36
US gallons	44			
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)	
COLOR p.13	
Black / White 66	\$475
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60



- Don't forget to specify the **finish of the integrated waste & overflow**.
  - \* Control must be wall-mounted. Faucets must be freestanding or wall-mounted.

    \*\* An Island Tub Drain™ is required when there is **no access under**
  - the bath.

    \*\*\* When ordering an AromaFlow, an Integrated waste & overflow
  - is mandatory (Included). Specify the finish of the waste.

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com


#### FOR THE INSTALLER **SCAN** TO VIEW INSTALLATION VIDEO (3:20 MIN)






#### **VIBE** 5828 (FREESTANDING)

# F C C Air intake





LETTER	DESCRIPTION	MEASURE
Α	Total length	58"
В	Total width	28"
С	Bathing well length	44"
D	Bathing well width	19 1/8"
E	Deck width	7/8"
F	Deck width at headrest	1"
G	Center drain to air intake	4 1/4"
Н	Total height	21"
ı	Maximum water level Maximum water level with AromaFlow	14 5/16" 12 1/2"
J	Slope of backrest	27°
К	Base length	52 1/8"
L	Base width	22 1/8"
М	Outer edge to center of drain	10 7/8"

- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SE	TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000078	
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	225 lb	
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power	550 W	
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W	
	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	WARRANTY		
Others	- Faucet must be freestanding or wall-mounted The turbine must be <b>remotely installed</b> .	Controls-LED-Geysair*	5 years	
	- Controls cannot be installed on the deck of the bath The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years	

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

 $\mbox{\tt *}$  Some restrictions apply | www.bainultra.com/warranty

# VIBE BACK TO WALL 5828

58" x 28" x 21" (FREESTANDING)

Vibe is a collection of therapeutic bathtubs with minimalist and contemporary flair. The collection is perfect for urban city dwellers who want to bring value and refinement to smaller bathrooms.



#### PRODUCT NO.

MODEL	тми	TUB
BTW - Left	BVBCHW0LT-XX	BVBCHW0LN-XX
BTW - Right	BVBCHW0RT-XX	BVBCHW0RN-XX
Front overflow - Left	BVFCHW0LT-XX	BVFCHW0LN-XX
Front overflow - Right	BVFCHW0RT-XX	BVFCHW0RN-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$9,155
Jets	40
1 heated backrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$6,705
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type			Freestanding	g (Back to wall)
No. of bathers	•	Imp. gallo	ns	36
US gallons	44			
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01				Included

OPTIONS (UPCHARGE APPLICABLE)	
COLOR p.13	
Black / White 66	\$475
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60



- Don't forget to specify the **finish of the integrated waste & overflow.** 
  - \* Control must be wall-mounted. Faucets must be freestanding or wall-mounted.
  - \*\* An Island Tub Drain™ is required when there is **no access under** the bath.
  - \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.


Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

#### FOR THE INSTALLER **SCAN** TO VIEW INSTALLATION VIDEO (3:20 MIN)



**TECHNICAL SPECIFICATIONS** 





Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000079
supply required	A	Approx. shipping weight	225 lb
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is</b>	Turbine power	550 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).</li> <li>Faucet must be freestanding or wall-mounted.</li> <li>The turbine must be remotely installed.</li> <li>Controls cannot be installed on the deck of the bath.</li> <li>The water level will be lower when an AromaFlow is installed.</li> </ul>	WARRANTY	
		Controls-LED-Geysair*	5 years
		Bath & turbine*	20 years
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).		* Some restrictions apply   www.bainultra.co	om/warranty

The specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.

# **VIBE OVAL** 5830

58" x 30" x 21" (FREESTANDING)

Vibe is a collection of therapeutic bathtubs with minimalist and contemporary flair. The collection is perfect for urban city dwellers who want to bring value and refinement to smaller bathrooms.



#### PRODUCT NO.

MODEL	тми	TUB	
Freestanding	BVIAOF00T-XX	BVIAOF00N-XX	

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$8,655
Jets	35
1 heated backrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$6,430
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type			Freestanding	
No. of bathers	*	Imp. gallo	ns	
US gallons	40			
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01			Included	

OPTIONS (UPCHARGE APPLICABLE)	
COLOR p. 13	
Black / White 66	\$475
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60



- Don't forget to specify the **finish of the integrated waste & overflow.** 
  - \* Control must be wall-mounted. Faucets must be freestanding or wall-mounted.
  - \*\* An Island Tub Drain™ is required when there is **no access under** the bath.
  - \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

#### FOR THE INSTALLER

**SCAN** TO VIEW INSTALLATION VIDEO (3:20 MIN)








#### VIBE OVAL 5830 (FREESTANDING)

# A C G H Air intake



LETTER	DESCRIPTION	MEASURE
Α	Total length	58"
В	Total width	30"
С	Bathing well length	41 1/4"
D	Bathing well width	20 1/8"
E	Center of air intake to center of drain (front)	3 1/2"
F	Center of air intake to center of drain (side)	3 1/2"
G	Outer edge to center of drain	10 1/16"
н	Total height	21"
ı	Deck width at headrest	1 3/8"
J	Slope of backrest	26°
K	Base length	47"
L	Deck width	1 3/8"
М	Base width	24 1/4"
N	Maximum water level Maximum water level with AromaFlow	14 5/16" 12 3/4"
0	Minimum spout reach	5 3/4"

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SP	ECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000080
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	225 lb
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power	550 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W
Others	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).  Faucet must be freestanding or wall-mounted.  The turbine must be remotely installed.  Controls cannot be installed on the deck of the bath.  The water level will be lower when an AromaFlow is installed.	WARRANTY	
		Controls-LED-Geysair*	5 years
		Bath & turbine*	20 years
	be installed by certified professionals only and according to our Owner's Manual as well as federal, d local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainult	ra.com/warranty

# VIBE DESIGN 6033 60" x 33" x 21" (FREESTANDING)

Vibe is a collection of therapeutic bathtubs with minimalist and contemporary flair. The collection is perfect for urban city dwellers who want to bring value and refinement to smaller bathrooms.



#### PRODUCT NO.

MODEL	тми	TUB	
Freestanding	BVDEOF00T-XX	BVDEOF00N-XX	

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$8,655
Jets	35
1 heated backrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$6,430
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type			Freestanding	
No. of bathers	•	Imp. gallo	ns	33
US gallons	40			
INTEGRATED WASTE 8	OVERFLO	W BOVERINI-)	<b>x</b> p. 10	
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01			Included	

OPTIONS (UPCHARGE APPLICABLE)	
COLOR p. 13	
Black / White 66	\$475
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL2	\$850
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
ISLAND TUB DRAIN™** p.11	
Island Tub Drain™ BISLDD	\$260
Cast Iron Island Tub Drain™ BISLDDCI	\$310
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60



- Don't forget to specify the **finish of the integrated waste & overflow.**
- \* Control must be wall-mounted. Faucets must be freestanding or wall-mounted.
- \*\* An Island Tub Drain™ is required when there is **no access under** the bath.
- \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

#### FOR THE INSTALLER **SCAN** TO VIEW INSTALLATION VIDEO (3:20 MIN)





#### VIBE DESIGN 6033 (FREESTANDING)

# A C C Air intake

LETTER	DESCRIPTION	MEASURE
Α	Total length	60"
В	Total width	33"
С	Bathing well length	41 1/2"
D	Bathing well width	20 3/8"
E	Center of air intake to center of drain (front)	3 1/2"
F	Center of air intake to center of drain (side)	3 1/2"
G	Outer edge to center of drain	11 1/4"
Н	Total height	21"
I	Deck width at headrest	2 1/2"
J	Slope of backrests	22°
К	Base length	47 1/2"
L	Deck width	2"
М	Base width	23 3/4"
N	Maximum water level Maximum water level with AromaFlow	14 5/16" 13"
0	Minimum spout reach	6 1/2"

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)


TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000081
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	230 lb
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power	550 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W
	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.         It must be connected to the hot water supply and be accessible (provide access).     </li> <li>Faucet must be freestanding or wall-mounted.</li> <li>The turbine must be remotely installed.</li> </ul>	WARRANTY	
Others		Controls-LED-Geysair*	5 years
	- Controls cannot be installed on the deck of the bath The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years
	to be installed by certified professionals only and according to our Owner's Manual as well as federal, d local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainult	ra.com/warranty



## DROP-IN & ALCOVE THERAPEUTIC BATHS



DISTINCTIVE AND WELL DESIGNED













60" x 30" x 21"

Amma takes its origin in the word "massage" as represented by two Chinese characters, AN and MO, meaning "calm through touch."



MODEL	тми	TUB
Alcove – Left	BAMBRA0LT-XX	BAMBRAOLN-XX
Alcove – Right	BAMBRAORT-XX	BAMBRAORN-XX

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$6,545
Jets	43
1 heated backrest & headrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair <sup>®</sup>	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$4,055
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type	Installation type		Alcove (3 walls)	
No. of bathers	•	Raised seat		1
US gallons	46	Inverted V		1
Imp. gallons	39	Integrated tile flange		Included
STANDARD COLOR p.13				
				Included
White 01 Biscuit 02				

OPTIONS (UPCHARGE APPLICABLE)		
<b>SKIRT</b> p.243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX
White 01, Biscuit 02	\$600	\$715
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED BOVERIN-XX
Chrome 07	\$260	\$235
White 01, Biscuit 02	\$290	\$235
Brushed Nickel 09, Polished Nickel 10	\$400	\$235
Oil-rubbed Bronze 11	\$400	N/A
Matte Black 19, Satin Brass 18	N/A	\$355
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit** BDRCOB		\$240
Brass waste kit** BDRCB		\$60
16" x 35" Cable driven brass waste & overflow kit BOVERBR		\$240



- Don't forget that you must specify the waste position, right or left.

  \* The AromaCloud\* is built into the deck (factory installed).

  - \*\* When ordered with integrated waste & overflow.
  - \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.










#### INSTALLATION

The AromaCloud® will automatically be installed on the opposite side of the tile flange.







LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	8 1/2"
В	Outside edge to overflow	2 1/2"
С	Total length	60"
D	Total width	30"
E	Bathing well length	46 1/4"
F	Bathing well width at center zone	17 1/2"
G	Raised seat length	18 1/2"
н	Raised seat width	19 3/8"
ı	Frontside deck width (narrowest point)	3 1/8"
J	Frontside deck width (widest point)	4"
K	Deck width at drain end	2 1/8"
L	Total height to headrest	22"
М	Height from bottom of bath to top deck	21"
N	Height from bottom of bath to bottom of deck	19 1/2"
0	Tile flange height	1 1/2"
P	Height from bottom of drain to center of overflow	17 1/16"
Q	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	15 5/16" 16 5/16" 15 1/16"
R	Slope of backrest	16°

- ⚠ AromaCloud® position
- Control position when factory-installed (Mia® or DOT)
- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SP	ECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	134 lb
supply required	Access to the numb point he at least 10% y 22% Standard connection is 20 A 120 V CO Hz dedicated	Turbine power	550 W
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is</b>	Air heater	600 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	WARRANTY	
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	Controls-LED-Geysair*	5 years
Others	Integrated tile flange is included (specify right or left).     The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years
	be installed by certified professionals only and according to our Owner's Manual as well as federal, d local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainultr	a.com/warranty

60" x 32" x 21"

Amma takes its origin in the word "massage" as represented by two Chinese characters, AN and MO, meaning "calm through touch."



MODEL	тми	TUB
	BAMDRB00T-XX	BAMDRB00N-XX

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$6,545
Jets	45
1 heated backrest & headrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$4,055
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type		Drop-in & A	Alcove (3 walls)	
No. of bathers	*	Raised sea	at	1
US gallons	46	Inverted V		1
Imp. gallons	39			
STANDARD COLOR p.	.13			
White 01 Biscuit 02				Included

OPTIONS (UPCHARGE APPLICABLE)		
<b>SKIRT</b> p.243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX
White 01, Biscuit 02	\$600	\$715
TILE FLANGE (specify right or left) p.11		
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Right BTILER, Left BTILEL, Special installation BTILEO		\$155
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED BOVERIN-XX
Chrome 07	\$260	\$235
White 01, Biscuit 02	\$290	\$235
Brushed Nickel 09, Polished Nickel 10	\$400	\$235
Oil-rubbed Bronze 11 \$400		N/A
Matte Black 19, Satin Brass 18 N/A		\$355
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit** BDRCOB		\$240
Brass waste kit** BDRCB		\$60
16" x 35" Cable driven brass waste & overflow kit BOVERBR		\$240



- \*The AromaCloud® is built into the deck (factory installed).

  \*\*When ordered with integrated waste & overflow.

  \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.

#### TO ORDER










#### INSTALLATION

⚠ When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.







provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	8 1/2"
В	Outside edge to overflow	2 1/2"
С	Total length	60"
D	Total width	32"
E	Bathing well length	46 1/4"
F	Bathing well width at center zone	17 1/2"
G	Raised seat length	18"
н	Raised seat width	19 3/8"
I	Deck width (narrowest point)	3 1/8"
J	Deck width (widest point)	3 7/8"
K	Deck width at drain end	2"
L	Deck width at backrest end	1 7/8"
М	Total height to headrest	22"
N	Height from bottom of bath to top deck	21"
0	Height from bottom of bath to bottom of deck	19 1/2"
P	Height from bottom of drain to center of overflow	17 1/16"
Q	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	15 5/16" 16 5/16" 15 1/16"
R	Slope of backrest	16°

- A AromaCloud® position
- **G** Control position when factory-installed (Mia® or DOT)
- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	138 lb
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Turbine power	550 W
Turbine	urbine line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Air heater	600 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	WARRANTY	
Others		Controls-LED-Geysair*	5 years
	- Optional tile flange (specify right or left) The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years

60" x 36" x 21"

Amma takes its origin in the word "massage" as represented by two Chinese characters, AN and MO, meaning "calm through touch."



#### PRODUCT NO.

MODEL	тми	TUB
	BAMFRB00T-XX	BAMFRB00N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$7,455
Jets	45
1 heated backrest & headrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$4,685
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type			Drop-in & A	cove (3 walls)
No. of bathers	Ÿ	Inverted V		1
US gallons	50	Armrests		2
Imp. gallons	41	Grab bars	(color match)	2
Raised seat	1			
STANDARD COLOR p. 13	3			
				Included

OPTIONS (UPCHARGE APPLICABLE)		
<b>SKIRT</b> p.243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX
White 01, Biscuit 02	\$600	\$715
<b>CLEAR ACRYLIC GRAB BARS</b> BGBG10-XX p.12		
With Chrome 07 or Brushed Nickel 09 inserts		\$60
TILE FLANGE (specify right or left) p.11		
Ordered with bath (not installed) BTILEN	\$79	
Factory-installed. Right BTILER, Left BTILEL, Special installation BTILEO		\$155
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED BOVERIN-XX
Chrome 07	\$260	\$235
White 01, Biscuit 02	\$290	\$235
Brushed Nickel 09, Polished Nickel 10	\$235	
Oil-rubbed Bronze 11 \$400		N/A
Matte Black 19, Satin Brass 18 N/A		\$355
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit** BDRCOB		\$240
	Brass waste kit** BDRCB	
Brass waste kit** BDRCB		\$60



- \* The AromaCloud\* is built into the deck (factory installed).

  \*\* When ordered with integrated waste & overflow.

  \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.

#### TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

White 01


Biscuit 02







#### INSTALLATION ⚠ When tile flange is added, the AromaCloud® will automatically



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	8 1/2"
В	Outside edge to overflow	2 1/2"
С	Total length	60"
D	Total width	36"
E	Bathing well length	46"
F	Bathing well width at center zone	17 1/8"
G	Raised seat length	20"
н	Raised seat width	20 5/8"
I	Deck width (narrowest point)	3 1/8"
J	Deck width (widest point)	4 1/8"
K	Deck width at drain end	2"
L	Total height to headrest	23 1/4"
М	Height from bottom of bath to top deck	21"
N	Height from bottom of bath to bottom of deck	19 1/2"
0	Height from bottom of drain to center of overflow	17 1/8"
Р	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	15 3/8" 16 3/8" 15 1/8"
Q	Slope of backrest	18°

⚠ AromaCloud® position

Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

Hot water	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	142 lb
supply required	Accord to the purpo must be at least 10" v 22" Chandard connection in 20 A 120 V CO He dedicated	Turbine power	550 W
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is</b>	Air heater	600 W
needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.		WARRANTY	
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> <li>Optional tile flange (specify right or left) The water level will be lower when an AromaFlow is installed.</li> </ul>	Controls-LED-Geysair*	5 years
		Bath & turbine*	20 years

The specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.

provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

66" x 36" x 21"

Amma takes its origin in the word "massage" as represented by two Chinese characters, AN and MO, meaning "calm through touch."



	PR	OD	UC.	ΤΝ	0.
--	----	----	-----	----	----

MODEL	тми	TUB
	BAMLRB00T-XX	BAMLRB00N-XX

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$7,680
Jets	49
1 heated backrest & headrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$4,790
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES					
Installation type Drop-in & Alcove (3 walls)					
No. of bathers	*	Inverted V		1	
US gallons	56	Armrests		2	
Imp. gallons	47	Grab bars	(color match)	2	
Raised seat	1				
STANDARD COLOR p.13					
				Included	

OPTIONS (UPCHARGE APPLICABLE)		
<b>SKIRT</b> p.243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX
White 01, Biscuit 02	\$600	\$715
CLEAR ACRYLIC GRAB BARS BGBG10-XX p.12		
With Chrome 07 or Brushed Nickel 09 inserts		\$60
TILE FLANGE (specify right or left) p.11		
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Right BTILER, Left BTILEL, Special installation BTILEO		\$155
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED BOVERIN-XX
Chrome 07	\$260	\$235
White 01, Biscuit 02	\$290	\$235
Brushed Nickel 09, Polished Nickel 10	\$400	\$235
Oil-rubbed Bronze 11	\$400	N/A
Matte Black 19, Satin Brass 18	\$355	
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit** BDRCOB		\$240
Brass waste kit** BDRCB		\$60
Brass waste kit** BDRCB		+00



- \*The AromaCloud® is built into the deck (factory installed).

  \*\*When ordered with integrated waste & overflow.

  \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.

#### TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

White 01

Biscuit 02








INSTALLATION

#### When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.





  P 	Q 	

LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	8 1/2"
В	Outside edge to overflow	2 1/2"
С	Total length	66"
D	Total width	36"
E	Bathing well length	52 1/4"
F	Bathing well width at center zone	18"
G	Raised seat length	21"
Н	Raised seat width	20 7/8"
I	Deck width (narrowest point)	3"
J	Deck width (widest point)	4 1/8"
K	Deck width at drain end	2 1/8"
L	Deck width at backrest end	1 3/8"
М	Total height to headrest	23 1/8"
N	Height from bottom of bath to top deck	21"
0	Height from bottom of bath to bottom of deck	19 1/2"
P	Height from bottom of drain to center of overflow	17 1/8"
Q	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	15 3/8" 16 3/8" 15 1/8"
R	Slope of backrest	18°


- ⚠ AromaCloud® position
- Control position when factory-installed (Mia® or DOT)
- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SP	ECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	145 lb
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Turbine power	550 W
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Air heater	600 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	WARRANTY	
Others	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).	Controls-LED-Geysair*	5 years
	- Optional tile flange (specify right or left) The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).		* Some restrictions apply   www.bainultra	.com/warranty

# **AMMA OVAL** 6638

66" x 38" x 21"

Amma takes its origin in the word "massage" as represented by two Chinese characters, AN and MO, meaning "calm through touch."



MODEL	тми	TUB
	BAMMOD00T-XX	BAMMOD00N-XX

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$7,680
Jets	49
1 heated backrest & headrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$4,930
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type				Drop-in
No. of bathers	Ÿ	Inverted V		1
US gallons	56	Armrests		2
Imp. gallons	47	Grab bars (color match)		2
Raised seat	1			
STANDARD COLOR p	.13			
White 01 Biscuit 02				Included


OPTIONS (UPCHARGE APPLICABLE)			
CLEAR ACRYLIC GRAB BARS BGBG10-XX p.12			
With Chrome 07 or Brushed Nickel 09 inserts		\$60	
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED BOVERIN-XX	
Chrome 07	\$260	\$235	
White 01, Biscuit 02	\$290	\$235	
Brushed Nickel 09, Polished Nickel 10	\$400	\$235	
Oil-rubbed Bronze 11	\$400	N/A	
Matte Black 19, Satin Brass 18	N/A	\$355	
IF REQUIRED BY CONSTRUCTION CODE			
Brass waste & overflow kit** BDRCOB		\$240	
Brass waste kit** BDRCB		\$60	
16" x 35" Cable driven brass waste & overflow kit BOVERBR		\$240	

- \* The AromaCloud® is built into the deck (factory installed).

  - \*\*When ordered with integrated waste & overflow.

    \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.


#### TO ORDER







#### **AMMA OVAL** 6638



TECHNICAL SP	PECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000037
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz,</b> dedicated	Approx. shipping weight	147 lb
Turbine line with a Ground-Fault Circuit Interrupter (GFCI). For any additional opti	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Turbine power	550 W
		Air heater	600 W
Others	- The Geysair <sup>®</sup> is located on the same side as the heated backrest. It must <b>NOT be relocated</b> . It must be <b>connected to the hot water supply</b> and be accessible (provide access).	WARRANTY	
	- The water level will vary when an AromaFlow is installed.	Controls-LED-Geysair*	5 years
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).		Bath & turbine*	20 years

<sup>\*</sup> Some restrictions apply  $\mid$  www.bainultra.com/warranty

72" x 36" x 21"

Amma takes its origin in the word "massage" as represented by two Chinese characters, AN and MO, meaning "calm through touch."

#### PRODUCT NO.

MODEL	тми	TUB
	BAMSRB00T-XX	BAMSRB00N-XX

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$7,965
Jets	54
2 heated backrests & headrests*	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®** BAROMAC	\$490
AromaFlow**** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$4,930
AromaCloud®** BAROMAC	\$490
AromaFlow**** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			Drop-in & Alcove (3 walls)	
No. of bathers	* *	Inverted V		2
US gallons	50	Armrests		4
Imp. gallons	41	Grab bars (color match)		2
Raised seats	2			
STANDARD COLOR p. 1	3			
				Included

OPTIONS (UPCHARGE APPLICABLE)		
<b>SKIRT</b> p.243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX
White 01, Biscuit 02	\$600	\$715
CLEAR ACRYLIC GRAB BARS BGBG10-XX p.12		
With Chrome 07 or Brushed Nickel 09 inserts		\$60
TILE FLANGE (specify front or back) p.11		
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Front BTILEF, Back BTILEB, Special installation BTILEO		\$155
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED BOVERIN-XX
Chrome 07	\$260	\$235
White 01, Biscuit 02	\$290	\$235
Brushed Nickel 09, Polished Nickel 10	\$400	\$235
Oil-rubbed Bronze 11	\$400	N/A
Matte Black 19, Satin Brass 18	N/A	\$355
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit*** BDRCOB		\$240
Brass waste kit*** BDRCB		\$60
16" x 35" Cable driven brass waste & overflow kit	BOVERBR	\$240



- \* Independently controlled.

  \*\* The AromaCloud® is built into the deck (factory installed).

  \*\*\* When ordered with integrated waste & overflow.

  \*\*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste. With the AromaFlow, the included Grab Bars can not be installed.

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

White 01

Biscuit 02









#### INSTALLATION

(A) When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.





LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	12"
В	Outside edge to overflow	4 1/4"
С	Total length	72"
D	Total width	36"
E	Bathing well length	52 1/2"
F	Bathing well width at center zone	18 3/4"
G	Raised seat length	18 1/2"
Н	Raised seat width	21 3/4"
I	Deck width (narrowest point)	3 1/8"
J	Deck width (widest point)	4"
K	Deck width at backrest end end	2"
L	Total height to headrest	23 1/8"
М	Height from bottom of bath to top deck	21"
N	Height from bottom of bath to bottom of deck	19 1/2"
0	Height from bottom of drain to center of overflow	17"
P	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	15 1/4" 16 1/4" 15 5/8"
Q	Slope of backrests	17°

⚠ AromaCloud® position

Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	158 lb
supply required	Access to the pump must be at least 18" x 22". Standard connection is two (2) dedicated breakers: One is 20A, 120 V, 60 Hz, and the other 15A, 120 V, 60 Hz, dedicated lines with a GFCI.	Turbine power	550 W
Turbine		Air heater	600 W
	Air vent necessary: 2" x 4" minimum.	WARRANTY	
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	Controls-LED-Geysair*	5 years
	<ul> <li>Optional tile flange (specify front or back).</li> <li>The water level will vary when an AromaFlow is installed.</li> </ul>	ed. Bath & turbine*	20 years
	be installed by certified professionals only and according to our Owner's Manual as well as federal, dlocal building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainultra.com/warranty	

72" x 42" x 22"

Amma takes its origin in the word "massage" as represented by two Chinese characters, AN and MO, meaning "calm through touch."



MODEL	тми	TUB	١
	BAMVRB00T-XX	BAMVRB00N-XX	

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$8,105
Jets	58
2 heated backrests & headrests*	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®** BAROMAC	\$490
AromaFlow**** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$5,060
AromaCloud®** BAROMAC	\$490
AromaFlow**** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			Drop-in & A	lcove (3 walls)
No. of bathers	* *	Inverted V		2
US gallons	65	Armrests		4
Imp. gallons	54	Grab bars	(color match)	2
Raised seats	2			
STANDARD COLOR p.	13			
White 01 Biscuit 02				Included

OPTIONS (UPCHARGE APPLICABLE)		
<b>SKIRT</b> p.243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX
White 01, Biscuit 02	\$600	\$715
<b>CLEAR ACRYLIC GRAB BARS</b> BGBG10-XX p.12		
With Chrome 07 or Brushed Nickel 09 inserts		\$60
TILE FLANGE (specify front or back) p.11		
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Front BTILEF, Back BTILEB, Special installation BTILEO		\$155
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED BOVERIN-XX
Chrome 07	\$260	\$235
Chrome 07 White 01, Biscuit 02	\$260 \$290	\$235 \$235
	1-11	
White 01, Biscuit 02	\$290	\$235
White 01, Biscuit 02 Brushed Nickel 09, Polished Nickel 10	\$290 \$400	\$235 \$235
White 01, Biscuit 02 Brushed Nickel 09, Polished Nickel 10 Oil-rubbed Bronze 11	\$290 \$400 \$400	\$235 \$235 N/A
White 01, Biscuit 02 Brushed Nickel 09, Polished Nickel 10 Oil-rubbed Bronze 11 Matte Black 19, Satin Brass 18	\$290 \$400 \$400	\$235 \$235 N/A
White 01, Biscuit 02 Brushed Nickel 09, Polished Nickel 10 Oil-rubbed Bronze 11 Matte Black 19, Satin Brass 18 IF REQUIRED BY CONSTRUCTION CODE	\$290 \$400 \$400	\$235 \$235 N/A \$355



- \* Independently controlled.

  \*\* The AromaCloud® is built into the deck (factory installed).

  \*\*\* When ordered with integrated waste & overflow.

  \*\*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste. With the AromaFlow, the included Grab Bars can not be installed.









## INSTALLATION

When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.





LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	13 1/2"
В	Outside edge to overflow	5 3/8"
С	Total length	72 1/4"
D	Total width	42"
E	Bathing well length	52 1/4"
F	Bathing well width at center zone	21 3/8"
G	Raised seat length	18 5/8"
н	Raised seat width	24"
ı	Deck width (narrowest point)	4"
J	Deck width (widest point)	5 1/4"
К	Deck width at backrest end end	1 1/4"
L	Total height to headrest	24 1/4"
М	Height from bottom of bath to top deck	22 1/8"
N	Height from bottom of bath to bottom of deck	20 1/8"
0	Height from bottom of drain to center of overflow	18 1/8"
P	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	16 3/8" 17 3/8" 16 3/4"
Q	Slope of backrests	18°

⚠ AromaCloud® position

Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SP	ECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	195 lb
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is two (2) dedicated</b>	Turbine power	550 W
Turbine	breakers: One is 20A, 120 V, 60 Hz, and the other 15A, 120 V, 60 Hz, dedicated lines with a GFCI.	Air heater	600 W
	Air vent necessary: 2" x 4" minimum.	WARRANTY	
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	Controls-LED-Geysair*	5 years
Optional tile flange (specify front or back).     The water level will vary when an AromaFlow is installed.		Bath & turbine*	20 years
	t be installed by certified professionals only and according to our Owner's Manual as well as federal, d local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainultra.co	om/warranty

# AMMA OVAL 7242

72" x 42" x 22"

Amma takes its origin in the word "massage" as represented by two Chinese characters, AN and MO, meaning "calm through touch."

#### PRODUCT NO. MODEL TUB Raised deck BAMVODP0T-XX BAMVODP0N-XX Flat deck 2" BAMVOUN0T-XX BAMVOUNON-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$7,965
Jets	58
2 heated backrests & headrests*	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®** BAROMAC	\$490
AromaFlow**** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$5,060
AromaCloud®** BAROMAC	\$490
AromaFlow**** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type				Drop-in
No. of bathers	* *	Inverted V		2
US gallons	65	Armrests		4
Imp. gallons	54	Grab bars (color match)		2
Raised seats	2			
STANDARD COLOR p.1	3			
White 01 Biscuit 02				Included

OPTIONS (UPCHARGE APPLICABLE)		
CLEAR ACRYLIC GRAB BARS BGBG10-XX p. 12	!	
With Chrome 07 or Brushed Nickel 09 inserts		\$60
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED BOVERIN-XX
Chrome 07	\$260	\$235
White 01, Biscuit 02	\$290	\$235
Brushed Nickel 09, Polished Nickel 10	\$400	\$235
Oil-rubbed Bronze 11	\$400	N/A
Matte Black 19, Satin Brass 18	N/A	\$355
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit*** BDRCOB		\$240
Brass waste kit*** BDRCB		\$60
16" x 35" Cable driven brass waste & overflow kit BOVERBR		\$240



Don't forget to indicate raised or flat deck.
 \* Independently controlled.
 \*\* The AromaCloud® is built into the deck (factory installed).

\*\*\* When ordered with integrated waste & overflow.


\*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste. With the AromaFlow, the included Grab Bars can not be installed.

#### TO ORDER





## AMMA OVAL 7242



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	13 1/2"
В	Outside edge to overflow	5 3/8"
С	Total length	72"
D	Total width	42"
E	Bathing well length	52 1/4"
F	Bathing well width at center zone	21 3/8"
G	Raised seat length	18 5/8"
н	Raised seat width	24"
ı	Flat surface width	3 7/8"
J	Deck width	5 1/4"
K	Total height to headrest	24 3/8"
L	Height from bottom of bath to top deck	22 1/8"
М	Height from bottom of bath to bottom of deck	20 1/8"
N	Height from bottom of deck to top deck	2"
0	Height from bottom of drain to center of overflow	18 1/8"
Р	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	16 3/8" 17 3/8" 16 3/4"
Q	Slope of backrests	18°

⚠ AromaCloud® position

• Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS					
Hot water supply required  The hot water supply should be 70% or more of the bath's total water capacity.		Cutting template	# 90000036		
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is two (2) dedicated</b>	Approx. shipping weight	170 lb		
Turbine	breakers: One is 20A, 120 V, 60 Hz, and the other 15A, 120 V, 60 Hz, dedicated lines with a GFCI.	Turbine power 55	550 W		
	Air vent necessary: 2" x 4" minimum.  - The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.  It must be connected to the hot water supply and be accessible (provide access).	Air heater	600 W		
		WARRANTY			
Others	Available with flat deck for raised deck.     There is a height difference for the flat deck (see drawing Detail A).	Controls-LED-Geysair* 5 ye	5 years		
	- The water level will vary when an AromaFlow is installed.	Bath & turbine*	20 years		
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).		* Some restrictions apply   www.bainultra.	com/warranty		

# BAIN DE VILLE 6030 60" x 30" x 17"

Designed for the urban environment, Bain de Ville immediately brings a touch of modern refinement to any alcove bathroom space. Strong lines, integrated skirt, a wider deck and subtle but purposeful accents make a bold statement.



MODEL	тми	TUB	
Alcove – Left	BBVBRA0LT-XX	BBVBRA0LN-XX	
Alcove – Right	BBVBRAORT-XX	BBVBRA0RN-XX	

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$3,595
Jets	42
1 heated backrest	Included
Mia® Control (not installed)	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud® BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$1,930
AromaCloud® BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type			Alcove (3 walls)	
Integrated skirt & tile flar	nge (specify rig	tht or left)	Installe	d & Included
No. of bathers	*	Imp. gallo	ns	33
US gallons	39			
INTEGRATED WASTE 8	k OVERFLO	W BOVERINI-)	xx p. 10	
White 01, Biscuit 02, Chrome 07, Brushed Nickel 09, Polished Nickel 10 Matte White with UltraVelour finish 32			Installe	d & Included
STANDARD COLOR p. 13				
White 01 Biscuit 02				Included

FINISH p.6	
UltraVelour Matte Finish (white only) BVEL1	\$650
CONTROL (TMU only) p.9	
MiaPlus®* BMIAP1-XX	\$285
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
WASTE & OVERFLOW 16" x 35" BOVER16-XX p.10	
Chrome 07	\$260
White 01, Biscuit 02	\$290
Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11	\$400
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit** BDRCOB	\$240
Brass waste kit** BDRCB	\$60
16" x 35" Cable driven brass waste & overflow kit BOVERBR	\$240



With the AromaCloud® and/or Control on the deck, a complete shower door cannot be installed.

- Don't forget to specify the finish of the integrated waste & overflow. \* The MiaPlus® Control is included when purchasing Chromatherapy
- \*\* When ordered with integrated waste & overflow.
- \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

#### TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

152








### **BAIN DE VILLE** 6030

#### INSTALLATION







LETTER	DESCRIPTION	MEASURE
Α	Total length	60"
В	Bathing well length	46 3/8"
С	Total width	30"
D	Bathing well width	20 1/2"
E	Outer edge to center drain (right side)	14 1/8"
F	Deck width (drain side)	3 3/16"
G	Deck width (backrest)	4 3/8"
Н	Deck width (wall side)	2"
ı	Deck width (skirt side)	3 7/8"
J	Outer edge to center drain Integrated waste & overflow (front)	10 3/8"
11	Outer edge to center of overflow Waste & overflow 16" x 35" only	2 3/8"
K	Tile flange height	1"
L	Height from floor to bottom of deck	17"
М	Slope of backrest	21°
N	Maximum water level Maximum water level with AromaFlow	12 1/4" 10 9/16"

A AromaCloud® position

**❸** Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)

(TUB) Indicates WarmTouchShell® position (TUB)

Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	125 lb
зарріў гецапеа	Turbine is factory installed, so access to the pump must be at least 18" x 22". <b>Standard connection</b>	Turbine power	550 W
Turbine	is 20 A. 120 V, 60 Hz, dedicated line with a Ground-Fault Circuit Interrupter (GFCI). For any	Air heater 60	600 W
	additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	WARRANTY	
	- The Geysair® is located on the same side as the heated backrest. It must <b>NOT be relocated</b> .	Controls-LED-Geysair*	5 years
Others	It must be <b>connected to the hot water supply</b> and be accessible (provide access).  - Integrated tile flange is included (specify right or left).	Bath & turbine* 20	20 years
	- The water level will be lower when an AromaFlow is installed.	* Some restrictions apply   www.bainultr	a.com/warranty
	be installed by certified professionals only and according to our Owner's Manual as well as federal, dlocal building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).		,

# BAIN DE VILLE 6632

66" x 32" x 20"

Designed for the urban environment, Bain de Ville immediately brings a touch of modern refinement to any alcove bathroom space. Strong lines, integrated skirt, a wider deck and subtle but purposeful accents make a bold statement.



MODEL		тми	TUB
	Alcove – Left	BBVIRA0LT-XX	BBVIRA0LN-XX
	Alcove – Right	BBVIRAORT-XX	BBVIRAORN-XX

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$5,085
Jets	44
1 heated backrest	Included
Mia® Control (not installed)	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud® BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$2,760
AromaCloud® BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type			Alcove (3 walls)	
Integrated skirt & tile flar	nge (specify rig	ght or left)	Installed & Included	
No. of bathers	*	Imp. gallo	ns	52
US gallons	62			
INTEGRATED WASTE 8	k OVERFLO	W BOVERINI-)	<b>x</b> p. 10	
White 01, Biscuit 02, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01 Biscuit 02			Included	

OPTIONS (UPCHARGE APPLICABLE)	
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL1	\$650
CONTROL (TMU only) p.9	
MiaPlus®* BMIAP1-XX	\$285
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
WASTE & OVERFLOW 16" x 35" BOVER16-XX p.10	
Chrome 07	\$260
White 01, Biscuit 02	\$290
Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11	\$400
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit** BDRCOB	\$240
Brass waste kit** BDRCB	\$60
16" x 35" Cable driven brass waste & overflow kit BOVERBR	\$240



With the AromaCloud® and/or Control on the deck, a complete shower


- door cannot be installed.

  Don't forget to specify the finish of the integrated waste & overflow.

  \* The MiaPlus® Control is included when purchasing Chromatherapy
- \*\* When ordered with integrated waste & overflow.
- \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.


#### TO ORDER





## **BAIN DE VILLE** 6632

#### INSTALLATION








LETTER	DESCRIPTION	MEASURE
Α	Total length	66"
В	Bathing well length	50 5/8"
С	Total width	32"
D	Bathing well width	21 3/8"
E	Outer edge to center drain (right side)	15 1/8"
F	Deck width (drain side)	3 3/16"
G	Deck width (backrest)	4 3/8"
н	Deck width (wall side)	2"
I	Deck width (skirt side)	3 7/8"
J	Outer edge to center drain Integrated waste & overflow (front)	10 7/8"
11	Outer edge to center of overflow Waste & overflow 16" x 35" only	2 5/16"
K	Tile flange height	1"
L	Height from floor to bottom of deck	20"
М	Slope of backrest	21°
N	Maximum water level Maximum water level with AromaFlow	16" 14 5/16"

- A AromaCloud® position
- **ⓒ** Control position when factory-installed (Mia® or DOT)
- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required  The hot water supply should be 70% or more of the bath's total water capacity.		Approx. shipping weight	140 lb
supply required	Turbine is factory installed, so access to the pump must be at least 18" x 22". Standard connection is 20 A. 120 V, 60 Hz, dedicated line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Turbine power	550 W
Turhine		Air heater	600 W
		WARRANTY	
	- The Geysair® is located on the same side as the heated backrest. It must <b>NOT be relocated</b> .	Controls-LED-Geysair*	5 years
Others	It must be <b>connected to the hot water supply</b> and be accessible (provide access).  Integrated tile flange is included (specify right or left).  The water level will be lower when an Aroma-Flow is installed.	Bath & turbine*	20 years
		* Some restrictions apply   www.bainultra	a.com/warranty
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).			

# 60" x 32" x 17"

Citti® is derived from sanskrit for "free spirit." At the same time, the name evokes today's great cities: these are the perfect baths for urban living.



MODEL	тми	TUB		
Left	BC7DRA0LT-XX	BC7DRA0LN-XX		
Right	BC7DRA0RT-XX	BC7DRA0RN-XX		

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$3,700
Jets	42
1 heated backrest	Included
Mia® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud® BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$2,015
AromaCloud® BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type		Alcove (3 walls)		
Integrated skirt & tile flar	nge (specify rig	tht or left)	Installed & Included	
No. of bathers	*	Imp. gallo	ns	37
US gallons	45			
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Biscuit 02, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01 Biscuit 02				Included

OPTIONS (UPCHARGE APPLICABLE)	
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL1	\$650
CONTROL (TMU only) p.9	
MiaPlus®* BMIAP2-XX	\$285
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10	
Matte Black 19, Satin Brass 18	\$120
WASTE & OVERFLOW 16" x 35" BOVER16-XX p.10	
Chrome 07	\$260
White 01, Biscuit 02	\$290
Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11	\$400
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60
16" x 35" Cable driven brass waste & overflow kit BOVERBR	\$240



Turbine must be remotely installed. With the AromaCloud® and/or Control on the deck, a complete shower door cannot be installed. Faucets must be wall-mounted.

- Don't forget to specify the **finish of the integrated waste & overflow.**
- \* The MiaPlus® Control is included when purchasing Chromatherapy on a TMU.


  \*\* When ordering an AromaFlow, an Integrated waste & overflow
- is mandatory (Included). Specify the finish of the waste.

#### TO ORDER





### **CITTI** 17



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain (integrated waste & overflow)	10 3/8"
В	Outside edge to center of drain hole Waste & overflow 16" x 35" only	2 5/16"
С	Total length	60"
D	Total width	32"
E	Bathing well length	48 1/2"
F	Bathing well width	22 1/2"
G	Deck width (skirt side)	3 7/8"
Н	Deck width (backrest and drain sides)	3 3/16""
ı	Height from bottom of bath to top deck	17"
J	Maximum water level Maximum water level with AromaFlow	12 1/2" 10 13/16"
K	Slope of backrest	17°
L	Deck width wall side	2"
М	Outside edge to center drain	15 1/8"
N	Tile flange height	1"

⚠ AromaCloud® position

**ⓒ** Control position when factory-installed (Mia® or DOT)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	125 lb
supply required	Access to the number must be at least 10" v 20" Standard connection is 20 & 120 V CO Hz dedicated	Turbine power	550 W
Turbine		Air heater	600 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	WARRANTY	
Others  It must be connected to the hot water  The turbine must be remotely installer  Citti bathtubs include an integrated tile	The Geysair® is located on the same side as the heated backrest. It must <b>NOT be relocated</b> . It must <b>NOT be relocated</b> . It must be <b>connected to the hot water supply</b> and be accessible (provide access).	Controls-LED-Geysair*	5 years
	- Citti bathtubs include an integrated tile flange, specify right or left.	Bath & turbine*	20 years
	- The water level will be lower when an AromaFlow is installed.	* Some restrictions apply   www.bainultra.co	om/warranty
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).			



#### PRODUCT NO.

MODEL		тми	TUB
	Left	BCIDRAJLT-XX	BCIDRAJLN-XX
	Right	BCIDRAJRT-XX	BCIDRAJRN-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$4,935
Jets	42
1 heated backrest	Included
Mia® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud® BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$2,590
AromaCloud® BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type		Alcove (3 walls)		
Integrated skirt & tile flar	nge (specify rig	ght or left)	Installe	d & Included
No. of bathers	*	Imp. gallo	ns	42
US gallons	50			
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Biscuit 02, Chror Polished Nickel 10, Matte finish 32			Installe	d & Included
STANDARD COLOR p.13				
White 01 Biscuit 02				Included

OPTIONS (UPCHARGE APPLICABLE)	
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL1	\$650
CONTROL (TMU only) p.9	
MiaPlus®* BMIAP2-XX	\$285
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60




Turbine must be remotely installed. With the Control installed on the deck, a complete shower door cannot be installed. Faucets must be wall-mounted.

Don't forget to specify the **finish of the integrated waste & overflow.**\* The MiaPlus® Control is included when purchasing Chromatherapy


- \*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

#### TO ORDER









LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	10 7/8"
В	Total length	60"
С	Total width	32"
D	Bathing well length	49 1/4"
DD	Bathing well length - insert side	42 5/8"
E	Bathing well width	21 1/8"
F	Deck width (skirt side)	3 3/4"
G	Deck width at drain end	2 1/8"
н	Height from bottom of bath to top deck	20"
ı	Maximum water level Maximum water level with AromaFlow	14 1/2" 13 13/16"
J	Slope of backrest	17°
K	Deck width overflow side	2 1/8"
L	Outside edge to center drain	15 1/8"
М	Tile flange height	1"

⚠ AromaCloud® position

**ⓒ** Control position when factory-installed (Mia® or DOT)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	125 lb
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Turbine power	550 W
Turbine	e with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Air heater	600 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	WARRANTY	
	- Citti bathtubs include an integrated tile flange, specify right or left.	Controls-LED-Geysair*	5 years
Others		Bath & turbine*	20 years
	<ul> <li>Insert can be installed on right or left side.</li> <li>The water level will be lower when an AromaFlow is installed.</li> </ul>	* Some restrictions apply   www.bainultra.co	om/warranty

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

## CITTI 6032 WITHOUT INSERT

60" x 32" x 20"

Citti® is derived from sanskrit for "free spirit." At the same time, the name evokes today's great cities: these are the perfect baths for urban living.



MODEL	тми	TUB
Left	BCIDRA0LT-XX	BCIDRA0LN-XX
Right	BCIDRA0RT-XX	BCIDRA0RN-XX
Front Overflow – Left	BC3DRA0LT-XX	BC3DRA0LN-XX
Front Overflow - Right	BC3DRA0RT-XX	BC3DRA0RN-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$4,670
Jets	44
1 heated backrest	Included
Mia® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud® BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$2,315
AromaCloud® BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type	Installation type		Alcove (3 walls)	
Integrated skirt & tile flar	nge (specify rig	ght or left)	Installed & Included	
No. of bathers	*	Imp. gallons		44
US gallons	53			
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Biscuit 02, Chron Polished Nickel 10, Matte finish 32			Installe	d & Included
STANDARD COLOR p.13				
White 01 Biscuit 02				Included

OPTIONS (UPCHARGE APPLICABLE)	
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL1	\$650
CONTROL (TMU only) p.9	
MiaPlus®** BMIAP2-XX	\$285
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10	
Matte Black 19, Satin Brass 18	\$120
WASTE & OVERFLOW 16" X 35"* BOVER16-XX p.10	
Chrome 07	\$260
White 01, Biscuit 02	\$290
Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11	\$400
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60
16" x 35" Cable driven brass waste & overflow kit* BOVERBR	\$240




Turbine must be remotely installed. With the AromaCloud® and/or Control on the deck, a complete shower door cannot be installed. Faucets must be wall-mounted.

Don't forget to specify the **finish of the integrated waste & overflow.** 

- \* Only for models with front overflow.
- \*\* The MiaPlus® Control is included when purchasing Chromatherapy on a TMU.

  \*\*\* When ordering an AromaFlow, an Integrated waste & overflow
- is mandatory (Included). Specify the finish of the waste.

#### TO ORDER





#### **CITTI** 6032 WITHOUT INSERT

#### INSTALLATION LETTER DESCRIPTION MEASURE Outside edge to center drain (integrated waste & overflow) 10 7/8" Α Air intake Outside edge to center of drain hole Waste & overflow 16" x 35" Front Overflow only В 1 3/8" c Total length 60" D Total width 32" Е 49 1/4" Bathing well length Bathing well width 21 1/8" G Deck width (skirt side) 3 3/4" н Deck width at drain end 2 1/8" Height from bottom of bath to top deck 20" Maximum water level 14 1/2" Maximum water level with AromaFlow 13 13/16" Citti 6032 Front Overflow without insert С Κ Slope of backrest 17° Air intake L Deck width overflow side 2 1/8" М Outside edge to center drain 15 1/8" N Tile flange height ⚠ AromaCloud® position **ⓒ** Control position when factory-installed (Mia® or DOT) Indicates heated backrest (TMU) Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	125 lb
supply required	Access to the pump must be at least 18" x 22". Standard connection is 20 A. 120 V, 60 Hz, dedicated line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Turbine power	550 W
Turbine		Air heater	600 W
		WARRANTY	
	- The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).  - The turbine must be remotely installed Citti bathtubs include an integrated tile flange, specify right or left.	Controls-LED-Geysair*	5 years
Others		Bath & turbine*	20 years
	- The water level will be lower when an AromaFlow is installed.	* Some restrictions apply   www.bainultra	.com/warranty
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal			

The specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.

provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

# CITTI 6032 TRIO WITH INSERT

60" x 32" x 20"

Citti® is derived from sanskrit for "free spirit." At the same time, the name evokes today's great cities: these are the perfect baths for urban living.



MODEL	ТМИ	TUB
Std 1 1/2" deck – Left	BCTDRAJLT-XX	BCTDRAJLN-XX
Std 1 1/2" deck – Righ	t BCTDRAJRT-XX	BCTDRAJRN-XX
Slim deck – Left	BCTDRAKLT-XX	BCTDRAKLN-XX
Slim deck – Right	BCTDRAKRT-XX	BCTDRAKRN-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$4,920
Jets	42
1 heated backrest	Included
Mia® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud® BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$2,560
AromaCloud® BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type			A	Icove (3 walls)
No. of bathers	*	Integrated	tile flange	Included
US gallons	50	Imp. gallo	ns	42
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Biscuit 02, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
White 01 Biscuit 02				Included

OPTIONS (UPCHARGE APPLICABLE)	
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL1	\$650
CONTROL (TMU only) p.9	
MiaPlus®* BMIAP2-XX	\$285
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
SKIRT MULTIFIT (standard 11/2" deck only) BSMUL-XX p. 24	13
White 01, Biscuit 02	\$600
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60

Turbine must be remotely installed in certain conditions. With the Control installed on the deck, a complete shower door cannot be installed.

- Faucets must be wall-mounted.
  Don't forget to specify the **finish of the integrated waste & overflow.**\* The MiaPlus® Control is included when purchasing Chromatherapy
- \*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.


#### TO ORDER








#### INSTALLATION





К	· FM
	I H

LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	10 7/8"
В	Total length	60"
С	Total width	32"
D	Bathing well length	49 1/4"
DD	Bathing well length - insert side	42 5/8"
E	Bathing well width	21 1/8"
F	Deck width (skirt side)	3 3/4"
G	Deck width at drain end	2 1/8"
Н	Height from bottom of bath to top deck	20"
ı	Maximum water level Maximum water level with AromaFlow	14 1/2" 13 13/16"
J	Slope of backrest	17°
K	Height from bottom of deck to top standard deck	1 1/2"
L	Height from bottom of deck to top slim deck	1/2"
М	Tile flange height	1"
N	Deck width overflow side	2 1/8"
0	Outside edge to center drain	15 1/8"

⚠ AromaCloud® position

**●** Control position when factory-installed (Mia® or DOT)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS				
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	125 lb	
supply required	Access to the pump must be at least 18" x 22". Standard connection is 20 A. 120 V, 60 Hz, dedicated line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.  - The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).  - The turbine must be remotely installed.  - Citti bathtubs include an integrated tile flange, specify right or left Insert can be installed on right or left side The water level will be lower when an AromaFlow is installed.	Turbine power	550 W	
Turbine Others		Air heater	600 W	
		WARRANTY		
		Controls-LED-Geysair*	5 years	
		Bath & turbine*	20 years	
		* Some restrictions apply   www.bainultra	a.com/warranty	

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

## TTI 6032 TRIO WITHOUT INSERT

60" x 32" x 20"

Citti® is derived from sanskrit for "free spirit." At the same time, the name evokes today's great cities: these are the perfect baths for urban living.




MODEL	TMU	TUB
Std 1 1/2" deck – Left	BCTDRA0LT-XX	BCTDRA0LN-XX
Std 1 1/2" deck – Righ	t BCTDRA0RT-XX	BCTDRA0RN-XX
Slim deck – Left	BCTDRA1LT-XX	BCTDRA1LN-XX
Slim deck – Right	BCTDRA1RT-XX	BCTDRA1RN-XX
Front Overflow – Std 1 1/2" deck – Left	BC2DRA0LT-XX	BC2DRA0LN-XX
Front Overflow – Std 1 1/2" deck – Righ	t BC2DRA0RT-XX	BC2DRA0RN-XX
Front Overflow – Slim deck Left	BC2DRA1LT-XX	BC2DRA1LN-XX
Front Overflow – Slim deck Right	BC2DRA1RT-XX	BC2DRA1RN-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$4,665
Jets	44
1 heated backrest	Included
Mia® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud® BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$2,315
AromaCloud® BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES					
Installation typ	е			А	lcove (3 walls)
No. of bathers		*	US gallons	:	53
Integrated tile (specify right or le		Included	Imp. gallo	ns	44
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10					
White 01, Biscuit 02, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32				Inst. & Incl.	
STANDARD COLOR p.13					
White 01 Bi	scuit 02				Included

FINISH p.6 UltraVelour Matte Finish (white only) BVEL1 \$650 CONTROL (TMU only) p.9 MiaPlus®\*\* BMIAP2-XX \$285 UNIVERSAL ARMRESTS BGBGU-XX p. 12 White 01 \$750 SKIRT MULTIFIT (standard 11/2" deck only) BSMUL-XX p. 243 White 01, Biscuit 02 \$600 **INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10** 



\$120

Turbine must be remotely installed. With the AromaCloud®

Matte Black 19, Satin Brass 18

Std 1 1/2" deck with optional Multifit skirt


**OPTIONS (UPCHARGE APPLICABLE)** 

and/or Control on the deck, a complete shower door cannot be installed. Faucets must be wall-mounted.

Don't forget to specify the **finish of the integrated waste & overflow.** 


- \* Only for models with front overflow
- \*\* The MiaPlus® Control is included when purchasing Chromatherapy on a TMU.
- \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.





#### **CITTI** 6032 **TRIO** WITHOUT INSERT

Others



The specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.

Bath & turbine\*

\* Some restrictions apply | www.bainultra.com/warranty

The turbine must be **remotely installed**.

Citti bathtubs include an integrated tile flange, specify right or left.


Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

The water level will be lower when an AromaFlow is installed.

20 years

66" x 36" x 21"

With shapes and lines that take us back to the Victorian era, this collection transcends time, fitting right in with today's styles.



	i Roboti ito.					
MODEL		тми	TUB			
	C10	BELLRDA0T-XX	BELLRDA0N-XX			
	C11	BELLODB0T-XX	BELLODBON-XX			
	C13	BELLODD0T-XX	BELLODD0N-XX			
	C14	BELLODE0T-XX	BELLODE0N-XX			

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$6,330
Jets	36
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud® BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$3,135
AromaCloud® BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES			
Installation type			Drop-in
No. of bathers	* *	Armrests	4
US gallons	46	Grab bars (color match)	2
Imp. gallons	38		
STANDARD COLOR p.	13		
White 01 Biscuit 02			Included

OPTIONS (UPCHARGE APPLICABLE)			
GRAB BARS p.12		CLEA	R ACRYLIC* BGBG10-XX
Chrome 07			\$60
Brushed Nickel 09			\$60
Polished Nickel 10			N/A
WASTE & OVERFLOW p.10	D13 BOVER D13-XX	D14** BOVER D14-XX	INTE- GRATED*** BOVERIN-XX
Chrome 07	\$490	\$250	\$235
White 01, Biscuit 02	N/A	\$265	\$235
Brushed Nickel 09, Polished Nickel 10	\$500	\$270	\$235
Unplated 00, Oil-rubbed Bronze 11	\$500	N/A	N/A
Matte Black 19, Satin Brass 18	N/A	N/A	\$355

## Don't forget to select a contour among the 4 available to choose from. \* Specify insert finish. With Chrome or Brushed Nickel inserts. \*\* Piping is not included for the waste & overflow D14.

- \*\*\* Only when ordering an AromaFlow; an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste. With the AromaFlow, the included Grab Bars can not be installed.






## Contour C13

#### INSTALLATION

**ELEGANCIA** 6636



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11 1/2"
В	Outside edge to overflow	5 1/2"
С	Total length	66"
D	Total width	36"
E	Bathing well length	42"
F	Bathing well width	21 3/8"
G	Deck width (widest point)	5 1/4"
Н	Deck width at backrest end	4 3/4"
ı	Height from bottom of drain to center of overflow	16"
J	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	14 5/16" 14 5/16"
K	Slope of backrests	30°

- ⚠ AromaCloud® position
- **ⓒ** Control position when factory-installed (Mia® or DOT)
- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

#### CHOOSE YOUR CONTOUR



Drop-in C10









Drop-in C13

LETTER	М	N	0
DESCRIPTION	Deck width (narrowest point)	Height from bottom of bath to top deck	Height from bottom of bath to bottom of deck
C10	3 1/4"	20 3/4"	18 1/4"
C11	3 1/2"	20 5/8"	17 5/8"
C13	3 5/8"	20 5/8"	18 5/8"
C14	3 1/4"	20 3/4"	18 1/4"


TECHNICAL SPECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting ter
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is</b>	Approx. sh
Turbine	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Turbine po
Others	- The Geysair® is located on the same side as the heated backrest. It must <b>NOT be relocated</b> .	Air heater
It must be <b>connected to the hot water supply</b> and be accessible (provide access).  Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal,		WARRANT
	rovincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	
		Doth 0 turk

Cutting template	# 90000044 (C11, C13 & C14)
Approx. shipping weight	135 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years

 $<sup>\</sup>mbox{\tt *}$  Some restrictions apply | www.bainultra.com/warranty

66" x 42" x 21"

With shapes and lines that take us back to the Victorian era, this collection transcends time, fitting right in with today's styles.



ı	PRODUCT NO.				
	MODEL	ТМU	TUB		
	C10	BELNRDA0T-XX	BELNRDA0N-XX		
	C11	BELNODB0T-XX	BELNODB0N-XX		
	C13	BELNODD0T-XX	BELNODD0N-XX		
	C14	BELNODE0T-XX	BELNODE0N-XX		

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$6,455
Jets	38
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud® BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$3,205
AromaCloud® BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES			
Installation type		Drop-in	
No. of bathers	* *	Armrests	4
US gallons	53	Grab bars (color match)	2
Imp. gallons	44		
STANDARD COLOR p.	13		
White 01 Biscuit 02			Included

OPTIONS (UPCHARGE APPLICABLE)			
GRAB BARS p.12		CLEA	AR ACRYLIC* BGBG10-XX
Chrome 07			\$60
Brushed Nickel 09		\$60	
Polished Nickel 10		N/A	
WASTE & OVERFLOW p.10	D13 BOVER D13-XX	<b>D14**</b> BOVER D14-XX	INTE- GRATED*** BOVERIN-XX
Chrome 07	\$490	\$250	\$235
White 01, Biscuit 02	N/A	\$265	\$235
Brushed Nickel 09, Polished Nickel 10	\$500	\$270	\$235
Unplated 00, Oil-rubbed Bronze 11	\$500	N/A	N/A
Matte Black 19, Satin Brass 18	N/A	N/A	\$355

## Don't forget to select a contour among the 4 available to choose from. \* Specify insert finish. With Chrome or Brushed Nickel inserts. \*\* Piping is not included for the waste & overflow D14.

- \*\*\* Only when ordering an AromaFlow; an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste. With the AromaFlow, the included Grab Bars can not be installed.




Contour C10

## **ELEGANCIA** 6642



#### INSTALLATION



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	12 1/2"
В	Outside edge to overflow	6 1/2"
С	Total length	66"
D	Total width	42"
E	Bathing well length	41 3/4"
F	Bathing well width	25 3/8"
G	Deck width (widest point)	6 1/8"
Н	Deck width at backrest end	4 3/4"
1	Height from bottom of drain to center of overflow	16"
J	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	14 5/16" 14 5/16"
K	Slope of backrests	30°

- ⚠ AromaCloud® position
- **ⓒ** Control position when factory-installed (Mia® or DOT)
- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

#### CHOOSE YOUR CONTOUR



Drop-in C10











Drop-in C13 Drop-in C14

LETTER	М	N	0
DESCRIPTION	Deck width (narrowest point)	Height from bottom of bath to top deck	Height from bottom of bath to bottom of deck
C10	2 7/8"	20 3/4"	18"
C11	3 1/4"	20 5/8"	17 1/8"
C13	2 5/8"	20 5/8"	18 5/8"
C14	2 3/4"	20 3/4"	18"

TECHNICAL SPECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	
Others	- The Geysair® is located on the same side as the heated backrest. It must <b>NOT be relocated</b> . It must be <b>connected to the hot water supply</b> and be accessible (provide access).	
	t be installed by certified professionals only and according to our Owner's Manual as well as federal, d local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	

# 90000043 (C11, C13 & C14)
140 lb
550 W
600 W
5 years
20 years

 $<sup>\</sup>mbox{*}$  Some restrictions apply | www.bainultra.com/warranty

72" x 36" x 21"

With shapes and lines that take us back to the Victorian era, this collection transcends time, fitting right in with today's styles.



MODEL	тми	TUB
C10	BELSRDA0T-XX	BELSRDA0N-XX
C11	BELSODB0T-XX	BELSODB0N-XX

BELSODD0T-XX BELSODDON-XX C13 BELSODE0T-XX BELSODE0N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$6,500
Jets	38
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud® BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$3,270
AromaCloud® BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation t	ype			Drop-in
No. of bathe	rs	**	Armrests	4
US gallons		52	Grab bars (color match)	2
Imp. gallons		44		
STANDARD	COLOR p. 1	3		
White 01	Biscuit 02			Included

OPTIONS (UPCHARGE APPLICABLE)			
GRAB BARS p.12		CLEA	R ACRYLIC* BGBG10-XX
Chrome 07			\$60
Brushed Nickel 09		\$60	
Polished Nickel 10		N/A	
WASTE & OVERFLOW p.10	D13 BOVER D13-XX	D14** BOVER D14-XX	INTE- GRATED*** BOVERIN-XX
Chrome 07	\$490	\$250	\$235
White 01, Biscuit 02	N/A	\$265	\$235
Brushed Nickel 09, Polished Nickel 10	\$500	\$270	\$235
Unplated 00, Oil-rubbed Bronze 11	\$500	N/A	N/A
Matte Black 19, Satin Brass 18	N/A	N/A	\$355

Don't forget to select a contour among the 4 available to choose from.

\* Specify insert finish. With Chrome or Brushed Nickel inserts.

\*\* Piping is not included for the waste & overflow D14.


- \*\*\* Only when ordering an AromaFlow; an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste. With the AromaFlow, the included Grab Bars can not be installed.














LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11 5/8"
В	Outside edge to overflow	5 5/8"
С	Total length	72"
D	Total width	36 1/8"
E	Bathing well length	47 1/4"
F	Bathing well width	21 3/8"
G	Deck width (widest point)	5 1/4"
Н	Deck width at backrest end	5 1/8"
ı	Height from bottom of drain to center of overflow	16"
J	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	14 5/16" 14 5/16"
K	Slope of backrests	30°

- ⚠ AromaCloud® position
- **ⓒ** Control position when factory-installed (Mia® or DOT)
- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

#### CHOOSE YOUR CONTOUR



Drop-in C10











Drop-in C14

LETTER	М	N	0
DESCRIPTION	Deck width (narrowest point)	Height from bottom of bath to top deck	Height from bottom of bath to bottom of deck
C10	1 7/8"	20 3/4"	18 1/4"
C11	1 7/8"	20 5/8"	17 5/8"
C13	1 1/4"	20 5/8"	18 5/8"
C14	1 5/8"	20 3/4"	18 1/4"


TECHNICAL SPECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	
Others	- The Geysair® is located on the same side as the heated backrest. It must <b>NOT be relocated</b> . It must <b>be connected to the hot water supply</b> and be accessible (provide access).	
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).		

Cutting template	# 90000042 (C11, C13 & C14)
Approx. shipping weight	137 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years

<sup>\*</sup> Some restrictions apply  $\mid$  www.bainultra.com/warranty

72" x 42" x 21"

With shapes and lines that take us back to the Victorian era, this collection transcends time, fitting right in with today's styles.



TRODUCT NO.				
MODEL	TMU	TUB		
C10	BELVRDA0T-XX	BELVRDA0N-XX		
C11	BELVODB0T-XX	BELVODB0N-XX		
C13	BELVODD0T-XX	BELVODD0N-XX		
C14	BELVODE0T-XX	BELVODE0N-XX		

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$6,585
Jets	40
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud® BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$3,420
AromaCloud® BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES			
Installation type			Drop-in
No. of bathers	* *	Armrests	4
US gallons	60	Grab bars (color match)	2
Imp. gallons	50		
STANDARD COLOR p. 1	3		
White 01 Biscuit 02			Included

OPTIONS (UPCHARGE APPLICABLE)			
GRAB BARS p.12 CLEAR ACRY BGBG1		AR ACRYLIC* BGBG10-XX	
Chrome 07			\$60
Brushed Nickel 09			\$60
Polished Nickel 10			N/A
WASTE & OVERFLOW p.10	D13 BOVER D13-XX	D14** BOVER D14-XX	INTE- GRATED*** BOVERIN-XX
Chrome 07	\$490	\$250	\$235
White 01, Biscuit 02	N/A	\$265	\$235
Brushed Nickel 09, Polished Nickel 10	\$500	\$270	\$235
Unplated 00, Oil-rubbed Bronze 11	\$500	N/A	N/A
Matte Black 19, Satin Brass 18	N/A	N/A	\$355

Don't forget to select a contour among the 4 available to choose from.

\* Specify insert finish. With Chrome or Brushed Nickel inserts.

\*\* Piping is not included for the waste & overflow D14.

- \*\*\* Only when ordering an AromaFlow; an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste. With the AromaFlow, the included Grab Bars can not be installed.

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com


172













LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	12 5/8"
В	Outside edge to overflow	6 5/8"
С	Total length	71 1/2"
D	Total width	41 1/2"
E	Bathing well length	47 1/4"
F	Bathing well width	25 3/8"
G	Deck width (widest point)	6 1/4"
Н	Deck width at backrest end	5 1/8"
I	Height from bottom of drain to center of overflow	16"
J	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	14 5/16" 14 5/16"
К	Slope of backrests	30°

- ♠ AromaCloud® position
- **ⓒ** Control position when factory-installed (Mia® or DOT)
- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

#### CHOOSE YOUR CONTOUR



Drop-in C10









Drop-in C13 Drop-in C14

LETTER	М	N	0
DESCRIPTION	Deck width (narrowest point)	Height from bottom of bath to top deck	Height from bottom of bath to bottom of deck
C10	2 5/8"	20 3/4"	18"
C11	2 7/8"	20 5/8"	17 1/8"
C13	2"	20 5/8"	18 5/8"
C14	2 1/2"	20 3/4"	18"

TECHNICAL SPECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cut
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	App Tur
Others	- The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).	Air
	be installed by certified professionals only and according to our Owner's Manual as well as federal, d local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	Con

Cutting template	# 90000041 (C11, C13 & C14)
Approx. shipping weight	141 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years



THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$6,425
Jets	50
1 heated backrest & headrest	Included
MiaPlus® Control*	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud® BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$4,525
AromaCloud® BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type				Drop-in
No. of bathers	*	Inverted V		1
US gallons	61	Armrests		2
Imp. gallons	51	Grab bars	(color match)	2
Raised seats	1	Footrest		Included
WASTE & OVERFLOW	16" x 35" BC	OVER16I-XX p.	.10	
White 01, Biscuit 02, Chro Brushed Nickel 09, Polish Oil-rubbed Bronze 11		,	Installed	d & Included
STANDARD COLOR p.13				
White 01 Biscuit 02				Included

OPTIONS (UPCHARGE APPLICABLE)		
FINISH p.6		
UltraVelour Matte Finish (white only) BVEL2	\$850	
CLEAR ACRYLIC GRAB BARS BGBG10-XX p.12		
With Chrome 07 or Brushed Nickel 09 inserts	\$60	
INTEGRATED WASTE & OVERFLOW BOVERIN-XX p.10		
White 01, Biscuit 02, Chrome 07, Brushed Nickel 09, Polished Nickel 10	\$235	
Oil-rubbed Bronze 11	N/A	
Matte Black 19, Satin Brass 18	\$355	
IF REQUIRED BY CONSTRUCTION CODE		
16" x 35" Cable driven brass waste & overflow kit BOVERBR	\$240	




- \* For TMU, control must be wall mounted. Faucets cannot be installed
- on the deck of the bath.

  \*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.


#### TO ORDER







## **ESSENCIA OVAL** 7236



LETTER	DESCRIPTION	MEASURE
Α	Total length	72"
В	Total width	36"
c	Outside edge to center drain	30 1/2"
D	Outside edge to overflow	20 1/2"
E	Bathing well width	21"
F	Raised seat length	22 5/8"
G	Bottom bathing well length	38"
н	Bathing well length	45 1/4"
ı	Deck width (top)	2 5/8"
J	Deck width (raised deck)	1 1/2"
K	Total height to headrest	24 7/8"
L	Slope of backrest	30°
М	Slope on drain side	32°
N	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	16 5/8" 16 9/16"
0	Height from bottom of drain to center of overflow	18 3/8"
P	Height from bottom of bath to top deck	23 1/2"
Q	Minimum faucet dimension	6 3/8"
R	Deck height at footrest	1"

- ▲ AromaCloud® position
- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS					
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000056		
supply required	Access to the pump must be at least 18" × 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Approx. shipping weight	146 lb		
Turbine lin		Turbine power	550 W		
		Air heater	600 W		
	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).</li> <li>Faucets cannot be installed on the deck of the bath.</li> <li>TMU: Control must be wall-mounted.</li> <li>TUB: Dot controls are located on the side of the AromaCloud®.</li> <li>The water level will be lower when an AromaFlow is installed.</li> </ul>	WARRANTY			
Others		Controls-LED-Geysair*	5 years		
		Bath & turbine*	20 years		
	be installed by certified professionals only and according to our Owner's Manual as well as federal, d local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainult	ra.com/warranty		

Esthesia, the new expression of beauty in the world of therapeutic baths. Neoclassically inspired Esthesia baths boast clean, purely geometric designs.



MODEL		тми	TUB
	Standard 2" deck	BEAMRD00T-XX	BEAMRD00N-XX
	Slim deck 1/2"	BEAMRD10T-XX	BEAMRD10N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$5,875
Jets	38
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud® BAROMAC	\$490
AromaFlow* BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$2,975
AromaCloud® BAROMAC	\$490
AromaFlow* BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			Drop-in	
No. of bathers	<b>† †</b> Imp. gallons		าร	49
US gallons	59			
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10				
White 01, Biscuit 02, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32				d & Included
STANDARD COLOR p. 13				
White 01 Biscuit 02				Included

OPTIONS (UPCHARGE APPLICABLE)	
FINISH p.6	
UltraVelour Matte Finish (white only) BVEL1	\$650
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10	
Matte Black 19, Satin Brass 18	\$120
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60

Don't forget to specify the **finish of the integrated waste & overflow**. Don't forget to specify the deck height (1/2" or 2").


\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.





#### **ESTHESIA** 6638

#### INSTALLATION




LETTER	DESCRIPTION	MEASURE
Α	Total length	66"
В	Total width	38"
С	Bathing well length	47 3/8"
D	Bathing well width	23"
E	Deck width (narrowest point)	2 5/8"
F	Deck width at 2 <sup>nd</sup> backrest	2 5/8"
G	Deck to drain center	19"
Н	Total height	21"
ı	Height from bottom of bath to bottom of standard deck 2"	19"
J	Slope of 2 <sup>nd</sup> backrest	21°
K	Slope of backrest	26°
L	Deck to edge of overflow	3 1/2"
М	Height from bottom of drain to center of overflow	16 5/8"
N	Maximum water level Maximum water level with AromaFlow	15 7/8" 15 1/8"
0	Height from bottom to top of deck	2"
P	Height from bottom to top of slim deck	1/2"

- ⚠ AromaCloud® position
- © Control position when factory-installed (Mia® or DOT)
- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000066
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	120 lb
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power	550 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W
Others	- The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.  It must be connected to the hot water supply and be accessible (provide access).	WARRANTY	
	- The water level will be lower when an AromaFlow is installed.	Controls-LED-Geysair*	5 years
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).		Bath & turbine*	20 years

 $<sup>\</sup>mbox{\tt *}$  Some restrictions apply | www.bainultra.com/warranty



MODEL		тми	TUB	
	Standard 1 1/2" deck	BINFRD00T-XX	BINFRD00N-XX	
	Slim deck 1/2"	BINFRD10T-XX	BINFRD10N-XX	

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$7,930
Jets	46
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud® BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$4,930
AromaCloud® BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type	Installation type			Drop-in
No. of bathers	•	Inverted V		1
US gallons	54	Armrests		2
Imp. gallons	45	Grab bars (color match)		2
Raised seats	1	Comfort Cushion (specify color: Grey or Black) p. 37		1
STANDARD COLOR p.13				
White 01 Biscuit 02				Included

OPTIONS (UPCHARGE APPLICABLE)		
FINISH p.6		
UltraVelour Matte Finish (white only) BVEL1		\$650
CLEAR ACRYLIC GRAB BARS BGBG10-XX p.12		
With Chrome 07 or Brushed Nickel 09 inserts		\$60
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED BOVERIN-XX
Chrome 07	\$260	\$235
White 01, Biscuit 02	\$290	\$235
Matte White with UltraVelour finish 32	N/A	\$235
Brushed Nickel 09, Polished Nickel 10	\$400	\$235
Oil-rubbed Bronze 11	\$400	N/A
Matte Black 19, Satin Brass 18 N/A		\$355
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit* BDRCOB		\$240
Brass waste kit* BDRCB		\$60
16" x 35" Cable driven brass waste & overflow kit BOVERBR		\$240



Don't forget to specify the deck height (1/2" or 1 1/2"). Faucet must be

- \* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.


#### TO ORDER






#### INSTALLATION

 With the AromaCloud®, you must choose to install the control or the faucet on opposite side.





LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11 1/4"
В	Outside edge to overflow	4 1/2"
С	Total length	60"
D	Total width	36"
E	Bathing well length	42 1/4"
F	Bathing well width at center zone	23"
G	Raised seat length	20 1/8"
Н	Deck width at backrest end	4 1/8"
I	Deck width at drain end	4 1/8"
J	Deck width	4"
K	Height from bottom of bath to top deck	23"
L	Total height to headrest	21"
М	Height from bottom of bath to bottom of standard deck	19 1/2"
M'	Height from bottom of bath to bottom of slim deck	20 1/2"
N	Height from bottom of drain to center of overflow	17 1/8"
0	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	15 3/8" 16 3/8" 15 3/8"
P	Slope of backrest	24°
Q	Minimum spout reach	8"
R	Slim deck minimum height	1/2"
S	Standard deck minimum height	1 1/2"


- ⚠ AromaCloud® position
- Control position when factory-installed (Mia® or DOT)
- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	
Therapeutic Comfort Cushion - INCLUDED	Made of ultraresistant urethane gel     Extremely comfortable and soft to the touch     Fully waterproof - Remarkably durable - Color available: Grey + Black	
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> <li>The water level may vary when an AromaFlow or an Integrated waste &amp; overflow is installed.</li> </ul>	

Approx. shipping weight	137 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Bath & turbine*	20 years

 $<sup>\</sup>mbox{*}$  Some restrictions apply | www.bainultra.com/warranty

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).



TRODUCT NO.			
MODEL	TMU	TUB	
Standard 1 1/2" deck	BINLRD00T-XX	BINLRD00N-XX	

BINLRD10T-XX

BINLRD10N-XX

PRODUCT NO

Slim deck 1/2"

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$7,975
Jets	50
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud® BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$4,955
AromaCloud® BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type				Drop-in
No. of bathers	•	Inverted V		1
US gallons	62	Armrests		2
Imp. gallons	51	Grab bars	(color match)	2
Raised seats	1	Comfort C (specify colo Grey or Blac	r:	1
STANDARD COLOR p.	13			
White 01 Biscuit 02				Included

OPTIONS (UPCHARGE APPLICABLE)		
FINISH p.6		
UltraVelour Matte Finish (white only) BVEL1		\$650
CLEAR ACRYLIC GRAB BARS BGBG10-XX p. 1	2	
With Chrome 07 or Brushed Nickel 09 inserts		\$60
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED BOVERIN-XX
Chrome 07	\$260	\$235
White 01, Biscuit 02	\$290	\$235
Matte White with UltraVelour finish 32	N/A	\$235
Brushed Nickel 09, Polished Nickel 10	\$400	\$235
Oil-rubbed Bronze 11	\$400	N/A
Matte Black 19, Satin Brass 18	N/A	\$355
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit* BDRCOB		\$240
Brass waste kit* BDRCB		\$60
16" x 35" Cable driven brass waste & overflow kit BOVERBR		\$240



Don't forget to specify the deck height (1/2" or 1 1/2"). Faucet must be installed on the deck flat surface.

- \* When ordered with integrated waste & overflow.
- \*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.

#### TO ORDER

Standard 1 1/2" deck







#### **INUA** 6636

#### INSTALLATION

 With the AromaCloud®, you must choose to install the control or the faucet on opposite side.





LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11 1/4"
В	Outside edge to overflow	4 1/2"
С	Total length	66"
D	Total width	36"
E	Bathing well length	48 1/8"
F	Bathing well width at center zone	22 7/8"
G	Raised seat length	20 1/8"
Н	Deck width at backrest end	4 1/8"
I	Deck width at drain end	4 1/8"
J	Deck width	4"
K	Height from bottom of bath to top deck	23"
L	Total height to headrest	21"
М	Height from bottom of bath to bottom of standard deck	19 1/2"
M'	Height from bottom of bath to bottom of slim deck	20 1/2"
N	Height from bottom of drain to center of overflow	17 1/8"
0	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	15 3/8" 16 5/16" 15 3/8"
P	Slope of backrest	24°
Q	Minimum spout reach	8"
R	Slim deck minimum height	1/2"
S	Standard deck minimum height	1 1/2"

- ⚠ AromaCloud® position
- Control position when factory-installed (Mia® or DOT)
- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

138 lb 550 W 600 W

5 years 20 years

TECHNICAL SP	ECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	138 I
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Turbine power	550 V
Turbine	Turbine line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Air heater	600 \
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	WARRANTY	
Comfort Cushion		Controls-LED-Geysair*	5 year
- INCLUDED	- Fully waterproof - Remarkably durable - Color available: Grey + Black	Bath & turbine*	20 year
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> <li>The water level may vary when an AromaFlow or an Integrated waste &amp; overflow is installed.</li> </ul>	* Some restrictions apply   www.bainultra	a.com/warranty

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

## **INUA** 7240

72" x 40" x 23"

In Inuit spirituality Inua means "everything that lives." INUA is the universal soul that unites all things in nature.



MODEL	тми	TUB	
Standard 1 1/2" deck	BINURD00T-XX	BINURD00N-XX	
Slim deck 1/2"	BINURD10T-XX	BINURD10N-XX	

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$8,500
Jets	58
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud® BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$5,470
AromaCloud® BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type				Drop-in
No. of bathers	* *	Inverted V		2
US gallons	67	Armrests		4
Imp. gallons	56	Grab bars	(color match)	2
Raised seats	2	Comfort C (specify colo Grey or Blac	r:	2
STANDARD COLOR p.13				
White 01 Riscuit 02				Included

OPTIONS (UPCHARGE APPLICABLE)		
FINISH p.6		
UltraVelour Matte Finish (white only) BVEL1		\$650
CLEAR ACRYLIC GRAB BARS BGBG10-XX p.12		
With Chrome 07 or Brushed Nickel 09 inserts		\$60
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED BOVERIN-XX
Chrome 07	\$260	\$235
White 01, Biscuit 02	\$290	\$235
Matte White with UltraVelour finish 32	N/A	\$235
Brushed Nickel 09, Polished Nickel 10	\$400	\$235
Oil-rubbed Bronze 11	\$400	N/A
Matte Black 19, Satin Brass 18	N/A	\$355
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit* BDRCOB		\$240
Brass waste kit* BDRCB		\$60
16" x 35" Cable driven brass waste & overflow kit BOVERBR		\$240



Don't forget to specify the deck height (1/2" or 1 1/2"). Faucet must be installed on the deck flat surface.

- \* When ordered with integrated waste & overflow.
- \*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste. With the AromaFlow, the included Grab Bars can not be installed.

#### TO ORDER









#### **INUA** 7240

#### INSTALLATION

 With the AromaCloud®, you must choose to install the control or the faucet on opposite side.





LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	20"
В	Outside edge to overflow	4 1/2"
С	Total length	72"
D	Total width	40"
E	Bathing well length	49 1/8"
F	Bathing well width at center zone	25 1/8"
G	Raised seat length	17 1/8"
Н	Deck width at backrest end	4 5/8"
I	Deck width	4 5/8"
J	Deck width	4 5/8"
K	Height from bottom of bath to top deck	23"
L	Total height to headrest	21"
М	Height from bottom of bath to bottom of standard deck	19 1/2"
M'	Height from bottom of bath to bottom of slim deck	20 1/2"
N	Height from bottom of drain to center of overflow	17 1/8"
0	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	15 3/8" 16 3/8" 15 15/16"
P	Slope of backrests	24°
Q	Minimum spout reach	8 3/4"
R	Slim deck minimum height	1/2"
s	Standard deck minimum height	1 1/2"

- ⚠ AromaCloud® position
- Control position when factory-installed (Mia® or DOT)
- Turbine position (TMU)
- Indicates heated backrest (TMU)

153 lb 550 W 600 W

5 years 20 years

Indicates WarmTouchShell® position (TUB)

TECHNICAL SP	ECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	153 l
supply required	Accorded to a construction of the state of AOU Construction in 20.8 ACCORD desired	Turbine power	550 V
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is</b>	Air heater	600 V
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	WARRANTY	
Comfort Cushion		Controls-LED-Geysair*	5 year
- INCLUDED	- Fully waterproof - Remarkably durable - Color available: Grey + Black	Bath & turbine*	20 year
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> <li>The water level will vary when an AromaFlow or an Integrated waste &amp; overflow is installed.</li> </ul>	* Some restrictions apply   www.bainultra	a.com/warranty

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

66" x 36" x 21"

Named after the meridians of our body—the paths along which our energy flows—the collection also brings to mind the meridian (or mid-point) of life with an invitation to relax and listen to your body and mind.



MODEL	ТМИ	TUB	
Rolled deck	BMELOUM0T-XX	BMELOUM0N-XX	
Flat deck	BMELOUN0T-XX	BMELOUN0N-XX	

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$6,080
Jets	38
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$2,690
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES			
Installation type			Drop-in
No. of bathers	* *	Imp. gallons	40
US gallons	48		
STANDARD COLOR p. 1	3		
White 01 Biscuit 02			Included

Flat deck

OPTIONS (UPCHARGE APPLICABLE)		
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED** BOVERIN-XX
Chrome 07	\$260	\$235
White 01, Biscuit 02	\$290	\$235
Brushed Nickel 09, Polished Nickel 10	\$400	\$235
Oil-rubbed Bronze 11	\$400	N/A
Matte Black 19, Satin Brass 18	N/A	\$355
IF REQUIRED BY CONSTRUCTION CODE		
16" x 35" Cable driven brass waste & overflow kit BOVERBR		\$240



Don't forget to indicate flat or rolled deck.

\* The AromaCloud® is built into the deck (factory installed).

\*\* Only when ordering an AromaFlow; an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.


#### TO ORDER









#### INSTALLATION








LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11 1/2"
В	Outside edge to overflow	4 5/8"
С	Total length	66"
D	Total width	36"
E	Bathing well length	42 3/8"
F	Bathing well width	22 1/4"
G	Deck width at backrest end	4 3/8"
Н	Flat surface width	4 1/4"
ı	Rolled deck width	4 3/4"
J	Height from bottom of bath to top deck	21"
K	Height from bottom of bath to top deck	22"
L	Height from bottom of bath to bottom of deck	19 1/2"
М	Height from bottom of deck to top deck	2 1/2"
N	Height from bottom of drain to center of overflow	16 5/8"
0	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	14 7/8" 14 3/8"
P	Slope of backrest	25°

- AromaCloud® position
- **●** Control position when factory-installed (Mia® or DOT)
- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS				
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000055	
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	100 lb	
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power	550 W	
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W	
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	WARRANTY		
Others	- There is a height difference for the rolled deck (see drawing Detail Å) The water level will be lower when an AromaFlow is installed.	Controls-LED-Geysair*	5 years	
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal,		Bath & turbine*	20 years	
provincial/state an	d local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainul	tra.com/warranty	

72" x 40" x 21"

Named after the meridians of our body—the paths along which our energy flows—the collection also brings to mind the meridian (or mid-point) of life with an invitation to relax and listen to your body and mind.



MODEL	тми	TUB
Rolled deck	BMEUOUM0T-XX	BMEUOUM0N-XX
Flat deck	BMEUOUN0T-XX	BMEUOUN0N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$6,420
Jets	40
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$2,970
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES			
Installation type			Drop-in
No. of bathers	* *	Imp. gallons	49
US gallons	59		
STANDARD COLOR p. 1	3		
White 01 Biscuit 02			Included

OPTIONS (UPCHARGE APPLICABLE)			
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED** BOVERIN-XX	
Chrome 07	\$260	\$235	
White 01, Biscuit 02	\$290	\$235	
Brushed Nickel 09, Polished Nickel 10	\$400	\$235	
Oil-rubbed Bronze 11	\$400	N/A	
Matte Black 19, Satin Brass 18	N/A	\$355	
IF REQUIRED BY CONSTRUCTION CODE			
16" x 35" Cable driven brass waste & overflow kit BOVERBR		\$240	



Don't forget to indicate flat or rolled deck.

\* The AromaCloud® is built into the deck (factory installed).

\*\* Only when ordering an AromaFlow; an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.

#### TO ORDER








INSTALLATION

## For rolled deck: deck modified to host the AromaCloud®

With flat deck, the AromaCloud® is built into the deck



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11 3/4"
В	Outside edge to overflow	4 7/8"
С	Total length	72"
D	Total width	40"
E	Bathing well length	46 1/8"
F	Bathing well width	24 3/4"
G	Deck width at backrest end	4 3/4"
Н	Deck width	4 5/8"
I	Rolled deck width	5 3/8"
J	Height from bottom of bath to top deck	21"
K	Height from bottom of bath to top deck	22"
L	Height from bottom of bath to bottom of deck	19 1/2"
М	Height from bottom of deck to top deck	2 1/2"
N	Height from bottom of drain to center of overflow	16 5/8"
0	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	14 7/8" 14 3/8"
P	Slope of backrest	27°

- ⚠ AromaCloud® position
- **●** Control position when factory-installed (Mia® or DOT)
- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000001
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	128 lb
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power	550 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).</li> <li>There is a height difference for the rolled deck (see drawing Detail A).</li> <li>Available with flat deck or rolled deck.</li> <li>The water level will be lower when an AromaFlow is installed.</li> </ul>	WARRANTY	
		Controls-LED-Geysair*	5 years
		Bath & turbine*	20 years
	t be installed by certified professionals only and according to our Owner's Manual as well as federal, d local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainul	tra.com/warranty

## MERIDIAN UNO

60" x 31" x 20"

Named after the meridians of our body—the paths along which our energy flows—the collection also brings to mind the meridian (or mid-point) of life with an invitation to relax and listen to your body and mind.



MODEL		тми	TUB
	Alcove – Right	BMUCRA0RT-XX	BMUCRA0RN-XX
	Alcove – Left	BMUCRA0LT-XX	BMUCRA0LN-XX

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$4,265
Jets	36
1 heated backrest	Included
Mia® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$2,260
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES			
Installation type		А	lcove (3 walls)
No. of bathers	*	Integrated tile flange	
US gallons	35	removable	
Imp. gallons	29		
STANDARD COLOR p. 13			
			Included
White 01 Biscuit 02			

OPTIONS (UPCHARGE APPLICABLE)			
CONTROL (TMU only) p.9			
MiaPlus®** BMIAP1-XX			\$285
WASTE & OVERFLOW p.10		<b>16" x 35"</b> BOVER16-XX	INTE- GRATED*** BOVERIN-XX
Chrome 07		\$260	\$235
White 01, Biscuit 02		\$290	\$235
Brushed Nickel 09, Polished Nickel 10		\$400	\$235
Oil-rubbed Bronze 11		\$400	N/A
Matte Black 19, Satin Brass 18		N/A	\$355
IF REQUIRED BY CONSTRUCTION CODE			
16" x 35" Cable driven brass waste & overflow kit BOVERBR		\$240	



- \* The AromaCloud® is built into the deck (factory installed).

  \*\* The MiaPlus® Control is included when purchasing Chromatherapy
- \*\*\* Only when ordering an AromaFlow; an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.

#### TO ORDER






#### MERIDIAN UNO

#### INSTALLATION

(A) When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	10 3/8"
В	Outside edge to overflow	5 7/8"
С	Total length	60"
D	Total width	31"
E	Bathing well length	42 3/4"
F	Bathing well width	19 5/16"
G	Deck width	3 1/4"
Н	Deck width at drain end	4"
I	Height from bottom of bath to top deck	20"
J	Tile flange height	1"
K	Height from bottom of drain to center of overflow	14 5/8"
L	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	13" 12 7/8"
М	Slope of backrest	23°

A AromaCloud® position

**❸** Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)


(TUB) Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	136 lb
supply required		Turbine power	550 W
Turbine		Air heater	600 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	WARRANTY	
Others	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access). Integrated tile flange is included (specify right or left). Integrated skirt can not be removed. The water level will be lower when an AromaFlow is installed.	Controls-LED-Geysair*	5 years
		Bath & turbine*	20 years
		* Some restrictions apply   www.bainultra.co	m/warranty
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).			

## MERIDIAN DUO

60" x 31" x 21"

Named after the meridians of our body—the paths along which our energy flows—the collection also brings to mind the meridian (or mid-point) of life with an invitation to relax and listen to your body and mind.



MODEL	тми	TUB
Alcove – Right	BMDCRA0RT-XX	BMDCRA0RN-XX
Alcove – Left	BMDCRA0LT-XX	BMDCRA0LN-XX

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$4,265
Jets	36
1 heated backrest	Included
Mia® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$2,260
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type		А	lcove (3 walls)	
No. of bathers	•	Integrated tile flange		
US gallons	35	and skirt with removable panel	Included	
Imp. gallons	29	(specify right or left)		
STANDARD COLOR p.	13			
			Included	
White 01 Biscuit 02				

· ·		
OPTIONS (UPCHARGE APPLICABLE)		
CONTROL (TMU only) p.9		
MiaPlus®** BMIAP1-XX		\$285
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED*** BOVERIN-XX
Chrome 07	\$260	\$235
White 01, Biscuit 02	\$290	\$235
Brushed Nickel 09, Polished Nickel 10	\$400	\$235
Oil-rubbed Bronze 11	\$400	N/A
Matte Black 19, Satin Brass 18	N/A	\$355
IF REQUIRED BY CONSTRUCTION CODE		
16" x 35" Cable driven brass waste & overflow ki	t BOVERBR	\$240



- \* The AromaCloud® is built into the deck (factory installed).

  \*\* The MiaPlus® Control is included when purchasing Chromatherapy
- \*\*\* Only when ordering an AromaFlow; an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.

#### TO ORDER



Integrated skirt with removable panel






#### **MERIDIAN DUO**

#### INSTALLATION

(A) When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	10 3/8"
В	Outside edge to overflow	5 7/8"
С	Total length	60"
D	Total width	31"
E	Bathing well length	42 3/4"
F	Bathing well width	19 5/16"
G	Deck width	3 1/4"
Н	Deck width at drain end	4"
ı	Height from bottom of bath to top deck	21"
J	Tile flange height	1"
К	Height from bottom of drain to center of overflow	14 5/8"
L	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	13" 12 7/8"
М	Slope of backrest	23°

A AromaCloud® position

**❸** Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS				
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight		
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Turbine power	550 W	
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	ine is Air heater		
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	WARRANTY		
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>		5 years	
	Integrated tile flange is included (specify right or left).     Integrated skirt with removable panel.		20 years	
	- The water level will be lower when an AromaFlow is installed.	* Some restrictions apply   www.bainultra.co	om/warranty	
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).				

60" x 30" x 21"

Named after the meridians of our body—the paths along which our energy flows—the collection also brings to mind the meridian (or mid-point) of life with an invitation to relax and listen to your body and mind.



#### PRODUCT NO.

MODEL	тми	TUB
Alcove – Right	BMEBRIORT-XX	BMEBRIORN-XX
Alcove – Left	BMEBRIOLT-XX	BMEBRIOLN-XX
Drop-in	BMEBRI00T-XX	BMEBRI00N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$4,265
Jets	37
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$1,875
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES					
Installation type		Drop-in & Alcove (3 walls)			
No. of bathers	•				
US gallons	50	Integrated tile flange (specify right or left)	Included		
Imp. gallons	41				
STANDARD COLOR p.	13				
White 01 Biscuit 02			Included		

OPTIONS (UPCHARGE APPLICABLE)				
<b>SKIRT</b> p.243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX		
White 01, Biscuit 02	\$600	\$715		
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED** BOVERIN-XX		
Chrome 07	\$260	\$235		
White 01, Biscuit 02	\$290	\$235		
Brushed Nickel 09, Polished Nickel 10	\$400	\$235		
Oil-rubbed Bronze 11	\$400	N/A		
Matte Black 19, Satin Brass 18	N/A	\$355		
IF REQUIRED BY CONSTRUCTION CODE				
16" x 35" Cable driven brass waste & overflow kit	BOVERBR	\$240		



- \* The AromaCloud® is built into the deck (factory installed).

  \*\* Only when ordering an AromaFlow; an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.


#### TO ORDER








#### INSTALLATION

A Deck modified to host the AromaCloud®. When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.









LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11"
В	Outside edge to overflow	4"
С	Total length	60"
D	Total width	30"
E	Bathing well length	43 5/8"
F	Bathing well width	19 5/8"
G	Deck width	3 1/4"
н	Deck width at drain end	3 1/2"
I	Height from bottom of bath to top deck	20 1/2"
J	Height from bottom of bath to bottom of deck	19"
K	Height from bottom of bath to top of tile flange	21 1/2"
L	Tile flange height	1"
М	Height from bottom of drain to center of overflow	15 13/16"
N	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	14 1/16" 13 15/16"
0	Slope of backrest	24°

⚠ AromaCloud® position

**●** Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS				
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	(	Cutting template	# 90000053
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	1	Approx. shipping weight	100 lb
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	urbine power	550 W	
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.		ir heater	600 W
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	١	VARRANTY	
	The water law will be leave when an Aremo-Flavi is installed	Controls–LED–Geysair*	5 years	
		E	Bath & turbine*	20 years
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog)		* Sc	ome restrictions apply   www.bainul	ra.com/warranty

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

60" x 32" x 21"

Named after the meridians of our body—the paths along which our energy flows—the collection also brings to mind the meridian (or mid-point) of life with an invitation to relax and listen to your body and mind.



PRODUCT NO.					
MODEL	тми	TUB			
Alcove – Right	BMEDRIORT-XX	BMEDRIORN-XX			
Alcove – Left	BMEDRIOLT-XX	BMEDRIOLN-XX			
Drop-in	BMEDRI00T-XX	BMEDRI00N-XX			

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$4,885
Jets	37
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$1,900
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES			
Installation type	Installation type Drop-in & Alcove (3 walls)		
No. of bathers	*		
US gallons	50	Integrated tile flange (specify right or left)	Included
Imp. gallons	41		
STANDARD COLOR	p.13		
White 01 Biscuit 02			Included

OPTIONS (UPCHARGE APPLICABLE)			
<b>SKIRT</b> p.243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX	
White 01, Biscuit 02	\$600	\$715	
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED** BOVERIN-XX	
Chrome 07	\$260	\$235	
White 01, Biscuit 02	\$290	\$235	
Brushed Nickel 09, Polished Nickel 10	\$400	\$235	
Oil-rubbed Bronze 11	\$400	N/A	
Matte Black 19, Satin Brass 18	N/A	\$355	
IF REQUIRED BY CONSTRUCTION CODE			
16" x 35" Cable driven brass waste & overflow kit	\$240		



- \* The AromaCloud® is built into the deck (factory installed).

  \*\* Only when ordering an AromaFlow; an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.


#### TO ORDER








#### INSTALLATION

(A) When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.









LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11"
В	Outside edge to overflow	4"
С	Total length	60"
D	Total width	32"
E	Bathing well length	43 5/8"
F	Bathing well width	19 5/8"
G	Deck width	4 1/4"
Н	Deck width at drain end	3 1/2"
I	Height from bottom of bath to top deck	20 1/2"
J	Height from bottom of bath to bottom of deck	19"
K	Height from bottom of bath to top of tile flange	21 1/2"
L	Tile flange height	1"
М	Height from bottom of drain to center of overflow	15 13/16"
N	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	14 1/16" 13 15/16"
0	Slope of backrest	24°

⚠ AromaCloud® position

**ⓒ** Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SP	ECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000053
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	100 lb
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power	550 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W
Others	- The Geysair <sup>®</sup> is located on the same side as the heated backrest. It must <b>NOT be relocated</b> . It must be <b>connected to the hot water supply</b> and be accessible (provide access).	WARRANTY	
	- There is a height difference for the integrated tile flange (see Detail A) The water level will be lower when an AromaFlow is installed.	Controls–LED–Geysair*	5 years
	t be installed by certified professionals only and according to our Owner's Manual as well as federal,	Bath & turbine*	20 years
provincial/state an	d local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).		

60" x 36" x 20"

Named after the meridians of our body—the paths along which our energy flows—the collection also brings to mind the meridian (or mid-point) of life with an invitation to relax and listen to your body and mind.



MODEL	TMU	TUB
	BMEFRI00T-XX	BMEFRI00N-XX

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$5,045
Jets	40
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$2,190
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

	Drop-in	& Alcove (3 walls)
*	Imp. gallons	38
45		
3		
		Included
	45	Imp. gallons

	MILL TIFIT	CI 4
<b>SKIRT</b> p.243	MULTIFIT BSMUL-XX	<b>SJ-1</b> BSJ1-XX
White 01, Biscuit 02	\$600	\$715
TILE FLANGE (specify right or left) p.11		
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Right BTILER, Left BTILEL, Special installation BTILEO		\$155
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED** BOVERIN-XX
Chrome 07	\$260	\$235
White 01, Biscuit 02	\$290	\$235
Brushed Nickel 09, Polished Nickel 10	\$400	\$235
Oil-rubbed Bronze 11	\$400	N/A
Matte Black 19, Satin Brass 18	N/A	\$355
IF REQUIRED BY CONSTRUCTION CODE		
	BOVERBR	\$240



- \* The AromaCloud® is built into the deck (factory installed).

  \*\* Only when ordering an AromaFlow; an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.


#### TO ORDER






#### INSTALLATION

(A) When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.





LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	10 7/8"
В	Outside edge to overflow	4 1/8"
С	Total length	60"
D	Total width	36 1/2"
E	Bathing well length	42 3/8"
F	Bathing well width	22 3/4"
G	Deck width	4 1/4"
Н	Deck width at backrest end	4"
ı	Height from bottom of bath to top deck	20 1/4"
J	Height from bottom of bath to bottom of deck	18 3/4"
К	Height from bottom of drain to center of overflow	16"
L	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	14 1/4" 14 1/8"
М	Slope of backrest	24°

A AromaCloud® position

**❸** Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SP	PECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000006
supply required	Access to the pump must be at least 18" x 22". Standard connection is 20 A. 120 V, 60 Hz, dedicated line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Approx. shipping weight	124 lb
Turbine		Turbine power	550 W
		Air heater	600 W
	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).</li> <li>Optional tile flange (specify right or left).</li> <li>If ordered with an installed tile flange, the control will be shipped separately.</li> </ul>	WARRANTY	
Others		Controls-LED-Geysair*	5 years
	- The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years
Our products mus	t he installed by certified professionals only and according to our Owner's Manual as well as federal		-

Our products must be installed by certified professionals only and according to our Owners Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

\* Some restrictions apply | www.bainultra.com/warranty

60" x 42" x 21"

Named after the meridians of our body—the paths along which our energy flows—the collection also brings to mind the meridian (or mid-point) of life with an invitation to relax and listen to your body and mind.



#### PRODUCT NO. MODEL TUB BMEGRI00T-XX BMEGRI00N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$5,440
Jets	41
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$2,680
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES			
Installation type	Drop-in & Alcove (3 walls		
No. of bathers	•	Imp. gallons	52
US gallons	62		
<b>STANDARD COLOR</b> p.	13		
White 01 Biscuit 02			Included

OPTIONS (UPCHARGE APPLICABLE)		
<b>SKIRT</b> p.243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX
White 01, Biscuit 02	\$600	\$715
TILE FLANGE (specify right or left) p.11		
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Right BTILER, Left BTILEL, Special installation BTILEO		\$155
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED** BOVERIN-XX
Chrome 07	\$260	\$235
White 01, Biscuit 02	\$290	\$235
Brushed Nickel 09, Polished Nickel 10	\$400	\$235
Oil-rubbed Bronze 11	\$400	N/A
Matte Black 19, Satin Brass 18	N/A	\$355
IF REQUIRED BY CONSTRUCTION CODE		
16" x 35" Cable driven brass waste & overflow kit BOVERBR		\$240



- \* The AromaCloud® is built into the deck (factory installed).

  \*\* Only when ordering an AromaFlow; an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.


#### TO ORDER






#### INSTALLATION

(A) When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.





LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11"
В	Outside edge to overflow	4"
С	Total length	60"
D	Total width	42"
E	Bathing well length	43 5/8"
F	Bathing well width	26 1/4"
G	Deck width	4 1/4"
н	Deck width at backrest end	3 1/2"
I	Height from bottom of bath to top deck	20 1/2"
J	Height from bottom of bath to bottom of deck	19"
K	Height from bottom of drain to center of overflow	17"
L	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	14 3/8" 14"
М	Slope of backrest	24°

A AromaCloud® position

**●** Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)

(TUB) Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000006
зарріў геципец	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	126 lb
Turbine	ne line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power	550 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	WARRANTY	
Others	Optional tile flange (specify right or left).     The water level will be lower when an AromaFlow is installed.	Controls-LED-Geysair*	5 years
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).		Bath & turbine*	20 years
		* Some restrictions apply   www.bainul	tra.com/warranty

66" x 36" x 20"

Named after the meridians of our body—the paths along which our energy flows—the collection also brings to mind the meridian (or mid-point) of life with an invitation to relax and listen to your body and mind.



MODEL	тми	TUB	
	BMELRI00T-XX	BMELRI00N-XX	

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$5,490
Jets	42
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$2,775
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES			
Installation type		Drop-in &	Alcove (3 walls)
No. of bathers	* *	Imp. gallons	39
US gallons	47		
<b>STANDARD COLOR</b> p.	13		
White 01 Biscuit 02			Included

SKIRT p.243	MULTIFIT	SJ-1
•	BSMUL-XX	BSJ1-XX
White 01, Biscuit 02	\$600	\$715
TILE FLANGE (specify front or back) p.11		
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Right BTILER, Left BTILEL, Special installation BTILEO		\$155
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED** BOVERIN-XX
Chrome 07	\$260	\$235
White 01, Biscuit 02	\$290	\$235
Brushed Nickel 09, Polished Nickel 10	\$400	\$235
Oil-rubbed Bronze 11	\$400	N/A
Matte Black 19, Satin Brass 18	N/A	\$355
IF REQUIRED BY CONSTRUCTION CODE		




- \* The AromaCloud® is built into the deck (factory installed).

  \*\* Only when ordering an AromaFlow; an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.


#### TO ORDER






#### INSTALLATION

When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.





LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11 3/8"
В	Outside edge to overflow	4 1/4"
С	Total length	65 1/2"
D	Total width	35 3/4"
E	Bathing well length	46 1/8"
F	Bathing well width	23 1/4"
G	Deck width at backrest end	4 3/8"
Н	Deck width	4"
I	Height from bottom of bath to top deck	20 1/4"
J	Height from bottom of bath to bottom of deck	18 3/4"
K	Height from bottom of drain to center of overflow	16 1/8"
L	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	14 3/8" 14 1/4"
М	Slope of backrest	24°
N	Slope of backrest	15°

- ⚠ AromaCloud® position
- **ⓒ** Control position when factory-installed (Mia® or DOT)
- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 9000007
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	127 lb
Turbine	urbine line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power	550 W
	ed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).</li> <li>Optional tile flange (specify front or back).</li> <li>If ordered with an installed tile flange and a back drain, the control will be shipped separately.</li> <li>The water level will be lower when an AromaFlow is installed.</li> </ul>	WARRANTY	
		Controls-LED-Geysair*	5 years
		Bath & turbine*	20 years
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).		* Some restrictions apply   www.bainul	,

72" x 36" x 21"

Named after the meridians of our body—the paths along which our energy flows—the collection also brings to mind the meridian (or mid-point) of life with an invitation to relax and listen to your body and mind.



#### PRODUCT NO.

MODEL	тми	TUB
	BMESRI00T-XX	BMESRI00N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$5,600
Jets	44
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$2,990
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES			
Installation type	Drop-in & Alcove (3 walls)		
No. of bathers	* *	Imp. gallons	52
US gallons	63		
<b>STANDARD COLOR</b> p.	13		
			Included
White 01 Biscuit 02			

OPTIONS (UPCHARGE APPLICABLE)		
<b>SKIRT</b> p.243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX
White 01, Biscuit 02	\$600	\$715
TILE FLANGE (specify front or back) p.11		
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Right BTILER, Left BTILEL, Special installation BTILEO		\$155
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED** BOVERIN-XX
Chrome 07	\$260	\$235
White 01, Biscuit 02	\$290	\$235
Brushed Nickel 09, Polished Nickel 10	\$400	\$235
Oil-rubbed Bronze 11	\$400	N/A
Matte Black 19, Satin Brass 18	N/A	\$355
IF REQUIRED BY CONSTRUCTION CODE		
16" x 35" Cable driven brass waste & overflow kit	\$240	



- \* The AromaCloud® is built into the deck (factory installed).

  \*\* Only when ordering an AromaFlow; an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.


#### TO ORDER





#### INSTALLATION

(A) When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.



<b>*</b>	<b>A</b>	
I	JM	 1
<u> </u>		 K ↓

LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	10 5/8"
В	Outside edge to overflow	4 1/4"
С	Total length	71 3/8"
D	Total width	35 3/4"
E	Bathing well length	47 1/4"
F	Bathing well width	24 1/4"
G	Deck width at backrest end	4 1/8"
Н	Deck width	4"
ı	Height from bottom of bath to top deck	21 1/4"
J	Height from bottom of bath to bottom of deck	19 3/4"
K	Height from bottom of drain to center of overflow	16 7/8"
L	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	15 1/8" 15"
М	Slope of backrests	26°

A AromaCloud® position

**❸** Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

Hot water	ECIFICATIONS  The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template
supply required	The not water supply should be 70% of more of the bath's total water capacity.	Approx. shipping weight
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is</b>	Turbine power
	<b>needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater
<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).</li> <li>Optional tile flange (specify front or back).</li> <li>If ordered with an installed tile flange and a back drain, the control will be shipped separately.</li> </ul>	It must be connected to the hot water supply and be accessible (provide access).	WARRANTY
	Optional tile flange (specify front or back).     If ordered with an installed tile flange and a back drain, the control will be shipped separately.	Controls-LED-Geysair*
	- The water level will be lower when an AromaFlow is installed.	Bath & turbine*
	be installed by certified professionals only and according to our Owner's Manual as well as federal, dlocal building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainultra.cc

The specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra\* assumes no responsibility for preparatory work done prior to the product being on site.

# 90000007 136 lb 550 W 600 W

> 5 years 20 years

66" x 34" x 20"

Named after the meridians of our body—the paths along which our energy flows—the collection also brings to mind the meridian (or mid-point) of life with an invitation to relax and listen to your body and mind.

#### PRODUCT NO.

MODEL	тми	TUB
	BPMKRI00T-XX	BPMKRI00N-XX

THERMOMASSEUR (TMU)	\$5,405
Hydro-thermo massage • Air jet system	
Jets	44
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$2,780
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES			
Installation type			Alcove (3 walls)
No. of bathers	•	Imp. gallons 46	
US gallons	55		
<b>STANDARD COLOR</b> p.	13		
White 01 Biscuit 02			Included

OPTIONS (UPCHARGE APPLICABLE)		
<b>SKIRT</b> p.243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX
White 01, Biscuit 02	\$600	\$715
TILE FLANGE (specify right or left) p.11		
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Right BTILER, Left BTILEL, Special installation BTILEO		\$155
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED** BOVERIN-XX
Chrome 07	\$260	\$235
White 01, Biscuit 02	\$290	\$235
Brushed Nickel 09, Polished Nickel 10	\$400	\$235
Oil-rubbed Bronze 11	\$400	N/A
Matte Black 19, Satin Brass 18	N/A	\$355
IF REQUIRED BY CONSTRUCTION CODE		
16" x 35" Cable driven brass waste & overflow kit	BOVERBR	\$240



- \* The AromaCloud® is built into the deck (factory installed).

  \*\* Only when ordering an AromaFlow; an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.


#### TO ORDER






#### INSTALLATION

(A) When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.





LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	9 1/4"
В	Outside edge to overflow	5"
С	Total length	65 3/4"
D	Total width	34"
E	Bathing well length	49 3/4"
F	Bathing well width	22 1/2"
G	Deck width	3 1/4"
Н	Deck width at drain end	4 1/4"
I	Height from bottom of bath to top deck	20"
J	Height from bottom of bath to bottom of deck	18 1/2"
К	Height from bottom of drain to center of overflow	15 7/8"
L	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	14 1/4" 14 1/8"
М	Slope of backrest	22°

A AromaCloud® position

**❸** Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)

(TUB) Indicates WarmTouchShell® position (TUB)

TECHNICAL SE	PECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000012
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	131 lb
Turbine line with a Ground-Fault Circuit Interrupte	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power	550 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W
<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).</li> <li>Optional tile flange (specify right or left).</li> <li>If ordered with an installed tile flange, the control will be shipped separately.</li> <li>The water level will be lower when an AromaFlow is installed.</li> </ul>	It must be connected to the hot water supply and be accessible (provide access).	WARRANTY	
	- If ordered with an installed tile flange, the control will be shipped separately.	Controls-LED-Geysair*	5 years
		Bath & turbine*	20 years
Our products mus	t ha installed by cartified professionals only and according to our Owner's Manual as well as federal		

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

72" x 36" x 20"

Named after the meridians of our body—the paths along which our energy flows—the collection also brings to mind the meridian (or mid-point) of life with an invitation to relax and listen to your body and mind.



MODEL	тми	TUB	ı
	BPMSRI00T-XX	BPMSRI00N-XX	

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$5,770
Jets	50
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$3,000
AromaCloud®* BAROMAC	\$490
AromaFlow** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES			
Installation type			Alcove (3 walls)
No. of bathers	•	Imp. gallons	58
US gallons	69		
<b>STANDARD COLOR</b> p.	13		
White 01 Biscuit 02			Included

OPTIONS (UPCHARGE APPLICABLE)		
<b>SKIRT</b> p.243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX
White 01, Biscuit 02	\$600	\$715
TILE FLANGE (specify right or left) p.11		
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Right BTILER, Left BTILEL, Special installation BTILEO		\$155
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED** BOVERIN-XX
Chrome 07	\$260	\$235
White 01, Biscuit 02	\$290	\$235
Brushed Nickel 09, Polished Nickel 10	\$400	\$235
Oil-rubbed Bronze 11	\$400	N/A
Matte Black 19, Satin Brass 18 N/A		\$355
IF REQUIRED BY CONSTRUCTION CODE		
16" x 35" Cable driven brass waste & overflow kit BOVERBR		\$240



- \* The AromaCloud® is built into the deck (factory installed).

  \*\* Only when ordering an AromaFlow; an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.


#### TO ORDER






#### INSTALLATION

(A) When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.





LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	9 5/8"
В	Outside edge to overflow	4 3/8"
С	Total length	71 3/4"
D	Total width	35 7/8"
E	Bathing well length	55 1/4"
F	Bathing well width	25 1/2"
G	Deck width	3 7/8"
н	Deck width at drain end	4 3/8"
ı	Height from bottom of bath to top deck	20 1/8"
J	Height from bottom of bath to bottom of deck	18 3/4"
К	Height from bottom of drain to center of overflow	16 1/4"
L	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	14 1/2" 14 3/8"
М	Slope of backrest	23°

A AromaCloud® position

**●** Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)


Indicates WarmTouchShell® position (TUB)

TECHNICAL SP	ECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000013
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Approx. shipping weight	133 lb
Turbine		Turbine power	550 W
		Air heater	600 W
	The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access). Optional tile flange (specify right or left). If ordered with an installed tile flange, the control will be shipped separately. The water level will be lower when an AromaFlow is installed.	WARRANTY	
Others		Controls-LED-Geysair*	5 years
		Bath & turbine*	20 years
Our products must	the installed by certified professionals only and according to our Owner's Manual as well as federal		-

Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

\* Some restrictions apply | www.bainultra.com/warranty he specifications shown indicate the outer edge dimension and the inside bathing capacity dimension measured at air jets' height. The manufacturer accepts a 1/4" [0.64 cm] variance. There are variations on each product and specifications are subject to change as we improve upon our product as required. The dimensions needed for site preparation and structure building will differ. BainUltra® assumes no responsibility for preparatory work done prior to the product being on site.

Monarch is a refined collection of therapeutic baths with distinctive Quartz deck surfaces, for a look that's noble and pure.



MODEL	тми	TUB
Standard (S)*	BMODRB00T-XX	BMODRB00N-XX
Grand Luxury (GL)*	BMLDRB00T-XX	BMLDRB00N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	s <b>\$5,805</b> GL <b>\$9,440</b>
Jets	37
1 heated backrest	Included
MiaPlus® Control (not installed)	Included
BU-Touch Control Application BU	TOUCH \$430
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	s \$3,595 GL \$7,185
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES					
Installation	type			Drop-in & A	Alcove (3 walls)
No. of bath	ers	•	Imp. gallo	ns	42
US gallons		50			
INTEGRAT	ED WASTE	& OVERFLO	W BOVERINI-)	xx p. 10	
		ushed Nickel ( vith UltraVelo		Installe	d & Included
STANDARI	COLOR (i	nner shell) p	.13		
White 01					Included
QUARTZ D	ECK COLO	<b>R</b> p.13	В	<b>S*</b> BDMO6032-XX	GL* BDML6032-XX
Grey Expo 21	Jet Black 23	Lagos Blue 24		Included	Included


OPTIONS (UPCHARGE APPLICABLE)		
QUARTZ DECK COLOR p.13	<b>S*</b> BDMO6032-XX	GL* BDML6032-XX
Quasar Light 25	\$395	\$1,320
Piatra Bianco Woodlands Grey 26 Drift 31 30	\$450	\$1,560
Statuario Maximus 29	\$900	\$3,300
FINISH (inner shell) p.6		
UltraVelour Matte Finish (white only) BVEL1		\$650
QUARTZ SKIRT 6018 (60" x 18 7/8") BSM6018-XX	(p.38	
Grey Expo 21		\$1,195
Jet Black 23, Lagos Blue 24		\$1,315
Quasar Light 25		\$1,860
Piatra Grey 26, Bianco Drift 31, Woodlands 30		\$1,915
Statuario Maximus 29		\$2,700
TILE FLANGE (specify right or left) p.11		
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Right BTILER, Left BTILEL, Special installation BTILEO		\$155
INTEGRATED WASTE & OVERFLOW BOVERINI-	xx p.10	
Matte Black 19, Satin Brass 18		\$120
WASTE & OVERFLOW 16" x 35" BOVER16-XX p.	10	
Chrome 07		\$260
White 01		\$290
Brushed Nickel 09, Polished Nickel 10, Oil-rubbed	Bronze 11	\$400
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit** BDRCOB	\$240	
Brass waste kit** BDRCB		\$60
16" x 35" Cable driven brass waste & overflow kit	BOVERBR	\$240







#### **MONARCH** 6032

#### INSTALLATION







LETTER	DESCRIPTION	MEASURE
Α	Total length	60"
В	Total width	32"
С	Bathing well length (at height of jets)	43 5/8"
D	Bathing well width (at height of jets)	19 5/8"
E	Deck width (edges)	4"
F	Deck width (sides)	4 5/8"
G	Bath height	19 7/8"
Н	Maximum water level Maximum water level with AromaFlow	15 1/16" 13 3/16"
ı	Outside edge to center drain	11 1/8"
J	Slope of backrest	24°
K	Quartz deck height	3/4"

Turbine position (TMU)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

Don't forget that this model is available in White only with choice of quartz deck color. Don't forget to specify the finish of the integrated waste & overflow.

- $\mbox{\ensuremath{\star}}$  Standard: Quartz deck with seam. Grand Luxury: one piece Quartz deck.
- $\ensuremath{^{\star\star}}$  When ordered with integrated waste & overflow.
- \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.


#### TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

TECHNICAL SP	ECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	234 lb
supply required	Accord to the purpose must be at least 10" v 22" Standard connection in 20 A 120 V CO He dedicated	Turbine power	550 W
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is</b>	Air heater	600 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI.	WARRANTY	
	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	Controls-LED-Geysair*	5 years
Others	- Control cannot be installed on the Quartz deck Optional tile flange (specify right or left).	Quartz deck*	15 years
	- The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years
	be installed by certified professionals only and according to our Monarch Installation Manual as well as federal, I local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainultr	a.com/warranty

**MONARCH** 6036 60" x 36" x 20"

Monarch is a refined collection of therapeutic baths with distinctive Quartz deck surfaces, for a look that's noble and pure.



MODEL		TMU	1	TUB	
Standard (S	)*	BMOFRB00T-XX	BMOF	RB00N-XX	
Grand Luxury	(GL)*	BMLFRB00T-XX	BMLFF	RB00N-XX	

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	s \$5,990 GL \$9,715
Jets	40
1 heated backrest	Included
MiaPlus® Control (not installed)	Included
BU-Touch Control Application BUT	OUCH \$430
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

TUB Soaker S \$3,740 GL \$7,47		
AromaCloud®	N/A	
AromaFlow*** BAROMAF NEW	\$950	
Illuzio Chromatherapy BCHRO6	\$925	
WarmTouchShell® BWTS	\$1,125	
DOT control	Included with therapy	

FEATURES					
Installation	type			Drop-in & A	Alcove (3 walls)
No. of bath	ers	•	Imp. gallo	ns	40
US gallons		48			
INTEGRAT	ED WASTE	& OVERFLO	W BOVERINI-)	<b>x</b> p. 10	
		ushed Nickel ( vith UltraVelo		Installe	d & Included
STANDAR	D COLOR (i	nner shell) p	.13		
White 01					Included
QUARTZ D	ECK COLO	<b>R</b> p.13	В	<b>S*</b> DMO6036-XX	GL* BDML6036-XX
Grey Expo 21	Jet Black 23	Lagos Blue 24		Included	Included


	S*	GL*
<b>QUARTZ DECK COLOR</b> p.13	<b>S*</b> BDMO6036-XX	
	¢ 400	¢4.47
Quasar Light 25	\$480	\$1,47
	\$540	\$1,74
Piatra Bianco Woodlands Grey 26 Drift 31 30	43.10	4.,, .
19.		
Statuario Maximus 29	\$1,200	\$3,78
FINISH (inner shell) p.6  UltraVelour Matte Finish (white only) BVEL1		\$65
QUARTZ SKIRT 6018 (60" x 18 7/8") BSM6018-X	v n 38	\$00
Grey Expo 21	x p. 30	\$1,19
Jet Black 23, Lagos Blue 24		\$1,31
Quasar Light 25		\$1,86
Piatra Grey 26, Bianco Drift 31, Woodlands 30		\$1,91
Statuario Maximus 29		\$2,70
TILE FLANGE (specify right or left) p.11		12,12
Ordered with bath (not installed) BTILEN		\$7
Factory-installed. Right BTILER, Left BTILEL,		
Special installation BTILEO		\$15
INTEGRATED WASTE & OVERFLOW BOVERINI	-XX p.10	
Matte Black 19, Satin Brass 18		\$12
WASTE & OVERFLOW 16" x 35" BOVER16-XX p	.10	
Chrome 07		\$26
White 01		\$29
Brushed Nickel 09, Polished Nickel 10, Oil-rubbed	l Bronze 11	\$40
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit** BDRCOB		\$24
Brass waste kit** BDRCB		\$6
16" x 35" Cable driven brass waste & overflow kit	BOVERBR	\$24





#### **MONARCH** 6036

# 



LETTER	DESCRIPTION	MEASURE
Α	Total length	60"
В	Total width	36"
С	Bathing well length (at height of jets)	42 3/8"
D	Bathing well width (at height of jets)	22 3/4"
E	Deck width (edges)	4 5/8"
F	Deck width (sides)	5 1/8"
G	Bath height	19 7/8"
н	Maximum water level Maximum water level with AromaFlow	15 1/16" 13 3/16"
ı	Outside edge to center drain	11 1/8"
J	Slope of backrest	24°
К	Quartz deck height	3/4"

Turbine position (TMU)Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

Don't forget that this model is available in **White only with choice** of quartz deck color. Don't forget to specify the **finish of the integrated** waste & overflow.

- \* Standard: Quartz deck with seam. Grand Luxury: one piece Quartz deck.
- \*\* When ordered with integrated waste & overflow.
- \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

#### TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

TECHNICAL SP	ECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	244 lb
	Turbine power	550 W	
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is</b>	Air heater	600 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI.	WARRANTY	
	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> <li>Control cannot be installed on the Quartz deck.</li> <li>Optional tile flange (specify right or left).</li> </ul>	Controls-LED-Geysair*	5 years
Others		Quartz deck*	15 years
	- The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years
	be installed by certified professionals only and according to our Monarch Installation Manual as well as federal, I local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainultra.c	com/warranty

## MONARCH 6636

66" x 36" x 20"

Monarch is a refined collection of therapeutic baths with distinctive Quartz deck surfaces, for a look that's noble and pure.

#### PRODUCT NO.

MODEL		TMU	TUB	
	Standard (S)*	BMOLRB00T-XX	BMOLRB00N-XX	
	Grand Luxury (GL)*	BMLLRB00T-XX	BMLLRB00N-XX	

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system  \$ \$6,050 GL \$10,14	
Jets	42
1 heated backrest	Included
MiaPlus® Control (not installed)	Included
BU-Touch Control Application BU	TOUCH \$430
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) B	SHB \$1,125

<b>TUB</b> Soaker	s <b>\$3,840</b> GL <b>\$7,960</b>
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

2 <sup>nd</sup> WarmTouchShell® BW	/TS2			\$370
FEATURES				
Installation type			Drop-in & A	Alcove (3 walls)
No. of bathers	* *	Imp. gallo	ns	42
US gallons	50			
INTEGRATED WASTE 8	INTEGRATED WASTE & OVERFLOW BOVERINI-XX p. 10			
White 01, Chrome 07, Bru Nickel 10, Matte White w			Installe	d & Included
STANDARD COLOR (in	ner shell) p.	.13		
White 01				Included
QUARTZ DECK COLOR	l p.13	В	<b>S*</b> DMO6636-XX	GL* BDML6636-XX
	Lagos Blue 24		Included	Included

QUARTZ DECK COLOR p.13	<b>S*</b> BDMO6636-XX	GL* BDML6636-
Quasar Light 25	\$540	\$1,620
Piatra Bianco Woodlands Grey 26 Drift 31 30	\$630	\$1,890
Statuario Maximus 29	\$1,260	\$4,080
FINISH (inner shell) p.6		
UltraVelour Matte Finish (white only) BVEL1		\$650
QUARTZ SKIRT 6618 (66" x 18 7/8") BSM6618-X	x p.38	
Grey Expo 21		\$1,31
Jet Black 23, Lagos Blue 24		\$1,380
Quasar Light 25		\$1,980
Piatra Grey 26, Bianco Drift 31, Woodlands 30		\$2,100
Statuario Maximus 29		\$2,940
TILE FLANGE (specify front or back) p.11		
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Front BTILEF, Back BTILEB, Special installation BTILEO		\$15
INTEGRATED WASTE & OVERFLOW BOVERING	-xx p.10	
Matte Black 19, Satin Brass 18		\$120
WASTE & OVERFLOW 16" x 35" BOVER16-XX p	.10	
Chrome 07		\$260
White 01		\$290
Brushed Nickel 09, Polished Nickel 10, Oil-rubbed	d Bronze 11	\$400
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit** BDRCOB		\$240
Brass waste kit** BDRCB		\$60
16" x 35" Cable driven brass waste & overflow kit	BOVERBR	\$240







#### **MONARCH** 6636

INSTALLATION

# В





LETTER	DESCRIPTION	MEASURE
Α	Total length	66"
В	Total width	36"
С	Bathing well length (at height of jets)	46 1/8"
D	Bathing well width (at height of jets)	23 1/4"
E	Deck width (edges)	4 3/4"
F	Deck width (sides)	4 5/8"
G	Bath height	19 5/8"
Н	Maximum water level Maximum water level with AromaFlow	15 3/8" 13 1/2"
ı	Outside edge to center drain	11 3/8"
J	Slope of backrest	23°
K	Quartz deck height	3/4"

Turbine position (TMU) Indicates heated backrest (TMU) Indicates WarmTouchShell® position (TUB)

Don't forget that this model is available in **White only with choice of quartz deck color**. Don't forget to specify the **finish of the integrated** 

- waste & overflow.

  \* Standard: Quartz deck with seam. Grand Luxury: one piece Quartz deck.

  \*\* When ordered with integrated drain & overflow.
- \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

#### TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	253 lb
supply required	A	Turbine power	550 W
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is</b>	Air heater	600 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI.	WARRANTY	
	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).</li> <li>Control cannot be installed on the Quartz deck.</li> <li>Optional tile flange (specify front or back).</li> <li>The water level will be lower when an AromaFlow is installed.</li> </ul>	Controls-LED-Geysair*	5 years
Others		Quartz deck*	15 years
		Bath & turbine*	20 years
	be installed by certified professionals only and according to our Monarch Installation Manual as well as federal, I local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainultr	a.com/warranty



#### PRODUCT NO.

MODEL		тми	TUB
	Standard (S)*	BMOMHB00T-XX	BMOMHB00N-XX
	Grand Luxury (GL)*	BMLMHB00T-XX	BMLMHB00N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	s <b>\$6,100</b> GL <b>\$10,255</b>
Jets	42
1 heated backrest	Included
MiaPlus® Control (not installed)	Included
BU-Touch Control Application BU	JTOUCH \$430
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone)	\$SHB \$1,125


<b>TUB</b> Soaker	s \$3,940 GL \$7,890
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type			Drop-in & A	Alcove (3 walls)
No. of bathers	* *	Imp. gallo	ns	42
US gallons	50			
INTEGRATED WASTE	& OVERFLO	W BOVERINI-)	<b>x</b> p. 10	
White 01, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32			d & Included	
STANDARD COLOR (inner shell) p.13				
Uncluded White 01				
QUARTZ DECK COLOR p. 13         S* GL* BDMO6638F-XX BDML6638F-XX				
Grey Jet Expo 21 Black 23	Lagos Blue 24		Included	Included

OPTIONS (UPCHARGE APPLICABLE)			
QUARTZ DECK COLOR p	.13	<b>S*</b> DMO6638F-XX	GL* BDML6638F->
Quasar Light 25		\$540	\$1,740
7	oodlands	\$630	\$2,040
Statuario Maximus 29		\$1,260	\$4,320
FINISH (inner shell) p.6			
UltraVelour Matte Finish (w	nite only) BVEL1		\$650
<b>QUARTZ SKIRT 6618</b> (66'	x 18 7/8") BSM6618-XX	p.38	
Grey Expo 21			\$1,31
Jet Black 23, Lagos Blue 24			\$1,380
Quasar Light 25			\$1,980
Piatra Grey 26, Bianco Drift 31, Woodlands 30			\$2,100
Statuario Maximus 29			\$2,940
TILE FLANGE p.11			
Ordered with bath (not installed) BTILEN			\$79
Factory-installed. Front BTILEF, Special installation BTILEO			\$15
INTEGRATED WASTE & C	OVERFLOW BOVERINI-	xx p.10	
Matte Black 19, Satin Brass	18		\$120
WASTE & OVERFLOW 16" x 35" BOVER16-XX p.10			
Chrome 07		\$260	
White 01		\$290	
Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11		\$400	
IF REQUIRED BY CONSTI			
Brass waste & overflow kit** BDRCOB			\$240
Brass waste kit** BDRCB			\$60
16" x 35" Cable driven brass	waste & overflow kit	BOVERBR	\$240

Piatra Grey with quartz skirt 6618







#### MONARCH 6638F CURVED DECK - FRONT

INSTALLATION

## В





LETTER	DESCRIPTION	MEASURE
Α	Total length	66"
В	Total width	38"
С	Bathing well length (at height of jets)	46 1/8"
D	Bathing well width (at height of jets)	23 1/4"
E	Deck width (edges)	4 3/4"
F	Deck width (straight side)	4 5/8"
G	Deck width (curved side)	6 5/8"
Н	Bath height	19 5/8"
ı	Maximum water level Maximum water level with AromaFlow	15 3/8" 13 1/2"
J	Outside edge to center drain	13 3/8"
K	Slope of backrest	23°
L	Quartz deck height	3/4"
М	Slope of backrest	15°

Turbine position (TMU)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

Don't forget that this model is available in White only with choice of quartz deck color. Don't forget to specify the finish of the integrated

- \*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

TECHNICAL SPECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the hath's total water canacity	
Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI.		
The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access). Control cannot be installed on the Quartz deck. Optional tile flange. The water level will be lower when an AromaFlow is installed.		

Our products must be installed by certified professionals only and according to our Monarch Installation Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).

Approx. shipping weight	260 lb
Turbine power	550 W
Air heater	600 W
WARRANTY	
Controls-LED-Geysair*	5 years
Quartz deck*	15 years
Bath & turbine*	20 years

<sup>\*</sup> Some restrictions apply | www.bainultra.com/warranty

#### MONARCH 7236 72" x 36" x 21"

Monarch is a refined collection of therapeutic baths with distinctive Quartz deck surfaces, for a look that's noble and pure.



MODEL		тми	TUB
	Standard (S)*	BMOSRB00T-XX	BMOSRB00N-XX
	Grand Luxury (GL)*	BMLSRB00T-XX	BMLSRB00N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	s <b>\$6,285</b> GL <b>\$10,600</b>
Jets	44
1 heated backrest	Included
MiaPlus® Control (not installed)	Included
BU-Touch Control Application BU	TOUCH \$430
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) B	SHB \$1,125

<b>TUB</b> Soaker	s \$4,100 GL \$8,385
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

2 <sup>no</sup> WarmTouchShell® BWTS2			\$370		
FEATURES					
Installation	type			Drop-in & A	Alcove (3 walls)
No. of bathe	ers	* *	Imp. gallo	ns	53
US gallons		63			
INTEGRAT	ED WASTE 8	& OVERFLO	N BOVERINI-)	<b>X</b> p. 10	
		ished Nickel 0 ith UltraVelor		Installe	d & Included
STANDARI	COLOR (ir	ner shell) p.	.13		
White 01					Included
QUARTZ D	ECK COLOR	<b>R</b> p.13	В	<b>S*</b> DMO7236-XX	GL* BDML7236-XX
Grey Expo 21	Jet Black 23	Lagos Blue 24		Included	Included


QUARTZ DECK COLOR p. 13	<b>S</b> *	GL*
	BDMO7236-XX	BDML7236
	\$510	\$1,71
Quasar Light 25		, ,,,,,
Piatra Bianco Woodlands Grey 26 Drift 31 30	\$600	\$2,07
Statuario Maximus 29	\$1,380	\$4,53
FINISH (inner shell) p.6		
UltraVelour Matte Finish (white only) BVEL1		\$65
<b>QUARTZ SKIRT 7220</b> (72" x 20") BSM7220-XX p	.38	
Grey Expo 21		\$1,50
Jet Black 23, Lagos Blue 24		\$1,62
Quasar Light 25		\$2,27
Piatra Grey 26, Bianco Drift 31, Woodlands 30		\$2,39
Statuario Maximus 29		\$3,35
TILE FLANGE (specify front or back) p.11		
Ordered with bath (not installed) BTILEN		\$7
Factory-installed. Front BTILEF, Back BTILEB, Special installation BTILEO		\$15
INTEGRATED WASTE & OVERFLOW BOVERINI	-xx p.10	
Matte Black 19, Satin Brass 18		\$120
WASTE & OVERFLOW 16" x 35" BOVER16-XX p	.10	
Chrome 07		\$26
White 01		\$29
Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11		\$40
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit** BDRCOB		\$24
Brass waste kit** BDRCB		\$60
16" x 35" Cable driven brass waste & overflow kit	ROVERBR	\$240






#### **MONARCH** 7236

# INSTALLATION





LETTER	DESCRIPTION	MEASURE
Α	Total length	72"
В	Total width	36"
С	Bathing well length (at height of jets)	47 1/4"
D	Bathing well width (at height of jets)	24 1/4"
E	Deck width (edges)	4 7/8"
F	Deck width (sides)	4 5/8"
G	Bath height	21"
Н	Maximum water level Maximum water level with AromaFlow	16 1/8" 14 1/4"
I	Outside edge to center drain	10 5/8"
J	Slope of backrest	26°
K	Quartz deck height	3/4"

Turbine position (TMU) Indicates heated backrest (TMU) Indicates WarmTouchShell® position (TUB)

Don't forget that this model is available in **White only with choice of quartz deck color**. Don't forget to specify the **finish of the integrated** waste & overflow.

- \*Standard: Quartz deck with seam. Grand Luxury: one piece Quartz deck.

  \*\*When ordered with integrated waste & overflow.
- \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

#### TO ORDER


Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

TECHNICAL SP	ECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	266 lb
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Turbine power	550 W
Turbine	Turbine line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Air heater	600 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI.	WARRANTY	
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> <li>Control cannot be installed on the Quartz deck.</li> </ul>	Controls-LED-Geysair*	5 years
Guicis	- Optional tile flange (specify front or back).	Quartz deck*	15 years
	- The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years
	be installed by certified professionals only and according to our Monarch Installation Manual as well as federal, I local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainultra	.com/warranty

## MONARCH 7238F

72" x 38" x 21"

Monarch is a refined collection of therapeutic baths with distinctive Quartz deck surfaces, for a look that's noble and pure.



MODEL	тми	TUB
Standard (S)*	BMOTHB00T-XX	BMOTFD00N-XX
Grand Luxury (GL)*	BMLTHB00T-XX	BMLTFD00N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	s <b>\$6,340</b> GL <b>\$10,705</b>
Jets	44
1 heated backrest	Included
MiaPlus® Control (not installed)	Included
BU-Touch Control Application BUT	OUCH \$430
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSH	HB \$1,125

<b>TUB</b> Soaker	s <b>\$4,165</b> GL <b>\$8,480</b>
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

2 <sup>nd</sup> WarmTouchShell® BWTS2			\$370	
FEATURES				
Installation type			Drop-in & A	Alcove (3 walls)
No. of bathers	* *	Imp. gallo	ns	53
US gallons	63			
INTEGRATED WASTE 8	& OVERFLO	<b>W</b> BOVERINI-)	<b>X</b> p. 10	
White 01, Chrome 07, Bru Nickel 10, Matte White w			Installe	d & Included
STANDARD COLOR (in	ner shell) p	.13		
White 01				Included
QUARTZ DECK COLOR	<b>R</b> p.13	ВС	<b>S*</b> 0MO7238F-XX	GL* BDML7238F-XX
Grey Jet Expo 21 Black 23	Lagos Blue 24		Included	Included


QUARTZ	DECK COL	<b>DR</b> p.13	<b>S*</b> BDMO7238F-XX	GL* K BDML7238F
Quasar Li	ght 25		\$510	\$1,86
Piatra Grey 26	Bianco Drift 31	Woodlands 30	\$600	\$2,19
Statuario	Maximus 29		\$1,380	\$4,71
FINISH (i	nner shell)	p.6		
UltraVelo	ır Matte Fini	sh (white only) BVEL1		\$65
QUARTZ	SKIRT 7220	(72" x 20") BSM7220	-XX p.38	
Grey Expo	21			\$1,50
Jet Black 2	3, Lagos Blu	e 24		\$1,62
Quasar Light 25			\$2,27	
Piatra Gre	y <mark>26,</mark> Bianco	Drift 31, Woodlands	30	\$2,39
Statuario Maximus 29		\$3,35		
TILE FLA	<b>NGE</b> p.11			
Ordered v	vith bath (no	installed) BTILEN		\$7
Factory-installed. Front BTILEF, Special installation BTILEO		\$15		
INTEGRA	TED WAST	E & OVERFLOW BOV	ERINI-XX p.10	
Matte Bla	ck 19, Satin E	Brass 18		\$12
WASTE &	OVERFLO	<b>N 16" x 35"</b> BOVER16	5-XX p.10	
Chrome 0	7			\$26
White 01		\$29		
Brushed Nickel 09, Polished Nickel 10, Oil-rubbed Bronze 11		\$40		
IF REQUI	RED BY CO	NSTRUCTION COD	E	
Brass was	te & overflo	w kit** BDRCOB		\$24
Brass waste kit** BDRCB			\$6	
16" v 35" (	ahle driven	brass waste & overflo	w kit BOVEDBD	\$24





#### MONARCH 7238F CURVED DECK - FRONT

## INSTALLATION В D G



LETTER	DESCRIPTION	MEASURE
Α	Total length	72"
В	Total width	38"
С	Bathing well length (at height of jets)	47 1/4"
D	Bathing well width (at height of jets)	24 1/4"
E	Deck width (edges)	4 7/8"
F	Deck width (straight side)	4 5/8"
G	Deck width (curved side)	6 5/8"
Н	Bath height	21"
ı	Maximum water level Maximum water level with AromaFlow	16 1/8" 14 1/4"
J	Outside edge to center drain	12 5/8"
К	Slope of backrest	26°
L	Quartz deck height	3/4"

Turbine position (TMU)

Indicates WarmTouchShell® position (TUB)

Indicates heated backrest (TMU)

Don't forget that this model is available in **White only with choice of quartz deck color**. Don't forget to specify the **finish of the integrated** waste & overflow.

- \* Standard: Quartz deck with seam. Grand Luxury: one piece Quartz deck.
  - \*\* When ordered with integrated waste & overflow.
- \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

#### TO ORDER

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

TECHNICAL SP	PECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	270 lb
supply required	Accord to the number must be at least 1911 y 2311 Chandard connection in 20 A 120 V CO He dedicated	Turbine power	550 W
Turbine		Air heater	600 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI.	WARRANTY	
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> <li>Control cannot be installed on the Quartz deck.</li> <li>Optional tile flange.</li> </ul>	Controls-LED-Geysair*	5 years
		Quartz deck*	15 years
	- The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years
	be installed by certified professionals only and according to our Monarch Installation Manual as well as federal, d local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainultr	a.com/warranty

Monarch is a refined collection of therapeutic baths with distinctive Quartz deck surfaces, for a look that's noble and pure.

#### PRODUCT NO.

MODEL	тми	TUB	Ī
Standard (s)*	BMOURB00T-XX	BMOURB00N-XX	
Grand Luxury (GL)*	BMLURB00T-XX	BMLURB00N-XX	


THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	s <b>\$6,470</b> GL <b>\$10,955</b>
Jets	44
1 heated backrest	Included
MiaPlus® Control (not installed)	Included
BU-Touch Control Application BU	TOUCH \$430
Geysair®	Included
AromaCloud®	N/A
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) B	SHB \$1,125

<b>TUB</b> Soaker	s <b>\$4,23</b>	0 GL \$8,745
AromaCloud®		N/A
AromaFlow*** BAROMAF NEW		\$950
Illuzio Chromatherapy BCHRO6		\$925
WarmTouchShell® BWTS		\$1,125
DOT control		Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2		\$370

2 <sup>nd</sup> WarmTouchShell® BW	/TS2			\$370
FEATURES				
Installation type			Drop-in & A	Alcove (3 walls)
No. of bathers	* *	Imp. gallo	ns	53
US gallons	63			
INTEGRATED WASTE 8	k OVERFLO	W BOVERINI-)	xx p. 10	
White 01, Chrome 07, Bru Nickel 10, Matte White w			Installe	d & Included
STANDARD COLOR (in	ner shell) p	.13		
White 01				Included
QUARTZ DECK COLOR	p.13	В	<b>S*</b> BDMO7240-XX	GL* BDML7240-XX
	Lagos Blue 24		Included	Included

OPTIONS (UPCHARGE APPLICABLE)		
QUARTZ DECK COLOR p.13	<b>S*</b> BDMO7240-XX	GL* BDML7240-XX
Quasar Light 25	\$610	\$1,930
Piatra Bianco Woodlands Grey 26 Drift 31 30	\$730	\$2,295
Statuario Maximus 29	\$1,510	\$4,930
FINISH (inner shell) p.6		
UltraVelour Matte Finish (white only) BVEL1		\$650
<b>QUARTZ SKIRT 7220</b> (72" x 20") BSM7220-XX p	.38	
Grey Expo 21		\$1,500
Jet Black 23, Lagos Blue 24		\$1,620
Quasar Light 25		\$2,275
Piatra Grey 26, Bianco Drift 31, Woodlands 30		\$2,395
Statuario Maximus 29		\$3,350
TILE FLANGE (specify front or back) p.11		
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Front BTILEF, Back BTILEB, Special installation BTILEO		\$155
INTEGRATED WASTE & OVERFLOW BOVERINI	-xx p.10	
Matte Black 19, Satin Brass 18		\$120
WASTE & OVERFLOW 16" x 35" BOVER16-XX p	.10	
Chrome 07		\$260
White 01		\$290
Brushed Nickel 09, Polished Nickel 10, Oil-rubbed	Bronze 11	\$400
IF REQUIRED BY CONSTRUCTION CODE		
Brass waste & overflow kit** BDRCOB		\$240
Brass waste kit** BDRCB		\$60
16" x 35" Cable driven brass waste & overflow kit	BOVERBR	\$240





#### **MONARCH** 7240

## INSTALLATION В Indicates heated backrest (TMU) TO ORDER

LETTER	DESCRIPTION	MEASURE
Α	Total length	72"
В	Total width	40"
С	Bathing well length (at height of jets)	47 1/4"
D	Bathing well width (at height of jets)	24 1/4"
E	Deck width (edges)	4 7/8"
F	Deck width (sides)	6 5/8"
G	Bath height	21"
н	Maximum water level Maximum water level with AromaFlow	16 1/8" 14 1/4"
ı	Outside edge to center drain	12 5/8"
J	Slope of backrest	26°
K	Quartz deck height	3/4"

Turbine position (TMU)

Indicates WarmTouchShell® position (TUB)

Don't forget that this model is available in **White only with choice of quartz deck color**. Don't forget to specify the **finish of the integrated** waste & overflow.

- \* Standard: Quartz deck with seam. Grand Luxury: one piece Quartz deck.
- \*\* When ordered with integrated waste & overflow.
- \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

Complete the ORDER FORM in the bainultra.com/interactive-price-list or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com

<b>TECHNICAL SP</b>	ECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Approx. shipping weight	280 lb
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Turbine power	550 W
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Air heater	600 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI.	WARRANTY	
	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	Controls-LED-Geysair*	5 years
Others	- Control cannot be installed on the Quartz deck Optional tile flange (specify front or back).	Quartz deck*	15 years
	- The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years
	be installed by certified professionals only and according to our Monarch Installation Manual as well as federal, I local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainultr	a.com/warranty

## ORIGAMI 6030 ORIGINAL SERIES

60" x 30" x 21"

The traditional Japanese art of folding paper into symbolic shapes is the inspiration behind the Origami Collection, which stands out for its clean lines and versatility.



#### PRODUCT NO.

MODEL	тми	TUB	
	BOOBRIOOT-XX	BOOBRIOON-XX	

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$5,725
Jets	40
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$3,025
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES			
Installation type		Drop-in	& Alcove (3 walls)
No. of bathers	•	Imp. gallons	38
US gallons	46		
STANDARD COLOR p.	13		
White 01 Biscuit 02			Included

FINISH p.6		
UltraVelour Matte Finish (white only) BVEL1		\$650
<b>SKIRT</b> p. 243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX
White 01, Biscuit 02	\$600	\$715
TILE FLANGE (specify right or left) p.11		
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Right BTILER, Left BTILEL, Special installation BTILEO		\$15
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED BOVERIN-X
Chrome 07	\$260	\$23
Citi dilic di		
White 01, Biscuit 02	\$290	\$23
	\$290 N/A	
White 01, Biscuit 02	1	\$23!
White 01, Biscuit 02  Matte White with UltraVelour finish 32	N/A	\$23! \$23!
White 01, Biscuit 02  Matte White with UltraVelour finish 32  Brushed Nickel 09, Polished Nickel 10	N/A \$400	\$23: \$23: N/A
White 01, Biscuit 02  Matte White with UltraVelour finish 32  Brushed Nickel 09, Polished Nickel 10  Oil-rubbed Bronze 11	N/A \$400 \$400	\$23! \$23! N//
White 01, Biscuit 02  Matte White with UltraVelour finish 32  Brushed Nickel 09, Polished Nickel 10  Oil-rubbed Bronze 11  Matte Black 19, Satin Brass 18	N/A \$400 \$400	\$23: \$23: N// \$35:
White 01, Biscuit 02  Matte White with UltraVelour finish 32  Brushed Nickel 09, Polished Nickel 10  Oil-rubbed Bronze 11  Matte Black 19, Satin Brass 18  IF REQUIRED BY CONSTRUCTION CODE	N/A \$400 \$400	\$23! \$23! \$23! \$23! \$35! \$240


- \* The AromaCloud® is built into the deck (factory installed).

  \*\* When ordered with integrated waste & overflow.

  - \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.

#### TO ORDER







#### **ORIGAMI** 6030 ORIGINAL SERIES

#### INSTALLATION

When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.







LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11"
В	Outside edge to overflow	3 5/8"
С	Total length	60"
D	Total width	30"
E	Bathing well length	43 1/4"
F	Bathing well width	19 5/8"
G	Deck width	3 1/4"
Н	Deck width	3 1/4"
ı	Height from bottom of bath to top deck	21"
J	Height from bottom of bath to bottom of deck	19"
K	Height from bottom of drain to center of overflow	15 5/8"
L	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	13 7/8" 14 7/8" 14 3/8"
М	Slope of backrest	24°

A AromaCloud® position

**ⓒ** Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS				
Hot water supply required  The hot water supply should be 70% or more of the bath's total water capacity.		Cutting template	# 90000048	
supply required		Approx. shipping weight	128 lb	
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is</b>	Turbine power	550 W	
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W	
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	WARRANTY		
Others	Optional tile flange (specify right or left).     The water level will vary when an AromaFlow or an Integrated waste & overflow is installed.	Controls-LED-Geysair*	5 years	
	be installed by certified professionals only and according to our Owner's Manual as well as federal,	Bath & turbine*	20 years	
provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).		* Some restrictions apply   www.bainul	ra.com/warranty	

## ORIGAMI 6032 ORIGINAL SERIES

60" x 32" x 21"

The traditional Japanese art of folding paper into symbolic shapes is the inspiration behind the Origami Collection, which stands out for its clean lines and versatility.



MODEL		тми	TUB
	3 1/4" deck	BOODRI00T-XX	BOODRIOON-XX
	2" deck	BOODRI20T-XX	BOODRI20N-XX
	Slim deck	BOODRI10T-XX	BOODRI10N-XX

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$5,820
Jets	38
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$3,090
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES					
Installation typ	е	Drop-ir	n: 1/2", 2" & 3 1	/4" & Alcov	re (3 walls): 2"
No. of bathers		*	Imp. gallons		40
US gallons		48			
STANDARD COLOR p.13					
White 01 Ri	scuit 02				Included

Slim deck 1/2"

OPTIONS (UPCHARGE APPLICABLE)		
FINISH p.6		
UltraVelour Matte Finish (white only) BVEL1		\$650
UNIVERSAL ARMRESTS BGBGU-XX p.12		
White 01		\$750
SKIRT (2" deck only) p. 243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX
White 01, Biscuit 02	\$600	\$715
TILE FLANGE (with 2" deck only) (specify right	or left) p.1	1
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Right BTILER, Left BTILEL, Special installation BTILEO		\$155
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED BOVERIN-XX
WASTE & OVERFLOW p.10 Chrome 07		GRATED
·	BOVER16-XX	GRATED BOVERIN-XX
Chrome 07	\$260	GRATED BOVERIN-XX \$235
Chrome 07 White 01, Biscuit 02	\$260 \$290	GRATED BOVERIN-XX \$235 \$235
Chrome 07 White 01, Biscuit 02 Matte White with UltraVelour finish 32	\$260 \$290 N/A	GRATED BOVERIN-XX \$235 \$235 \$235
Chrome 07 White 01, Biscuit 02 Matte White with UltraVelour finish 32 Brushed Nickel 09, Polished Nickel 10	\$260 \$290 N/A \$400	\$235 \$235 \$235 \$235
Chrome 07 White 01, Biscuit 02 Matte White with UltraVelour finish 32 Brushed Nickel 09, Polished Nickel 10 Oil-rubbed Bronze 11	\$260 \$290 N/A \$400 \$400	\$235 \$235 \$235 \$235 \$235 \$235
Chrome 07 White 01, Biscuit 02 Matte White with UltraVelour finish 32 Brushed Nickel 09, Polished Nickel 10 Oil-rubbed Bronze 11 Matte Black 19, Satin Brass 18	\$260 \$290 N/A \$400 \$400	\$235 \$235 \$235 \$235 \$235 \$235
Chrome 07  White 01, Biscuit 02  Matte White with UltraVelour finish 32  Brushed Nickel 09, Polished Nickel 10  Oil-rubbed Bronze 11  Matte Black 19, Satin Brass 18  IF REQUIRED BY CONSTRUCTION CODE	\$260 \$290 N/A \$400 \$400	\$235 \$235 \$235 \$235 \$235 \$235 \$235 \$235



Don't forget to indicate the deck height (1/2", 2" or 3 1/4"). Slim deck are available for Drop-in installation only.

- \* The AromaCloud® is built into the deck (factory installed).
- \*\* When ordered with integrated waste & overflow.
- \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.


#### TO ORDER





#### INSTALLATION

When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11 5/8"
В	Outside edge to overflow	4 1/4"
С	Total length (with 1/2" deck height) Total length (with 2" deck height) Total length (with 3 1/4" deck height)	59 3/4" 60" 60 1/4"
D	Total width (with 1/2" deck height) Total width (with 2" deck height) Total width (with 3 1/4" deck height)	31 5/8" 31 7/8" 32 1/8"
E	Bathing well length	42 5/8"
F	Bathing well width	20 3/8"
G	Deck width	3 5/8"
Н	Deck width at drain end	3 7/8"
I	Deck width at backrest	2"
J	Height from bottom of bath to top deck	21"
К	Height from bottom of deck to top deck	2"
L	Height from bottom of deck to top deck	3 1/4"
М	Height from bottom of drain to center of overflow	16"
N	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	14 1/4" 15 1/4" 14 3/4"
О	Slope of backrest	24°
P	Height from bottom of deck to top deck	1/2"


- ⚠ AromaCloud® position
- Indicates heated backrest (TMU)
- Control position when factory-installed (Mia® or DOT)
- Indicates WarmTouchShell® position (TUB)
- Turbine position (TMU)

TECHNICAL SPECIFICATIONS					
Hot water supply required	The hot water cumply should be 70% or more of the bath's total water capacity		# 90000048		
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	130 lb		
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Turbine power	550 W		
		Air heater	600 W		
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	WARRANTY			
	<ul> <li>Optional tile flange with 2" deck height only (specify right or left).</li> <li>The water level will vary when an AromaFlow or an Integrated waste &amp; overflow is installed.</li> </ul>	Controls-LED-Geysair*	5 years		
	be installed by certified professionals only and according to our Owner's Manual as well as federal,	Bath & turbine* 20 year			
provincial/state an	d local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainultr	a.com/warrantv		

## ORIGAMI 6632 ORIGINAL SERIES

66" x 32" x 21"

The traditional Japanese art of folding paper into symbolic shapes is the inspiration behind the Origami Collection, which stands out for its clean lines and versatility.



MODEL	тми	TUB
3 1/4" deck	BOOIRI00T-XX	BOOIRI00N-XX
2" deck	BOOIRI20T-XX	BOOIRI20N-XX
Slim deck	BOOIRI10T-XX	BOOIRI10N-XX

<b>THERMOMASSEUR (TMU)</b> Hydro-thermo massage • Air jet system	\$6,180
Jets	45
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$3,340
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type	Drop-ii	n: 1/2", 2" & 3 1/4" & A	Alcove (3 walls): 2"	
No. of bathers	*	Imp. gallons	41	
US gallons	49			
STANDARD COLOR p.13				
White 01 Riscuit 02			Included	

FINISH p.6		
UltraVelour Matte Finish (white only) BVEL1		\$650
UNIVERSAL ARMRESTS BGBGU-XX p.12		
White 01		\$750
SKIRT (2" deck only) p.243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX
White 01, Biscuit 02	\$600	\$715
TILE FLANGE (with 2" deck only) (specify rigi	nt or left) p.1	1
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Right BTILER, Left BTILEL, Special installation BTILEO		\$155
WASTE & OVERFLOW p.10	16" x 35"	INTE- GRATED
	BOVER16-XX	BOVERIN-X
Chrome 07	\$260	\$235
emonie v		
emonie v	\$260	\$23
	\$260 \$290	\$23! \$23!
White 01, Biscuit 02  Matte White with UltraVelour finish 32  Brushed Nickel 09, Polished Nickel 10	\$260 \$290 N/A	\$23! \$23! \$23!
White 01, Biscuit 02  Matte White with UltraVelour finish 32	\$260 \$290 N/A \$400	\$23 \$23 \$23 \$23 N/A
White 01, Biscuit 02  Matte White with UltraVelour finish 32  Brushed Nickel 09, Polished Nickel 10  Oil-rubbed Bronze 11	\$260 \$290 N/A \$400 \$400	\$23. \$23. \$23. \$23.
White 01, Biscuit 02  Matte White with UltraVelour finish 32  Brushed Nickel 09, Polished Nickel 10  Oil-rubbed Bronze 11  Matte Black 19, Satin Brass 18	\$260 \$290 N/A \$400 \$400	\$23 \$23 \$23 \$23
White 01, Biscuit 02  Matte White with UltraVelour finish 32  Brushed Nickel 09, Polished Nickel 10  Oil-rubbed Bronze 11  Matte Black 19, Satin Brass 18  IF REQUIRED BY CONSTRUCTION CODE	\$260 \$290 N/A \$400 \$400	\$23: \$23: \$23: \$23: \$23: N// \$35:



Don't forget to indicate the deck height (1/2", 2" or 3 1/4"). Slim deck are available for Drop-in installation only.

- \* The AromaCloud® is built into the deck (factory installed).
- \*\* When ordered with integrated waste & overflow.
- \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.


#### TO ORDER





INSTALLATION

When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11 1/4"
В	Outside edge to overflow	4 1/8"
С	Total length (with 1/2" deck height) Total length (with 2" deck height) Total length (with 3 1/4" deck height)	65 5/8" 65 7/8" 66"
D	Total width (with 1/2" deck height) Total width (with 2" deck height) Total width (with 3 1/4" deck height)	31 5/8" 31 7/8" 32"
E	Bathing well length	49 1/2"
F	Bathing well width	20 7/8"
G	Deck width	3 5/8'
Н	Deck width	3 5/8'
ı	Deck width at backrest	1 3/8'
J	Height from bottom of bath to top deck	21'
К	Height from bottom of deck to top deck	2'
L	Height from bottom of deck to top deck	3 1/4'
М	Height from bottom of drain to center of overflow	15 5/8'
N	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	13 7/8' 15' 14 1/2'
0	Slope of backrest	24°
P	Height from bottom of deck to top deck	1/2"

A AromaCloud® position Turbine position (TMU)

**ⓒ** Control position when factory-installed (Mia® or DOT)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000047
supply required	Accorded to the control of the state of the	Approx. shipping weight	132 lb
Turbine	Access to the pump must be at least 18" x 22". Standard connection is 20 A. 120 V, 60 Hz, dedicated line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Turbine power	550 W
		Air heater	600 W
Others	- The Geysair® is located on the same side as the heated backrest. It must <b>NOT be relocated</b> .  It must be <b>connected to the hot water supply</b> and be accessible (provide access).	WARRANTY	
	Optional tile flange with 2" deck height only (specify right or left).     The water level will vary when an AromaFlow or an Integrated waste & overflow is installed.	Controls-LED-Geysair*	5 years
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal, provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).		Bath & turbine*	20 years
		* Some restrictions apply   www.bainul	tra.com/warranty

## ORIGAMI 6636 ORIGINAL SERIES

66" x 36" x 22"

The traditional Japanese art of folding paper into symbolic shapes is the inspiration behind the Origami Collection, which stands out for its clean lines and versatility.



MODEL	тми	TUB	
4" deck	BOOLRI00T-XX	BOOLRI00N-XX	
2" deck	BOOLRI20T-XX	BOOLRI20N-XX	
Slim deck	BOOLRI10T-XX	BOOLRI10N-XX	

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$6,425
Jets	40
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$3,370
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type	Dro	p-in: 1/2", 2" & 4" & A	Alcove (3 walls): 2"	
No. of bathers	*	Imp. gallons	52	
US gallons	62			
STANDARD COLOR p. 13				
White 01 Risquit 02			Included	

Slim deck 1/2"


OPTIONS (UPCHARGE APPLICABLE)		
FINISH p.6		
UltraVelour Matte Finish (white only) BVEL1		\$650
UNIVERSAL ARMRESTS BGBGU-XX p.12		
White 01		\$750
SKIRT (2" deck only) p. 243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX
White 01, Biscuit 02	\$600	\$715
TILE FLANGE (with 2" deck only) (specify right	or left) p.1	1
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Right BTILER, Left BTILEL, Special installation BTILEO		\$155
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED BOVERIN-XX
WASTE & OVERFLOW p.10 Chrome 07		GRATED
·	BOVER16-XX	GRATED BOVERIN-XX
Chrome 07	\$260	GRATED BOVERIN-XX \$235
Chrome 07 White 01, Biscuit 02	\$260 \$290	GRATED BOVERIN-XX \$235 \$235
Chrome 07 White 01, Biscuit 02 Matte White with UltraVelour finish 32	\$260 \$290 N/A	GRATED BOVERIN-XX \$235 \$235 \$235
Chrome 07 White 01, Biscuit 02 Matte White with UltraVelour finish 32 Brushed Nickel 09, Polished Nickel 10	\$260 \$290 N/A \$400	\$235 \$235 \$235 \$235
Chrome 07 White 01, Biscuit 02 Matte White with UltraVelour finish 32 Brushed Nickel 09, Polished Nickel 10 Oil-rubbed Bronze 11	\$260 \$290 N/A \$400 \$400	\$235 \$235 \$235 \$235 \$235 \$235
Chrome 07 White 01, Biscuit 02 Matte White with UltraVelour finish 32 Brushed Nickel 09, Polished Nickel 10 Oil-rubbed Bronze 11 Matte Black 19, Satin Brass 18	\$260 \$290 N/A \$400 \$400	\$235 \$235 \$235 \$235 \$235 \$235
Chrome 07  White 01, Biscuit 02  Matte White with UltraVelour finish 32  Brushed Nickel 09, Polished Nickel 10  Oil-rubbed Bronze 11  Matte Black 19, Satin Brass 18  IF REQUIRED BY CONSTRUCTION CODE	\$260 \$290 N/A \$400 \$400	\$235 \$235 \$235 \$235 \$235 \$235 \$235 \$235



Don't forget to indicate the deck height (1/2", 2" or 4"). Slim deck are available for Drop-in installation only.

- \* The AromaCloud® is built into the deck (factory installed).
- \*\* When ordered with integrated waste & overflow.
- \*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.


#### TO ORDER





#### INSTALLATION

⚠ When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	12 3/8"
В	Outside edge to overflow	4 5/8"
С	Total length (with 1/2" deck height) Total length (with 2" deck height) Total length (with 4" deck height)	65 5/8" 65 7/8" 66 1/4"
D	Total width (with 1/2" deck height) Total width (with 2" deck height) Total width (with 4" deck height)	35 1/2" 35 3/4" 36 1/8"
E	Bathing well length	47 1/4"
F	Bathing well width	22 1/4"
G	Deck width	4 1/2"
н	Deck width at drain end	4 1/2"
ı	Deck width at backrest	1 5/8"
J	Height from bottom of bath to top deck	21 7/8"
K	Height from bottom of deck to top deck	2"
L	Height from bottom of deck to top deck	4"
М	Height from bottom of drain to center of overflow	17 1/4"
N	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	15 1/2" 17" 16 1/2"
0	Slope of backrest	24°
P	Height from bottom of deck to top deck	1/2"

- ⚠ AromaCloud® position
- Control position when factory-installed (Mia® or DOT)
- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS			
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000047
supply required	Access to the number must be at least 10" v 22" Standard connection is 20 A 120 V CO He dedicated	Approx. shipping weight	135 lb
Turbine	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Turbine power	550 W
		Air heater	600 W
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	WARRANTY	
J	Optional tile flange with 2" deck height only (specify right or left).     The water level will vary when an AromaFlow or an Integrated waste & overflow is installed.	Controls-LED-Geysair*	5 years
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal,		Bath & turbine*	20 years
provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).  * Some restrictions apply   www.bainultra.com/warranty			

### ORIGAMI 7236 original series

72" x 36" x 22"

The traditional Japanese art of folding paper into symbolic shapes is the inspiration behind the Origami Collection, which stands out for its clean lines and versatility.



MODEL	тми	TUB
4" deck	BOOSRI00T-XX	BOOSRIOON-XX
2" deck	BOOSRI20T-XX	BOOSRI20N-XX
Slim deck	BOOSRI10T-XX	BOOSRI10N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$6,700
Jets	42
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$3,635
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES			
Installation type	Dro	Drop-in: 1/2", 2" & 4" & Alcove (3 walls): 2"	
No. of bathers	* *	Imp. gallons	54
US gallons	64		
STANDARD COLOR p.	13		
White 01 Biscuit 02			Included

OPTIONS (UPCHARGE APPLICABLE)		
FINISH p.6		
UltraVelour Matte Finish (white only) BVEL1		\$650
UNIVERSAL ARMRESTS BGBGU-XX p.12		
White 01		\$750
SKIRT (2" deck only) p. 243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX
White 01, Biscuit 02	\$600	\$715
TILE FLANGE (with 2" deck only) (specify front	or back) p.	11
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Front BTILEF, Back BTILEB, Special installation BTILEO		\$155
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED BOVERIN-XX
WASTE & OVERFLOW p.10 Chrome 07		GRATED
·	BOVER16-XX	GRATED BOVERIN-XX
Chrome 07	\$260	GRATED BOVERIN-XX \$235
Chrome 07 White 01, Biscuit 02	\$260 \$290	GRATED BOVERIN-XX \$235 \$235
Chrome 07 White 01, Biscuit 02 Matte White with UltraVelour finish 32	\$260 \$290 N/A	<b>GRATED</b> BOVERIN-XX  \$235  \$235  \$235
Chrome 07 White 01, Biscuit 02 Matte White with UltraVelour finish 32 Brushed Nickel 09, Polished Nickel 10	\$260 \$290 N/A \$400	\$235 \$235 \$235 \$235
Chrome 07 White 01, Biscuit 02 Matte White with UltraVelour finish 32 Brushed Nickel 09, Polished Nickel 10 Oil-rubbed Bronze 11	\$260 \$290 N/A \$400 \$400	\$235 \$235 \$235 \$235 \$235 \$235
Chrome 07 White 01, Biscuit 02 Matte White with UltraVelour finish 32 Brushed Nickel 09, Polished Nickel 10 Oil-rubbed Bronze 11 Matte Black 19, Satin Brass 18	\$260 \$290 N/A \$400 \$400	\$235 \$235 \$235 \$235 \$235 \$235
Chrome 07  White 01, Biscuit 02  Matte White with UltraVelour finish 32  Brushed Nickel 09, Polished Nickel 10  Oil-rubbed Bronze 11  Matte Black 19, Satin Brass 18  IF REQUIRED BY CONSTRUCTION CODE	\$260 \$290 N/A \$400 \$400	\$235 \$235 \$235 \$235 \$235 \$235 \$235 \$235




Don't forget to indicate the deck height (1/2", 2" or 4"). Slim deck are available for Drop-in installation only.

\* The AromaCloud® is built into the deck (factory installed).

\*\* When ordered with integrated waste & overflow.

\*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.


#### TO ORDER





#### INSTALLATION

When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.



LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	11 1/4"
В	Outside edge to overflow	4 5/8"
С	Total length (with slim deck height) Total length (with 2" deck height) Total length (with 4" deck height)	71 1/4" 71 5/8" 72"
D	Total width (with slim deck height) Total width (with 2" deck height) Total width (with 4" deck height)	35 1/4" 35 5/8" 36"
E	Bathing well length	48 1/8"
F	Bathing well width	22"
G	Deck width	4 3/8"
Н	Deck width at backrest ends	1 3/4"
I	Height from bottom of deck to top deck	1/2"
J	Height from bottom of deck to top deck	2"
K	Height from bottom of deck to top deck	4"
L	Height from bottom of bath to top deck	22"
М	Height from bottom of drain to center of overflow	17 3/4"
N	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	16" 17" 16 1/2"
0	Slope of backrests	24°

⚠ AromaCloud® position

**●** Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)


Indicates WarmTouchShell® position (TUB)

lot water	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000047
upply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	137 lb
urbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power	550 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W
The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).	WARRANTY		
	Optional tile flange with 2" deck height only (specify front or back).     The water level will vary when an AromaFlow or an Integrated waste & overflow is installed.	Controls-LED-Geysair*	5 years
Our products must	be installed by certified professionals only and according to our Owner's Manual as well as federal,	Bath & turbine*	20 years

## ORIGAMI 7242 ORIGINAL SERIES

72" x 42" x 22"

The traditional Japanese art of folding paper into symbolic shapes is the inspiration behind the Origami Collection, which stands out for its clean lines and versatility.



MODEL	тми	TUB
5" deck	BOOVRI00T-XX	BOOVRI00N-XX
2" deck	BOOVRI20T-XX	BOOVRI20N-XX
Slim deck	BOOVRI10T-XX	BOOVRI10N-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$7,105
Jets	44
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$3,890
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES			
Installation type	Dro	Drop-in: 1/2", 2" & 5" & Alcove (3 walls): 2"	
No. of bathers	* *	Imp. gallons	60
US gallons	72		
STANDARD COLOR p.	13		
White 01 Biscuit 02			Included

OPTIONS (UPCHARGE APPLICABLE)		
FINISH p.6		
UltraVelour Matte Finish (white only) BVEL1		\$650
UNIVERSAL ARMRESTS BGBGU-XX p.12		
White 01		\$750
SKIRT (2" deck only) p.243	MULTIFIT BSMUL-XX	SJ-1 BSJ1-XX
White 01, Biscuit 02	\$600	\$715
TILE FLANGE (with 2" deck only) (specify front	or back) p.	11
Ordered with bath (not installed) BTILEN		\$79
Factory-installed. Front BTILEF, Back BTILEB, Special installation BTILEO		\$155
		INITE
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED BOVERIN-XX
WASTE & OVERFLOW p.10 Chrome 07		GRATED
· ·	BOVER16-XX	GRATED BOVERIN-XX
Chrome 07	\$260	GRATED BOVERIN-XX \$235
Chrome 07 White 01, Biscuit 02	\$260 \$290	GRATED BOVERIN-XX \$235 \$235
Chrome 07 White 01, Biscuit 02 Matte White with UltraVelour finish 32	\$260 \$290 N/A	<b>GRATED</b> BOVERIN-XX  \$235  \$235  \$235
Chrome 07 White 01, Biscuit 02 Matte White with UltraVelour finish 32 Brushed Nickel 09, Polished Nickel 10	\$260 \$290 N/A \$400	\$235 \$235 \$235 \$235
Chrome 07 White 01, Biscuit 02 Matte White with UltraVelour finish 32 Brushed Nickel 09, Polished Nickel 10 Oil-rubbed Bronze 11	\$260 \$290 N/A \$400 \$400	\$235 \$235 \$235 \$235 \$235 \$235
Chrome 07  White 01, Biscuit 02  Matte White with UltraVelour finish 32  Brushed Nickel 09, Polished Nickel 10  Oil-rubbed Bronze 11  Matte Black 19, Satin Brass 18	\$260 \$290 N/A \$400 \$400	\$235 \$235 \$235 \$235 \$235 \$235
Chrome 07  White 01, Biscuit 02  Matte White with UltraVelour finish 32  Brushed Nickel 09, Polished Nickel 10  Oil-rubbed Bronze 11  Matte Black 19, Satin Brass 18  IF REQUIRED BY CONSTRUCTION CODE	\$260 \$290 N/A \$400 \$400	\$235 \$235 \$235 \$235 \$235 \$235 \$235 \$235




Don't forget to indicate the deck height (1/2", 2" or 5"). Slim deck are available for Drop-in installation only.

\* The AromaCloud® is built into the deck (factory installed).

\*\* When ordered with integrated waste & overflow.

\*\*\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.


#### TO ORDER






#### INSTALLATION

When tile flange is added, the AromaCloud® will automatically be installed on the opposite side of the flange.







LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	12 1/4"
В	Outside edge to overflow	5 3/8"
С	Total length (with 1/2" deck height) Total length (with 2" deck height) Total length (with 5" deck height)	71 1/4" 71 5/8" 72 1/8"
D	Total width (with 1/2" deck height) Total width (with 2" deck height) Total width (with 5" deck height)	41 1/4" 41 5/8" 42 1/8"
E	Bathing well length	45"
F	Bathing well width	26 1/4"
G	Deck width	5 3/8"
Н	Deck width at backrest ends	3"
ı	Height from bottom of bath to top deck	22"
J	Height from bottom of deck to top deck	2"
K	Height from bottom of deck to top deck	5"
L	Height from bottom of drain to center of overflow	17 1/8"
М	Maximum water level (Waste & overflow 16" x 35") Maximum water level (Integrated waste & overflow) Maximum water level with AromaFlow	16" 16 3/4" 16 1/4"
N	Slope of backrests	24°
0	Height from bottom of deck to top deck	1/2"

⚠ AromaCloud® position

**ⓒ** Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)


Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS				
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000052	
supply required	Assessed the second country of the state of AON COUNTRY Country and a second country to the second country of	Approx. shipping weight	140 lb	
Turbine	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated line with a Ground-Fault Circuit Interrupter (GFCI). <b>For any additional option, a second line is needed 15 A. 120 V, 60 Hz</b> , dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Turbine power	550 W	
		Air heater	600 W	
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.     It must be connected to the hot water supply and be accessible (provide access).</li> <li>Optional tile flange with 2" deck height only (specify front or back).</li> <li>The water level will vary when an AromaFlow or an Integrated waste &amp; overflow is installed.</li> </ul>	WARRANTY		
		Controls-LED-Geysair*	5 years	
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal,		Bath & turbine*	20 years	
provincial/state an	d local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainul	tra.com/warranty	

## THALASSA SENSATION

54" x 54" x 20"

Thalassa means "the sea," where all states of being co-mingle.




MODEL	тми	TUB	
	BTHACD00T-XX	BTHACD00N-XX	

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$5,100
Jets	40
1 heated backrest & headrest	Included
Mia® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
2 <sup>nd</sup> heated backrest (WTS-1 zone) BSHB	\$1,125

<b>TUB</b> Soaker	\$2,380
AromaCloud®* BAROMAC	\$490
AromaFlow*** BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy
2 <sup>nd</sup> WarmTouchShell® BWTS2	\$370

FEATURES				
Installation type	Installation type			
No. of bathers	**	Imp. gallor	ns	46
US gallons	55	Grab bars (color match)		1
STANDARD COLOR p. 13				
White 01 Biscuit 02				Included

OPTIONS (UPCHARGE APPLICABLE)			
CONTROL (TMU only) p.9			
MiaPlus®** BMIAP1-XX		\$285	
SKIRT SJ-3 SE BSJ3-XX p. 243			
White 01, Biscuit 02		\$1,310	
CLEAR ACRYLIC GRAB BARS BGBG10-XX p. 1	2		
With Chrome 07 or Brushed Nickel 09 inserts		\$60	
TILE FLANGE p.11			
Ordered with bath (not installed) BTILEN		\$79	
Factory-installed. Front BTILEF. Special installation BTILEO		\$155	
WASTE & OVERFLOW p.10	<b>16" x 35"</b> BOVER16-XX	INTE- GRATED** BOVERIN-XX	
Chrome 07	\$260	\$235	
White 01, Biscuit 02	\$290	\$235	
Brushed Nickel 09, Polished Nickel 10	\$400	\$235	
Oil-rubbed Bronze 11	\$400	N/A	
Matte Black 19, Satin Brass 18	N/A	\$355	
IF REQUIRED BY CONSTRUCTION CODE			
16" x 35" Cable driven brass waste & overflow l	kit BOVERBR	\$240	




and/or a 2<sup>nd</sup> heated backrest on a TMU.

\*\*\* Only when ordering an AromaFlow, an Integrated waste & overflow is mandatory (Upcharge). Specify the finish of the waste.





#### INSTALLATION



1	1	1		
	J	K	The state of the s	· 1
<u> </u>	Į.	ļ	→ N	

LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	10 1/2"
В	Outside edge to overflow	5 1/2"
С	Total length	58 7/8"
D	Total width	75 7/8"
E	Bathing well length	44"
F	Bathing well width	28 7/8"
G	Sidewall length	53 7/8"
Н	Deck width (widest point)	5 1/4"
ı	Total height to raised headrest	22 1/4"
J	Height from bottom of bath to top deck	20 1/4"
К	Height from bottom of bath to bottom of deck	18 3/4"
L	Height from bottom of drain to center of overflow	15 3/4"
М	Maximum water level (Waste & overflow 16" x 35") Maximum water level with AromaFlow	14" 13 3/4"
N	Slope of backrests	21°

⚠ AromaCloud® position

Control position when factory-installed (Mia® or DOT)

Turbine position (TMU)

Indicates heated backrest (TMU)

Indicates WarmTouchShell® position (TUB)

TECHNICAL SPECIFICATIONS				
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000014	
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	135 lb	
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power	550 W	
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W	
Others	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated. It must be connected to the hot water supply and be accessible (provide access).</li> <li>Optional tile flange.</li> <li>The water level will be lower when an AromaFlow is installed.</li> </ul>	WARRANTY		
Others		Controls-LED-Geysair*	5 years	
Our products must be installed by certified professionals only and according to our Owner's Manual as well as federal,		Bath & turbine*	20 years	
provincial/state and local building codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).			tra.com/warranty	

## **VIBE** 6030

60" x 30" x 19"

Vibe is a collection of therapeutic bathtubs with minimalist and contemporary flair. The collection is perfect for urban city dwellers who want to bring value and refinement to smaller bathrooms.



	MODEL	тми	TUB
S	Drop-in standard 1 1/2" deck	BVIBRD00T-XX	BVIBRD00N-XX
S	Alcove – Left standard 1 1/2" deck	BVIBRB0LT-XX	BVIBRB0LN-XX
S	Alcove – Right Standard 1 1/2" deck	BVIBRBORT-XX	BVIBRBORN-XX
	Slim deck	BVIBRD10T-XX	BVIBRD10N-XX
	Slim deck – Left	BVIBRB1LT-XX	BVIBRB1LN-XX
	Slim deck – Right	BVIBRB1RT-XX	BVIBRB1RN-XX

THERMOMASSEUR (TMU) Hydro-thermo massage • Air jet system	\$4,895
Jets	40
1 heated backrest	Included
MiaPlus® Control	Included
BU-Touch Control Application BUTOUCH	\$430
Geysair®	Included
AromaFlow* BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925

<b>TUB</b> Soaker	\$2,435
AromaFlow* BAROMAF NEW	\$950
Illuzio Chromatherapy BCHRO6	\$925
WarmTouchShell® BWTS	\$1,125
DOT control	Included with therapy

FEATURES				
Installation type			Drop-in & Alcove (3 walls)	
No. of bathers	•	Imp. gallo	ns	36
US gallons	US gallons 44 Integrated		l tile flange	Included
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10				
White 01, Biscuit 02, Chrome 07, Brushed Nickel 09, Polished Nickel 10, Matte White with UltraVelour finish 32		Installe	d & Included	
STANDARD COLOR p.13				
			Included	
White 01 Biscuit 02				

OPTIONS (UPCHARGE APPLICABLE)	
FINISH p.6	
UltraVelour Matte Finish (white only) BVE1	\$650
UNIVERSAL ARMRESTS BGBGU-XX p.12	
White 01	\$750
SKIRT MULTIFIT (standard 11/2" deck only) BSMUL-XX p.243	
White 01, Biscuit 02	\$600
INTEGRATED WASTE & OVERFLOW BOVERINI-XX p.10	
Matte Black 19, Satin Brass 18	\$120
IF REQUIRED BY CONSTRUCTION CODE	
Brass waste & overflow kit BDRCOB	\$240
Brass waste kit BDRCB	\$60

Don't forget that an integrated tile flange is available at no extra cost.

You must specify drain position (right or left). With the control on the deck, a complete shower door cannot be installed. **Don't forget to specify the finish of the integrated waste & overflow.**Don't forget to specify the deck height (1/2" or 1 1/2").

\* When ordering an AromaFlow, an Integrated waste & overflow is mandatory (Included). Specify the finish of the waste.

#### TO ORDER


Complete the  ${\bf ORDER\ FORM\ }$  in the  ${\bf bainultra.com/interactive\text{-}price\text{-}list\ }$  or on bainultra.com/extranet or send your PO to orderdesk@bainultra.com






#### **VIBE** 6030

#### INSTALLATION Control should always be installed on the opposite side of the tile flange С -





	<del>``</del>
With tile flange	
Detail A O	$oxed{J}$

LETTER	DESCRIPTION	MEASURE
Α	Outside edge to center drain	10 7/8"
В	Outside edge to center of overflow	2 1/2"
С	Total length	60"
D	Total width	30"
E	Bathing well length	44"
F	Bathing well width	19 1/8"
G	Deck width 17/8	
Н	Deck width at drain end 2	
I	Height from bottom of bath to top deck 181	
J	Maximum water level 14.5/16" Maximum water level with AromaFlow 12.1/2"	
K	Slope of backrest	27°
L	Height from bottom of deck to top std deck	1 1/2"
М	Height from bottom of deck to top slim deck	
N	Tile flange height	
0	Height of bath from bottom of bath to top of tile flange	

- $\ensuremath{\bullet}$  Control position when factory-installed (Mia  $^{\ensuremath{\circ}}$  or DOT)
- Turbine position (TMU)
- Indicates heated backrest (TMU)
- Indicates WarmTouchShell® position (TUB)

TECHNICAL SP	ECIFICATIONS		
Hot water supply required	The hot water supply should be 70% or more of the bath's total water capacity.	Cutting template	# 90000078
supply required	Access to the pump must be at least 18" x 22". <b>Standard connection is 20 A. 120 V, 60 Hz</b> , dedicated	Approx. shipping weight	200 lb
Turbine	line with a Ground-Fault Circuit Interrupter (GFCI). For any additional option, a second line is	Turbine power	550 W
	needed 15 A. 120 V, 60 Hz, dedicated line with a GFCI. Air vent necessary: 2" x 4" minimum.	Air heater	600 W
	<ul> <li>The Geysair® is located on the same side as the heated backrest. It must NOT be relocated.</li> <li>It must be connected to the hot water supply and be accessible (provide access).</li> </ul>	WARRANTY	
Others	- Turbine must be remotely installed in certain conditions Integrated tile flange is included (specify right or left).	Controls-LED-Geysair*	5 years
	- The water level will be lower when an AromaFlow is installed.	Bath & turbine*	20 years
	be installed by certified professionals only and according to our Owner's Manual as well as federal, be installed by codes and regulations (www.bainultra.com/dealers/dealer-documentation-and-catalog).	* Some restrictions apply   www.bainult	ra.com/warranty

#### **VEDANA®**

21" x 80" x 9 1/2"

PRODUCT NO.	
MODEL	BVEDANA-XX


VEDANA®	\$11,200

THERAPIES	
Aromatherapy	Included
ThermoTherapy®	Included
Light Therapy®	Included
Chromatherapy	Included
Sound Therapy®	Included



FEATURES	
Installation type	Wall-mounted
Control	MiaPlus®
STANDARD COLOR p.13	
White 01 Biscuit 02	Included





#### **OUR 5 THERAPIES**

VEDANA COMBINES 5 THERAPIES FOR A COMPLETE RESTORATIVE RELAXATION SESSION. WHILE THE THERAPIES WORK TOGETHER, EACH ONE CAN ALSO BE ENJOYED INDIVIDUALLY.

#### **REAL DAILY BENEFITS**

Vedana® combines the best spa technologies and therapeutic techniques. That means luxury care equal to the world's best wellness establishments, at only a fraction of the cost.

With Vedana, that special care you deserve is yours to be savored every day.



.....



#### THERMOTHERAPY®

The system can reach and maintain 175°F (80°C), the temperature recommended for authentic dry-heat Thermotherapy.



#### LIGHT THERAPY®

With its precision Litebook® technology, Vedana® is the cutting edge in terms of light intensity, wavelength, and range.



#### **AROMATHERAPY**

The aromatherapy system operates with an essential-oil nebulizing diffuser, the most authentic and effective method available.



#### SOUND THERAPY®

The Vedana® sound system totally surrounds you, covering up any other audible frequencies, and offers an exquisite sound experience.

#### BLUETOOTH TECHNOLOGY

To accompany your experiences and sessions, you can download Vedana's music sound track directly from our website:


bainultra.com/Vedana



#### **CHROMATHERAPY**

Vedana® diffuses colors in precise wavelengths that maximize the benefits of your therapeutic care, in accordance with your needs at a given moment.







#### **AKAŜA®**



## COMFORT CUSHION

15 7/8" x 21 1/8" x 5/8"

COMFOR	T CUSHION BCUSHIONA	\$540
Grey 05	Black 06	


#### **FEATURES**

Made in Italy, this high quality ure thane cushion offers the best comfort possible and bonifies the Hydro-thermo <code>Massage®</code> experience benefits.

Its isolating properties will keep your body feeling warm all through the bath session.

It will adhere naturally to the bath. No magnets are used.

The Akas̃a Comfort Cushion is available for several BainUltra models (see table below).





#### TO ORDER

BAINULTRA BATH MODELS AV	AILABLE FOR AKAŠA COMFORT C	USHION	
Amma 7242 Narrow Base‡	Elegancia 6636 C10	Elegancia 7242 C10	Meridian 6032
Amma 7242 Freestanding <sup>‡</sup>	Elegancia 6636 C11	Elegancia 7242 C11	Meridian 6042
Amma 7242 Drop-in <sup>‡</sup>	Elegancia 6636 C13	Elegancia 7242 C13	Opalia 6839 Centered Ellipse
Bain de Ville 6030	Elegancia 6636 C14	Elegancia 7242 C14	Opalia 6839 Off-Centered Ellipse - Left
Bain de Ville 6632	Elegancia 6642 C10	Essencia 6838	Pro-Meridian 55
Balneo Sanos 6636‡	Elegancia 6642 C11	Esthesia 6638	Pro-Meridian 60
Balneo Sanos 7240 <sup>‡</sup>	Elegancia 6642 C13	Inua 6036*	Meridian Ellipse 7240‡
Balneo Cella 6636‡	Elegancia 6642 C14	Inua 6636*	Meridian 6030
Balneo Cella 7240‡	Elegancia 7236 C10	Inua 7240*	Meridian 6031 Uno
Balneo Naos 6636‡	Elegancia 7236 C11	Meridian 50	Meridian 6031 Duo
Balneo Naos 7240 <sup>‡</sup>	Elegancia 7236 C13	Meridian 55	Meridian Ellipse 6636‡
Charism 6434	Elegancia 7236 C14	Meridian 60	

<sup>&</sup>lt;sup>‡</sup> Flat Deck \* Comfort Cushion included



#### **ESSENTIAL CARE PRODUCT**



<sup>\*</sup> Essential oils not included with the AromaFlow.



#### **PILLOW**


9 7/8" x 5 7/8" x 1 5/8"

PILLOW BPILLOW

\$240

#### **FEATURES**

Finesse, smoothness and sturdiness come together to offer the bather more comfort and well-being. Wisely placed by bather to the desired position, the bath pillow supports the neck wonderfully to offer the upmost in comfort and a feeling of complete relaxation and increased benefits. Offered in dark grey.



## SKIRTS

#### **SKIRTS**





#### **MULTIFIT** (ADJUSTABLE & REMOVABLE)

FEATURES		
Skirt (with bat	) BSMUL-XX	\$600
Skirt (alone)	60" BSSMUL60- 66" BSSMUL66- 72" BSSMUL72-	XX \$670
Piece		1

Notes: Fits most rectangular models. (Check with BainUltra® customer service)
Skirt is designed to fit full length and height of TUB. (See Owner's Manual)

## from 60" to 72" (from 152.4 cm to 182.9 cm) from 17 <sup>3/4</sup>" to 20 <sup>1/4</sup>" (from 45.1 cm to 51.3 cm)


#### SJ-1

FEATURES		
Skirt (with bath	) BSJ1-XX	\$715
Skirt (alone)	60" BSSJ160-XX	
	66" BSSJ166-XX	\$785
	72" BSSJ172-XX	
Piece		1

Notes: Fits most rectangular models.

Skirt is designed to fit full length and height of TUB. (See Owner's Manual)

Universal skirt SJ1 is not avalable in UltraVelour finish.










#### SJ-3 SE

FEATURES	
Skirt (with bath) BSJ3SE-XX	\$1,310
Skirt (alone) BSSJ3SE-XX	\$1,385

**Notes:** For Thalassa Sensation only.

Skirt is designed to fit full length and height of TUB. (See Owner's Manual) Will ship in a separate box.
Universal skirt SJ3 is not avalable in UltraVelour finish.







#### **MONARCH QUARTZ SKIRTS**

Quartz skirts are available in the same colors as the Monarch deck. When ordering a Quartz skirt, it is essential to specify the model and color. Quartz skirts are optional.

MODEL	SKIRT 6018 60" X 18 7/8" BSM6018-XX	SKIRT 6618 66" X 18 5/8" BSM6618-XX	SKIRT 7220 72" X 20" BSM7220-XX
Grey Expo 21	\$1,195	\$1,315	\$1,500
Jet Black 23 Lagos Blue 24	\$1,315	\$1,380	\$1,620
Quasar Light 25	\$1,860	\$1,980	\$2,275
Piatra Grey 26 Bianco Drift 31 Woodlands 30	\$1,915	\$2,100	\$2,395
Statuario Maximus 29	\$2,700	\$2,940	\$3,350

Notes: Quartz skirts are offered for Monarch Collection only.





NO	TES











© LIBRA AURORA 6634

© EVANESCENCE 6634 WITH AROMAFLOW



956, chemin Olivier Lévis (Québec) G7A 2N1 Canada

bainultra.com

Printed in Canada. Copyright © January 2024 | Bains Ultra Inc. All rights reserved. 45200755